

Pilot Study on Quality Aspects of PV Power Plants in India

Conducted in the framework of the Indo-German cooperation project
“Strengthening Quality Infrastructure for the Solar Industry”

by PI Photovoltaik-Institut Berlin AG

on behalf of Physikalisch-Technische Bundesanstalt (PTB)

First published: September 2017



Executive Summary	5
1 Introduction	6
1.1 Background	6
1.2 Cooperation, Financing and Duration	7
2 About PI Berlin	7
3 Site Selection and Description of the Inspection Methodology	8
3.1 List of the Selected Sites.....	8
3.2 Representativeness of the Selected Plants in the Indian Market	9
3.3 Scope of the Analysis Applied to Each PV Plant	12
4 Technical Background	13
4.1 Potential Induced Degradation.....	13
4.2 Snail trails.....	13
4.3 Hot spots	14
4.4 Soldering failures during module manufacturing.....	14
4.5 Inactive cell string.....	15
4.6 Cell breakage and micro-cracks.....	15
4.7 Backsheet scratches	16
5 Results of the Analysis	17
5.1 Plant 1 - 200kW rooftop (Delhi).....	17
5.1.1 Contracts	17
5.1.2 PV Plant Design	17
5.1.3 Electromechanical Installation.....	18
5.1.4 Commissioning.....	26
5.1.5 System Performance.....	26
5.1.6 PV Module Quality	27
5.1.7 Operation and Maintenance	28
5.1.8 Summary of the Results.....	29
5.2 Plant 2 - 1,505 kWp rooftop (Uttar Pradesh).....	31
5.2.1 Contracts	31
5.2.2 PV Plant Design	32
5.2.3 Electromechanical Installation.....	32
5.2.4 Commissioning.....	36
5.2.5 System Performance.....	36
5.2.6 PV Module Quality	37
5.2.7 Operation and Maintenance	38
5.2.8 Summary of the Results.....	39
5.3 Plant 3 - 50MW ground mounted (Rajasthan)	42
5.3.1 Contracts	42
5.3.2 PV Plant Design	42

5.3.3	Electromechanical Installation.....	44
5.3.4	Commissioning.....	52
5.3.5	System Performance.....	52
5.3.6	PV Module Quality	53
5.3.7	Operation and Maintenance	56
5.3.8	Summary of the Results.....	59
5.4	Plant 4 - 100MW ground mounted (Rajasthan)	62
5.4.1	Contracts	62
5.4.2	PV Plant Design	62
5.4.3	Electromechanical Installation.....	63
5.4.4	Commissioning.....	69
5.4.5	System Performance.....	70
5.4.6	PV Module Quality	71
5.4.7	Operation and Maintenance	74
5.4.8	Summary of the Results.....	77
5.5	Plant 5 - 30 MW ground mounted (Madhya Pradesh)	80
5.5.1	Contracts	80
5.5.2	PV Plant Design	80
5.5.3	Electromechanical Installation.....	82
5.5.4	Commissioning.....	89
5.5.5	System Performance.....	90
5.5.6	PV Module Quality	90
5.5.7	Operation and Maintenance	94
5.5.8	Summary of the Results.....	95
5.6	Plant 6 - 10MW ground mounted (Karnataka)	98
5.6.1	Contracts	98
5.6.2	PV Plant Design	98
5.6.3	Electromechanical Installation.....	99
5.6.4	Commissioning.....	104
5.6.5	System Performance.....	104
5.6.6	PV Module Quality	105
5.6.7	Operation and Maintenance	108
5.6.8	Summary of the Results.....	110
6	Interpretation of the Results	113
6.1	Failure Matrix	113
6.2	Risk Analysis	117
7	Lessons Learned and Take-away Messages for the Future PV Deployment in India	126
8	Literature and References.....	128
9	Disclaimer	129

ANNEX I – Chronology of the Inspection Period	129
ANNEX II – Shortlist Criteria	130
ANNEX III – Extract of the TDD Checklist	131
ANNEX IV – Measurement Equipment Used On Site.....	134
ANNEX V – Normative References Used for the Study.....	136

List of abbreviations

AC	Alternating Current	LTA	Lender’s Technical Advisor
BOM	Bill of Materials	LV	Low Voltage
BOS	Balance of System	MPP	Maximum Power Point
CAPEX	Capital Expenditures	MPPT	Maximum Power Point Tracker
COD	Commercial Operation Date	MV	Middle Voltage
CUF	Capacity Utilisation Factor	MWp	Megawatt peak
DC	Direct Current	MNRE	Ministry of New and Renewable Energy
DIF	Diffuse Horizontal Irradiance [Wh/m ²]	OE	Owner’s Engineer
Discom	Distribution Company	OPEX	Operating Expense
EL	Electroluminescence	O&M	Operations and Maintenance
EOW	End of Warranty	PAC	Provisional Acceptance Commissioning
EPC	Engineering Procurement and Construction	PCU	Power Central Unit
FAC	Final Acceptance Commissioning	PID	Potential Induced Degradation
FC	Financial Close	POA	Plane of the Array
FT	Fixed Tilt	PPA	Power Purchase Agreement
GHI	Global horizontal irradiation [Wh/m ²]	PR	Performance Ratio
Isc	Short-circuit current	PV	Photovoltaic
IR	Infrared	SAT	Single Axis Tracking
IV	Irradiation / Voltage	SECI	Solar Energy Corporation of India
KVA	Kilo-Volt-Ampere	SPD	Solar Project Developer
LCOE	Levelised Cost of Energy	STC	Standard Test Conditions
LID	Light Induced Degradation	Voc	Open circuit voltage

Executive Summary

The present study shows the results of a pioneer analysis conducted by PI Photovoltaik-Institut Berlin AG (PI Berlin), on behalf of Physikalisch-Technische Bundesanstalt (PTB), of the status of operating grid connected solar photovoltaic plants installed across India in the recent years. Six representative plants were selected and inspected by PI Berlin between the 3rd and 14th July 2017 thanks to the support of the Solar Energy Corporation of India (SECI) and the Kreditanstalt für Wiederaufbau (KfW), in cooperation with the Ministry for New and Renewable Energy (MNRE) and the National Institute for Solar Energy of India (NISE). The shortlisted plants were selected considering Indian specific environmental stress factors present in different climates, representative module and mounting structure technologies used in Indian solar plants and statewise accumulated solar capacity. The selected plants were evaluated by PI Berlin using a Technical Due Diligence product (Q3) developed for operating assets that focuses on aspects such as contracting, installation quality, long term durability of the components, design assumptions, operation and maintenance, PV plant commissioning and system performance calculations. The purpose of this study is to document the status quo of the six plants in terms of safety, performance and commercial touching points, and to identify failures, risks and mitigation measures that help to increase the awareness of solar project developers (SPD) and financing institutions in regards to quality assurance of solar PV projects.

As previously mentioned the selected plants are located in some of the most PV-active states in India and the technologies used in these plants represent all dominant technologies used in the Indian market. However, due to the reduced sample covered in the framework of this study, the results and interpretations shown and illustrated in this document are only applicable to the inspected sites and are not representative for the entirety of the Indian solar PV market. It should be also borne in mind that the failures and risks identified during the inspection process are not specific to the Indian PV plants, but are present and detectable in other markets around the world.

The results and outcomes of the survey show that strict technical requirements in regards to accurate component selection considering Indian specific environmental stress factors, PV plant design orientated towards a minimization of the LCOE, failure free installation, commissioning aligned with the norms and standards and a comprehensive site and PV specific operation and maintenance program, should be part of tender requirements and should also be reflected in the EPC and O&M contracts along with the necessary performance warranties. Missing or poorly expressed warranties in the EPC and O&M contracts are a risk for the owner since the quality can't be properly assessed during the various project stages. Lax tender requirements should be avoided as they give comfort to module suppliers and installation companies as no legal framework is forcing them to provide evidence of long-term durable products and failure free installation works. PI Berlin detected three types of failures during the evaluation of the electro-mechanical status of the PV plants: (i) sporadic failures with impact on the performance, (ii) systemic failures with impact on the performance, and (iii) sporadic and/or systemic safety-related failures without primary impact on the system performance. In order to assess the influence of the performance-related failures on the overall energy output of the plant, a visual inspection of 100% of the system would be necessary combined with an in-depth analysis of the yield, system availability and other monitored data since COD. A proper evaluation is especially challenging in those plants where a monitoring system doesn't even exist.

A special focus should be put on the PV module as it is the most sensitive component of the PV system and its stability during the full operational lifecycle is strongly affected by the environmental factors and damages caused by improper module handling during transport, installation and maintenance. The lack of trained installers and operators, the use of nondurable and cheap system components, and the lack of supervision of owner's engineers (OE) and lender's technical advisors (LTA) representing the interests of SPD and financing institutions respectively, are some of the ingredients that increase significantly the investment risk of the project.

Competitive reverse auctions that push down bid prices to extremely low levels, is a scenario where cutting corners in regards to quality may become a common practice. The present study helps to counteract and prevent the negative effects of poor quality during the deployment of PV projects, by detecting risks and translating them into clear statements and recommendations that contribute to the sustainable achievement of the Jawaharlal Nehru Solar Missions' political goals, aiming at installing 100 GW of solar generating capacity by 2022.

1 Introduction

The present study is part of a PTB project whose aim is to improve the scope and increase the use of quality infrastructure (QI) services needed for assuring the quality and reliability of solar energy systems by taking into account international best practices.

More specifically, the following areas are targeted: (i) strengthening capacities of the Indian metrology system relevant for the solar sector; (ii) supporting conformity assessment bodies to use and set up quality assurance procedures for solar energy systems and components; (iii) informing standardization bodies and regulatory agencies on international requirements and good practices for quality assurance in the solar sector; and (iv) awareness raising and qualification of companies and public institutions with regards to quality aspects in the sector.

The main project partner is the Ministry of New and Renewable Energy (MNRE) as political partner and the National Institute of Solar Energy (NISE) as implementation partner. Further implementation partners include the National Physical Laboratory (NPL) for primary reference solar cell calibration plus a variety of well-established QI institutions in India.

1.1 Background

India has become a very competitive market with a strong cost pressure present in all stages and stakeholders of the value chain, especially EPCs [20]¹. Chinese module prices in India have fallen about 33% in the last 12 months with average selling prices coming to \$0.32/Wp in the first quarter of 2017 and 11% decrease from \$0.36/Wp in Q4 2016. The predictions forecast 11.2 GW of solar capacity connected by the end of 2017 [Mercom Capital Group], while the total capacity already in the bidding phase is currently at about 14 GW, and there are approximately 6.5 GW of tenders pending auction [20]. The following graphs show the accumulated solar capacity by states and the accumulated solar capacity in India since 2009:




Figure 1: State wise accumulated solar capacity in India [Source: Mercom Capital Group (Mar 2017)]

The present project supports the sustainable achievement of the Jawaharlal Nehru Solar Missions' political goals, aiming at installing 100 GW of solar generating capacity until 2022. A central precondition is the use

¹ "Quality in India: battling the stereotypes"; pv tech; September 2017; "...the revelation that India has the cheapest EPC services in the world is worth investigating."

of premium-quality and secure solar energy systems which are complying with international standards. This, in turn, makes it necessary for the national quality infrastructure to render internationally recognized and demand-oriented services which comprise metrology and standardization as well as conformity assessment, certification and accreditation. The envisaged activities to promote QI services increase the basis for assuring the quality and safety of solar collectors and solar-operated instruments. Ultimately, investment security is increased as well.

Competitive reverse auctions that push down bid prices to extremely low levels, is a scenario where cutting corners in regards to quality may become a common practice [20]². The present study contributes to counteract and prevent the negative effects of poor quality during the deployment of PV projects, by detecting failures and their associated risks, and suggesting solutions for a sustainable development of the solar industry in India.

1.2 Cooperation, Financing and Duration

Within the scope of German Development Cooperation the project is part of the program for the promotion of renewable energies and energy efficiency in India. Close cooperation is especially envisaged with the Indo-German Energy Program (IGEN) implemented by GIZ (Deutsche Gesellschaft für Internationale Zusammenarbeit). The project is financed by the Federal Ministry for Economic Cooperation and Development (BMZ) and will last from 2014 to 2018.

2 About PI Berlin

PI Photovoltaik-Institut Berlin AG (PI Berlin), with its internationally focused team of photovoltaic experts provides a wide spectrum of inspection, planning, consultation services throughout the value chain. With the knowledge acquired through years of field experience, laboratory testing and R+D, PI Berlin offers a full range of engineering services for photovoltaic plants, from the development and construction phase to operation and maintenance.

PI Berlin features two laboratories, since 2006 in Berlin (Germany), and the second one in Suzhou (China) since 2012. The Berlin testing laboratory is accredited as a Certified Body Testing Laboratory (CBTL) in the IECCEB scheme, and internationally acknowledged as a satellite laboratory for Intertek (UL 1703). Both laboratories are certified according to DIN / EN / ISO / IEC 17025. PI Berlin follows a strict culture of independence and impartiality, based on internationally recognized and proven scientific methods.

The activities at PI Berlin laboratory are mainly focused on testing according to IEC, development and implementation of new tests (mainly in tropical and desert climates), factory audits and production control; installation support and reception of test equipment, lab audits and training courses. Since 2010, this PI Berlin business unit has carried out 202 certification projects of PV modules from Asia, USA and Europe, and more than 50 factory audits in Germany, China and MENA.

The second business unit is the R+D department. The area is in charge of evaluating and certifying new technologies, and furthermore, providing experience on failure diagnosis and interpretation for PV cells and modules, both in laboratory and in the field. The R&D unit has more than 42 international publications since 2006 in various subjects, such as on site electroluminescence measurements, hot spots, Potential Induced Degradation (PID), soiling, cell encapsulation, module thermal behavior, module mechanical damage, shading, cell corrosion, abrasion tests, and reliability and durability of PV modules in the desert. The full list of the R&D department publications is given in Annex I. The members of this department are currently involved in 12 national and international projects, including the EU-funded Horizon 2020 project; IBB, ZIM, BMBF and PTJ projects funded by the German Federal Ministry for Economic Affairs and Energy (BMWi).

Regarding PI Berlin's contribution to the development of international standards, since 2014, PI Berlin has been the technical consultant responsible for the development of on-site quality infrastructure programs in collaboration with the German Physikalisch-Technische Bundesanstalt. Moreover, PTB belongs to the German Ministry of Energy, in charge for the implementation of quality standards in countries such as Tunisia, Senegal, Indonesia, India, Malaysia, the Philippines and Mexico. Alongside this endeavor, PI Berlin is directly involved in the development of standards for the photovoltaic industry, such as IEC60904-12 TS Ed.1 and IEC60904-13 TS Ed.1 regarding infrared measurements in plant, or IEC TS 62804-1: 2015 about prevention

² In the recently concluded 750 MW Rewa Solar Park auction in Madhya Pradesh, bids reached a new record low of INR 3.30/kWh (\$0.0494) – LCOE over 25 years [20]

of Potential Induced Degradation (PID).

In addition, PI Berlin is also a member of the international PV Quality Assurance Task Force (PV-Qat). The objective of this association, is the development of regulations in specific fields such as the influence of humidity, temperature and voltage on PV modules, functionality and durability of bypass diodes, and field study of the effects of dirt and dust in arid climates.

3 Site Selection and Description of the Inspection Methodology

PI Berlin has conducted on behalf of Physikalisch-Technische Bundesanstalt (PTB), a pioneer study on 6 representative PV plants spread around India. The purpose was to document the status quo of these plants in terms of safety and functionality, by identifying potential failures and their associated risks. The status of these plants helped reflecting the actual situation of the operating solar assets in India, considering various factors such as the impact of harsh environmental conditions, the uncertainty associated to the long term durability of the selected components and the installation quality on the DC and AC side, among others. After evaluating the 6 PV plants and identifying the failures and risks, the outcomes were wrapped up into conclusive statements containing mitigation actions, recommendations and risk prevention measures for developers, system integrators and financing institutions.

3.1 List of the Selected Sites

According to the prerequisites specified in Annex II, a shortlist of suitable PV plants was created by PI Berlin. These prerequisites focused mainly on logistic aspects and available documentation needed to perform the present study. The final list of selected plants was created based on the following criteria:

- At least one plant should have c-Si PV modules
- At least one plant should have thin film PV modules
- At least one plant should have fixed tilt mounting structures
- At least one plant should have single axis tracking systems
- At least one plant should be located on a roof top
- Different climates should be considered (desert, tropical, steppe.)
- States with significant growing PV potential in the next years will be favored

The PV plants inspected by PI Berlin are listed hereunder:

Plant 1 - 200kW rooftop PV plant (Delhi)




Figure 2: 200kW located in Delhi
[Source: Google Earth]

Plant 2 - 1,505 kWp rooftop PV (Uttar Pradesh)



Figure 3: 1,505 kWp located in Uttar Pradesh
[Source: Google Earth]

Plant 3 - 50MW ground mounted PV plant (Rajasthan)




Figure 4: 100MW located in Rajasthan
[Source: Google Earth]

Plant 4 - 100 MW ground mounted PV plant (Rajasthan)



Figure 5: 100 MW located in Rajasthan
[Source: Google Earth]

Plant 5 - 30 MW ground mounted PV plant (Madhya Pradesh)



Figure 6: 30 MW located in Madhya Pradesh
[Source: Google Earth]

Plant 6 - 10MW ground mounted PV plant (Karnataka)



Figure 7: 10MW located in Karnataka
[Source: Google Earth]

3.2 Representativeness of the Selected Plants in the Indian Market

The 6 selected sites are located in 5 states where currently 40% of the total solar capacity in India is installed. The module and racking types used in these plants represent all dominant technologies used in India such as (i) crystalline and thin film technology for the PV modules, and (ii) fixed tilt ground mounted, fixed tilt roof top, seasonal horizontal tracking and full horizontal tracking for the anchorage of the PV modules.




Figure 8: Overview of the visited sites by PI Berlin

The 6 selected plants are located in the 4 main climate zones of India according to the Köppen-Geiger classification [21], which are:

Plant 1 and Plant 5 (BSh-Arid/Steppe/Hot)

The prevailing climate here is known as a local steppe climate. During the year, there is little rainfall and the temperature here averages 25.2 °C. The average annual rainfall is 693 mm and the driest month is April. There is 3 mm of precipitation in April and most precipitation falls in August, with an average of 246 mm. With an average of 34.3 °C, June is the warmest month and January the coldest with an average temperature of 14.2 °C. The precipitation varies 243 mm between the driest month and the wettest month. The average temperatures vary during the year by 20.1 °C [source: climate-data.org]. The Global Horizontal Irradiation (GHI) in Plant 1 and Plant 5 is approximately 1,700 kWh/m² and 1,870 kWh/m² per year respectively [source: SolarGIS].

Plant 2 (Csa-Temperate/Dry summer/Hot summer)

The climate here is mild, and generally warm and temperate. The rain falls mostly in the winter, with relatively little rain in the summer. The average annual temperature is 26.1 °C and the rainfall here averages 998 mm. At an average temperature of 34.3 °C, May is the hottest month of the year and January the coldest with an average temperature of 16.5 °C. Between the driest and wettest months, the difference in precipitation is 296 mm. The variation in annual temperature is around 17.8 °C [source: climate-data.org]. The Global Horizontal Irradiation (GHI) is approximately 1,750 kWh/m² per year [source: SolarGIS].

Plant 3 and Plant 4 (BWh-Arid/Desert/Hot)

Here the climate is a desert one. During the year, there is virtually no rainfall. The average temperature is 26.6 °C and the average annual rainfall is 363 mm. Precipitation is the lowest in April, with an average of 2 mm. Most of the precipitation here falls in August, averaging 125 mm. At an average temperature of 34.4 °C, May is the hottest month of the year and January the coldest with temperatures averaging 16.9 °C. Between the driest and wettest months, the difference in precipitation is 123 mm. Throughout the year, temperatures vary by 17.5 °C [source: climate-data.org]. The Global Horizontal Irradiation (GHI) is approximately 1,980 kWh/m² per year [source: SolarGIS]. The presence of dust and sand, as well as strong winds and salinity are additional environmental factors that need to be taken into account.

Plant 6 (Aw-Tropical/Savanna/Wet)

The climate here is tropical. The summers are much rainier than the winters and the temperature here averages 23.6 °C. In a year, the average rainfall is 831 mm. The driest month is January, with 1 mm of rain. The greatest amount of precipitation occurs in September with an average of 182 mm. April is the warmest month of the year averaging 27.1 °C. The lowest average temperatures in the year occurs in December with 20.7 °C. There is a difference of 181 mm of precipitation between the driest and wettest months. The variation in temperatures throughout the year is 6.4 °C [source: climate-data.org]. The Global Horizontal Irradiation (GHI) is approximately 1,900 kWh/m² per year [source: SolarGIS].




Figure 9: (left) Climate classification of India according to Köppen-Geiger; (right) GHI map of India

The climatic and the environmental description of the selected locations, shows that the most relevant PV specific stress factors such as humidity, salinity, sand and dust, abrasion, temperature cycling, high UV loads and strong wind are present in one or several of the selected site. The high levels of humidity during all or part of the year and the relatively high UV loads especially in the desert area, are environmental characteristics common to the 6 sites³.

Even though (i) the selected sites are located in 5 of the most PV-active states in India, (ii) the climatic and environmental characteristics of the selected sites cover most of the Indian country, and (iii) the module and mounting structure technologies used in the selected projects represent the dominant technologies in the PV industry, the results and interpretations shown and illustrated in this document are only applicable to the inspected sites and are not representative for the entirety of the Indian solar PV market, due to the reduced sample covered in the present study.

³ The Köppen-Geiger classification was originally developed for agriculture and plant growth in different regions. There is no correlation between the PV specific environmental stress factors and the KG classification. The KG map is used merely for displaying the various climatic zones in India. As more PV systems are operating in diverse climatic zones, stronger correlations between KG climatic zones and failure modes will be developed [22].

3.3 Scope of the Analysis Applied to Each PV Plant

PI Berlin offers 3 TDD products across the value chain of a PV project. The Q1 product is created for PV projects that are still in the development phase prior to Financial Close (FC). The Q2 product is used after construction and commissioning prior to take over and Provisional Acceptance Commissioning. Finally, the Q3 product is applied for operating assets during refinancing or acquisition processes. PI Berlin has applied a reduced version of the Q3 to the 6 selected project since all of them are in the operational phase.




Figure 10: TDD products offered by PI Berlin

The Q3 is divided in 7 evaluation topics as shown in the following scheme.



Figure 11: Scope of the Q3 product

In the first topic **Contracts and Warranties**, the legal and commercial scenario of the PV project is evaluated from a technical perspective. EPC and O&M contracts along with the performance warranties are analyzed. The suitability of the selected products for a specific location together with the technical design are evaluated in the second topic, **PV Plant Design**. The quality of the **Electromechanical Installation** of the PV plant is the third topic and is assessed onsite. The fourth topic **Commissioning** evaluates the tests conducted after the construction phase and the generated protocols during the Provisional Acceptance Commissioning (PAC). The fifth topic **System Performance** evaluates the yield prognose conducted prior to FC, as well as the accuracy of the installed weather station and the onsite PR calculation. The topic **PV Module Quality** assesses the status of the PV modules onsite by conducting a visual inspection and measurements using special hardware. Finally, the last topic **Operation and Maintenance** evaluates the preventive and corrective measures carried out by the O&M team, the system availability calculation, the SCADA system, the reporting and the module cleaning among other activities. The Q3 will be applied separately to each of the 6 plant using the checklist specified in Annex III.

4 Technical Background

The following chapters serve as a guide for the better understanding of some of the module failures mentioned in the present study.

4.1 Potential Induced Degradation

The phenomenon of Potential-Induced Degradation (PID) is based on a power loss degradation caused by a negative potential of the solar cells towards earth, which leads to an accumulation of Na^+ located in the glass and migrating into the solar cells damaging the p-n junction responsible for the electron flow. The degree of affection is highly dependent on the level of the potential (high voltage stress) relative humidity and temperature. The first bibliographic references relate to the investigations carried out by Hoffman and Ross (JPL) in 1978 (Impact of voltage-biased humidity exposure of solar modules on long-term stability) in which this physical effect was internationally presented for the first time. The PID effect was associated in the past principally to back contact cell technology, TCO corrosion in thin film modules and processes based upon band silicon. In recent years, the PID effect has also been linked to silicon technology; thus, this phenomenon has become more and more relevant due to the enormous amount of solar facilities built with this technology.




Figure 12: (left) pn-junction damage (left); (right) typical PID pattern [source: PI Berlin]

The necessary conditions for the appearance of PID in the field can be summarized as follows:

- High system voltage (has increased in the last years in order to minimize transport losses in the string)
- High relative humidity
- High temperature
- Certain combination of materials (glass, encapsulate material, etc.)

The degree of PID of the PV modules decreases towards the positive pole, with the first modules of the negative pole being usually the most affected with power drops up to 95% in cases of advanced PID.

4.2 Snail trails

It is defined as a grey/black discoloration of the silver paste of the front metallization of screen-printed solar cells. In the PV module the effect looks like a snail trail on the front glass of the module and is visible for the human eye. The discoloration occurs along invisible cell cracks. The discoloration typically occurs 3 months to 1 year after installation of the PV modules. The initial rate of discoloration depends on the season and the environmental conditions. During the summer and in hot climates snail trails occur faster [12]. The origin of the discoloration of the silver paste is not clear. However, the area of the snail trail discoloration along the silver finger of the front side cell metallization shows nanometer-sized silver particles in the EVA above the silver finger. These silver particles cause the discoloration [12]. The snail trails appear typically as branched trails across the cells and are a clear sign of hidden cell damages.



Figure 13: PV module showing snail trails [source: PI Berlin]

4.3 Hot spots

A hot spot is defined as a localized region in a PV module whose operating temperature is very high in comparison with its surroundings. This can occur when a cell generates less current than the rest of cells connected in series as a result of partial shading, cell damage, mismatching or interconnection failure. As a result, the defective cell is reverse biased and behaves like a load that dissipates the power generated by the rest of cells in the form of heat [13]. The protection against hot spots is also well-known and consists of connecting a bypass diode, with reverse polarity, in parallel with a group of cells, typically 12 or 18 for crystalline silicon modules. Thus, the defective cell is reverse biased to a point that causes the forward conduction of the bypass diode, which almost short circuits the group of cells and ensures that, in the worst case, the aforementioned cell dissipates nearly the power generated by the remaining cells in the group. Hot spots present a potential risk of irreversible damage for PV modules. They can cause, for example, tedlar delamination, glass breakage, loss of electrical insulation or even fire [13].




Figure 14: PV Module affected by a hot spot [source: PI Berlin]

4.4 Soldering failures during module manufacturing

The soldering of the ribbon to the cell busbar is a key process in PV module manufacturing. Soldering may easily provoke perpetual cell damages if not conducted properly. Already slight process issues may create tiny damages that can get worse during field operation of the module. Ultimately, bad soldering quality can lead to a detachment of the ribbon and a consequent reduction of the current flow. The inhomogeneous current guidance leads to a chromatic mismatch in the electroluminescence pictures. One defect busbar forces the other busbars to handle higher currents which might lead to an earlier failure of those busbars as well. A second effect that may occur during an insufficient supervised soldering process is the creation of micro-cracks and associated cell short circuits (shunts) due to improper settings such as soldering temperature or duration. These shunts appear as hot spots in the infrared images and as bright dots in the electroluminescence pictures.




Figure 15: (left) Inhomogeneous current guidance in a cell affected by inaccurate soldering [source: PI Berlin]
 Figure 16: (middle and right) Shunts in a cell affected by inaccurate soldering [source: PI Berlin]

4.5 Inactive cell string

In parallel to a certain number of solar cells, bypass diodes are integrated into the PV module. These bypass diodes reduce the power loss caused by partial shading on the PV module. Besides the power loss, the diode avoids the reverse biasing of single solar cells higher than the allowed cell reverse bias voltage of the solar cells. If a cell is reversed with a higher voltage than it is designed for, the cell may create hot spots that may cause browning, burn marks or, in the worst case, fire. Typically, Schottky diodes are used as bypass diodes in PV modules. Schottky diodes are very susceptible to static high voltage discharges and mechanical stress. So they should be handled with care and human contact without grounding should be avoided [12]. Consequently, many bypass diode failures may occur. But it is difficult to find them because they only attract attention when the PV modules have severe mismatch in the individual I - V characteristic of single cells, e.g. caused by shading or disconnected parts of a cell due to cell cracks [12].




Figure 17: PV Module with an inactive cell string [source: PI Berlin]

4.6 Cell breakage and micro-cracks

Photovoltaic cells are made of silicon. This makes photovoltaic cells very fragile. Cell cracks are cracks in the silicon substrate of the photovoltaic cells that often cannot be seen by the naked eye. Cell cracks can form in different lengths and orientations in a solar cell. The wafer slicing, cell production, stringing, the embedding process during the production of the solar cell and module, transport, handling and installation are all sources of cell cracks in the photovoltaic cells [12]. The cracks and microcracks can be detected easily with electroluminescence technique as shown in the picture below.




Figure 18: PV Module showing cracks and micro-cracks [source: PI Berlin]

The associated power losses to the aforementioned phenomenon will depend on the size and depth of the crack, while the crack propagation is purely influenced by the site conditions (for instance wind, temperature or snow).

4.7 Backsheet scratches

Backsheet scratches generally occur during transport and handling of the PV modules. They are caused typically when construction tools fall on the back side of the modules, when stacking the modules on top of each other or during the module fixing to the mounting structure. A damage of the module backsheet has primarily safety consequences rather than performance related issues. The safety impact is caused by a decrease of the module insulation values (and thus, of the whole string and electrical circuit) and a loss of the protection class II as well as the IP degree.



Figure 19: PV Module showing backsheet scratches [source: PI Berlin]

5 Results of the Analysis

The following chapters will summarize the main outcomes of the investigations carried out in the selected plants and will serve as a basis for the risk analysis conducted in chapter 6.2.

5.1 Plant 1 - 200kW rooftop (Delhi)

Date of inspection by PI Berlin	03.07.2017
Name and size of the plant	confidential, 200kW (roof top)
Coordinates	confidential
Commercial Operation Date (COD)	confidential
Name of the Owner	confidential
Name of the EPC	confidential
Name of the O&M company	confidential
<p>The 200kWp PV plant is split in several roofs. 2 PV modules are arranged in portrait and tilted at 26° building strings of 20 modules in series. Between 4 and 6 strings are connected in parallel to 20kW or 30kW string inverters. The inverters are connected with 4R: 1Cx16mm² or 4R: 1Cx10mm² XLPE Cu cables protected with 63A breakers to IP65 AC combiner boxes. The lines 1R 3.5Cx50mm² XLPE Al are protected with 200A and are collected by one aluminium bar that leads to the meter. The level of injection is 400V. A PPA between the building owner and the PV plant owner was signed for 25 years.</p>	

5.1.1 Contracts

Under this chapter PI Berlin has put the main focus on:

- EPC contract
- O&M contract
- Role of the Owner's Engineer
- Role of the Lender's Technical Advisor supporting the financing institution

The evaluation of the above mentioned points leads to the following outcomes:

- A typical EPC contract wasn't created since the Owner and EPC are the same entity. Hence, no standard EPC warranties expressed as Provisional Acceptance Commissioning (PAC) or Final Acceptance Commissioning (FAC) certificates exist.
- A typical O&M contract wasn't created since the Owner and Operator are the same entity. Hence, no standard O&M warranties based on Performance Ratio or system availability were formulated. The only warranty in place is an internal requirement forcing the plant to reach a CUF of 15% on yearly basis.
- There is no EPC contract, hence no binding Provisional Acceptance Commissioning (PAC) tests have been conducted.
- No Owner's Engineer was appointed.
- No Lender's Technical Advisor was appointed since the plant was financed by the Owner. At the time of the visit, the Owner was looking for refinancing options.

5.1.2 PV Plant Design

This chapter analyses:

- Interrow shading based on the selected pitch and tilt
- Statics
- Location of inverters and combiner boxes in regards to voltage drop minimization

Interrow shading based on the selected pitch and tilt

The pitch is 5.8m (lower edge-lower edge) according to the design and PV SYST simulation provided by the Owner. PI Berlin has measured values between 5.3m and 6,53m at some locations of the PV plant. A difference of the pitch between 5.3m and 6.53m at 26° can lead to variations of the mutual shading losses of 1%. The tilt of the modules according to the design is 26° south. PI Berlin has measured values between 24° and 27° at some locations of the PV plant. Combining the pitch and tilt variations and comparing the worst case (5.8m/27°) and the best case (6.53m/24°) the interrow shading losses can vary up to 1.8% according to the PV SYST simulations conducted by PI Berlin.



Figure 20: Tilt measurement device

Statics

The statics of the mounting structure in combination with the structural integrity of the roof and the applicable wind loads have been calculated comprehensively.⁴

Location of inverters and combiner boxes

The inverters and distribution boxes are located considering cable and voltage drop reduction criteria. The cable runs are kept short avoiding an unnecessary voltage mismatch at inverter level. This statement bases both on the onsite inspection as well as on the review of the as-built layouts provided by the Owner.⁵

5.1.3 Electromechanical Installation

The quality of the electromechanical installation was assessed onsite by PI Berlin evaluating the following subsystems:

- Mounting structure
- Combiner boxes
- DC Cables
- Inverter
- Grounding and equipotential bonding
- Civil work
- Documentation

Mounting structure and module fixation

- i. **Module fixation:** The module clamps used for fixing the modules do not seem to be manufactured for PV applications. In some cases the clamps do not ensure a proper fixation and even lead to hotspot effects by shading partially the solar cells next to them.

⁴ PI Berlin has reviewed the project report "XXXX_Complete Document.pdf" sent by the Owner on the 3rd July 2017.

⁵ PI Berlin has reviewed the drawings JEL-S042-DRG-GE-01, JEL-S042-DRG-EE-02, JEL-S042-DRG-EE-03 included in the project report "XXXX_Complete Document.pdf" sent by the Owner on the 3rd July 2017




Figure 21: Improper module fixing and associated hot spots due to microshading effects

- ii. Labelling of rows: No labelling of module rows could be observed.



Figure 22: Missing labelling of the module rows

- iii. Rust on the mounting structure surface: Rust is present in many parts of the mounting structure after 18 months of outdoor exposure. Some areas of the plant show advanced levels of rust. No aluminium has been used, all parts are made of steel.





Figure 23: Presence of rust in the mounting structure

Combiner boxes

- i. Sealing of the cable glands: The cable glands are properly sealed both in the DC and AC combiner boxes.



Figure 24: Cable glands of the combiner box

- ii. Cleanliness of the CB: The DC combiner boxes have a significant amount of dust and dirt inside. Signs of rust could also be detected. The AC combiner boxes couldn't be opened.




Figure 25: Presence of dust inside the combiner box

- iii. Overvoltage in the CB: An overvoltage protection is present in the DC combiner boxes.




Figure 26: View of the combiner box hardware

- iv. Labelling of the CB: A durable and clearly visible labelling of the DC combiner boxes is missing. The AC combiner boxes are labelled.



Figure 27: (left) Missing labelling of the DC combiner box; (right) Labelled AC combiner boxes

Cable fixation and routing

- i. Cable damage: Some cables show mechanical damages caused by monkey bites. Additionally, some cables are in contact with sharp edges of the mounting structure components leading to abrasion of the cable shield.





Figure 28: String cables damaged by monkey bites



Figure 29: (left) Monkeys present on site; (right) String cables in contact with sharp edges

- ii. Labelling of cables: Each module string is labelled. The positive and negative poles are also labelled. In both cases the used tags do not seem to be durable for the whole lifetime of the project.



Figure 30: Non-durable string cable labelling

- iii. Connectors: The connectors are in general in a good shape. Some of them were not properly closed and screwed.



Figure 31: PV module connectors not properly closed

- iv. Cable fixation: The cables ties used for the cable fixation are not suitable for outdoor exposure and start falling apart.



Figure 32: String cables not properly fixed due to degraded cable ties

- v. Bending radius: In general, the minimum bending radius has been respected. In some sporadic cases the manufacturer's requirements are not fulfilled.



Figure 33: Low bending radius in the string cables

- vi. Sealing of tubes: The tubes are not sealed.



Figure 34: Non sealed cable tubes

- vii. Cable pipes: The tubes where the cables are routed show degradation due to outdoor exposure. That leads to a lack of UV protection of the cables in some areas of the plant.




Figure 35: Degraded cable pipes

Inverter

The inverters have an overvoltage protection both on the DC and AC side as well as a DC switch. The cooling of the inverter is ensured with active fans and the inverter filters are clean. The housing is grounded and the IP 65 is ensured. The inverters could not be opened due to warranty aspects, hence no information about the cleanliness of the inverter inside can be provided. The cable size of the RS 485 communication cable exceeds the maximum size of the gland diameter. This has led to an improvised solution where the shield had to be removed letting the interface between cable and gland unprotected. All inverters are protected from the sun.



Figure 36: (left) String inverter; (right) Unprotected interface between communication cables and inverter housing

Grounding and equipotential bonding

The equipotential bonding system connects all conductive parts of the PV plant as the mounting structure, module frames or housings. The equipotential bonding system is integrated in the equipotential bonding system of the building. The equipotential bonding belt shows signs of corrosion. In terms of Potential Induced Degradation (PID) avoidance, no measures have been taken, such as functional grounding of the negative pole. However, the presence of PID could not be detected.



Figure 37: (Top) Equipotential bonding system installed onsite; (bottom) Rust in the equipotential bonding system

Civil work

The access to the roof as well as to the PV plant components is ensured. The foundation of the mounting structure is robust and the statics are compatible with the roof integrity. No damage on the roof has been observed. No drainage system has been installed on the roof, however, no water accumulation has been detected.

Documentation

In terms of completeness, the provided documents do not comply with all the requirements of the IEC 62446. Some aspects are missing, such as the commissioning protocols, the string layout or the O&M activities. During the 2 months of installation where 11 workers were involved, no progress reports were issued.

5.1.4 Commissioning

PI Berlin considers the commissioning process conducted at the end of the installation phase a crucial milestone in the deployment of a PV project. The commissioning process as per IEC 62446 is divided in “cold” and “hot” commissioning⁶, and ends with the issuance of the Provisional Acceptance Certificate, and is the last step before the EPC warranty starts. This process gives an idea of the status of the plant in terms of safety and functionality. Due to the fact that no EPC contract has been issued since the Owner and EPC are the same entity, there are no warranties to be provided by the latter either. That leads to no existing commissioning tests as per the IEC 62446.

5.1.5 System Performance

In this chapter PI Berlin analyses several factors that influence the calculation of the system performance.

Weather station status and sensor accuracy

The weather station is constituted by a c-Si sensor which is measuring the irradiation on the tilted plane and the ambient temperature. A Pt sensor adhered to the backsheet of the modules for measuring the module temperature is missing. The global horizontal irradiation (GHI) is not measured. The cables connecting the sensor to the communication box are not protected and properly fixed. PI Berlin quantified an offset of 54W/m² at 4.34PM at the plane of the array (POA). The onsite sensor was reading lower values. Possible reasons for that can be dirt on the sensor surface, a communication problem with the SCADA system or a shading on the irradiation sensor. According to the Operator, the last calibration of the irradiation sensor was conducted on the 13th December 2016. According to the Owner a calibration is conducted once a year.



Figure 38: (left) Not protected communication cable; (right) Irradiation sensor installed onsite

Performance Ratio calculation

The PR is calculated as a ratio of the accumulated POI in kWh/m² and the metered production in kWh. No temperature correction of the PR is conducted. According to the Owner, the PR varies between 78% and 83% depending on the season. PI Berlin did not have access to the daily and monthly PR values since COD. The losses due to soiling are not measured in order to calculate the real PR of the plant. The yield assessment conducted by the Owner with the simulation program PV SYST on the 12th January 2016 represents the state of the art.⁷

⁶ „cold“ stands for all tests performed before grid connection, while „hot“ stands for the tests conducted after grid connection.

⁷PI Berlin has reviewed the file “PVSyst_200kWp_XXXX.pdf” sent by the Owner on the 3rd July 2017

5.1.6 PV Module Quality

The PV modules represent the most sensitive part of the PV plant, especially in harsh climates with high UV loads, high temperatures and high humidity rates. These environmental stressing factors are present in Plant 1 whose climate is classified as BSh according to Köppen-Geiger [21]. In order to assess the quality of the modules, PI Berlin has conducted a visual inspection and an infrared analysis using the equipment specified in Annex IV. The investigated aspects are listed as follows:

Results of the visual inspection

The visual inspection on the modules did not show major defects affecting the quality of the BOM, the system performance or the safety of persons, animals and goods. No scratches of the backsheet were detected. No snail trails were detected on site.




Figure 39: PV modules installed onsite

Long term durability certificates

No specific Q certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors mentioned above.

Infrared analysis

The infrared inspection did not show major defects apart from a few hot spots.






Figure 40: Modules affected by hot spots

5.1.7 Operation and Maintenance

The quality of the Operation and Maintenance service has been evaluated considering the points listed below. PI Berlin had the chance to interview a few members of the O&M team while conducting the site visit.

Experience of the O&M team

According to the Owner, at the time of the installation of the PV plant, the workers had an accumulated experience between 0 and 2 years. The Owner and Operator of the plant is currently operating 100 roof top plants across India.

Cleaning methodology and calculation of the soiling loss

A bias of 10% production difference between a clean inverter unit (benchmark) and the rest of units is set as a maximum acceptable value before starting a module cleaning campaign. The bias is monitored over the SCADA system. PI Berlin considers the bias of 10% as too high. The PV plant is cleaned 3 times a year in order not to exceed the 10% production difference. The module cleaning is performed using cotton wipers and tap water. The impact of the selected cleaning methodology on the module warranty hasn't been analysed by the Owner and Operator.

Tools used on site

The plant Operator uses the following devices: IV curve tracer, IR camera, thermometer and current clamp. PI Berlin considers this set as sufficient.

Reporting and reaction times

According to the Operator a report is issued monthly. PI Berlin did not have access to the same. According to the Operator, the reaction time is kept below 24h for all failures. PI Berlin could not prove this statement.

Preventive and corrective maintenance

PI Berlin did not have access to the preventive and corrective maintenance checklists.

Availability calculation and SCADA monitoring

The system availability is not monitored. According to the Operator, the grid availability is above 99%. The regular check of the PV plant via the SCADA system is performed by the Operator. PI Berlin could not check if the SCADA system visualizes each module string which is highly recommended.

Curtailement and grid stability

According to the plant Operator the curtailment losses originated by the Discom are not significant due to the high grid availability in the area. According to the plant Operator the PV plant is not forced to support actively the grid due to its reduced size.

5.1.8 Summary of the Results

The following table summarizes the failures detected onsite and the associated risks.

Table 1: Summary of the failures and the associated risks – Plant 1

Ref.	Item	Risk Description
1	Contracts	
1.1	No appointment of an Owner's Engineer	The OE has the task to support the Owner's interests against the EPC and the various product suppliers. The OE conducts independent checks and verifications starting at the earlier phases of the EPC tendering and ending after commissioning or beyond. The absence of an experienced OE as an independent party, may lead to an increased risk for the Owner. In this case, the Owner and EPC are the same entity, so no OE was requested from any of the parties. The quality assurance services provided by an OE are highly recommended in order to avoid mistakes in all stages of the value chain.
1.2	No appointment of a Lender's Technical Advisor	Similarly to the OE, the LTA supports the interests of the bank as the financing institution. Accordingly, the bank is interested in financing projects which are bankable and are exposed to low risks. Thus, the task of the LTA is to ensure the bankability of the project by supervising that all steps made by the Developer (very often also the Owner at the same time) lead to a low risk scenario. In this project the Owner financed the project, so the services of an LTA were not contracted. Strictly seen, the role of the LTA and OE could have been unified under the same entity. One way or the other, no independent advisory has been conducted in this project.
1.3	Not existing EPC contract.	A typical EPC contract wasn't created since the Owner and EPC are the same entity. Hence, no standard EPC warranties expressed as Provisional Acceptance Commissioning (PAC) or Final Acceptance Commissioning (FAC) certificates exist. Only the product warranties prevail. The lack of an EPC contract is typical in scenarios where the Owner and EPC are the same company since all services are placed under the same roof. The EPC warranties have the goal to put pressure on the EPC in order to ensure that the plant meets certain quality criteria which ensure that the plant will last longer than the EPC warranty period (usually 24 months). According to the present scenario, no EPC warranties exist, so no specific tests were conducted that would help assessing the quality of the plant in terms of functionality, safety and performance.
1.4	Not existing O&M contract.	A typical O&M contract wasn't created since the Owner and Operator are the same entity. Hence, no standard O&M warranties based on Performance Ratio or system availability were formulated. The only warranty in place is an internal requirement forcing the plant to reach a CUF of 15%. The lack of O&M warranties leads to a comfortable scenario where the O&M team has no special incentive to force the PV plant to run at its maximum potential. The consequences are usually a lower availability and a lower output than expected.
2	PV Plant Design	
2.1	Not consistent interrow shading simulation.	The PV plant shows variations of the pitch and tilt in different areas which leads to a variation of the interrow shading losses up to 1.8% between the worst and the best case according to the PV SYST simulations conducted by PI Berlin. The design and simulation of the plant has been conducted by the EPC with a fixed tilt and pitch which does not fully reflect the as-built situation. This uncertainty may affect directly the P90 and financial model of the project.
3	Electromechanical Installation	
3.1	Mounting structure	
3.1.1	Poor module fixation	The module clamps are unsuitable for PV applications and do not ensure the proper fixation of the modules to the mounting structure. In case of strong wind, the modules might suffer severe damages. Apart from this, the micro-shadings caused by the clamps have an influence on the module performance.
3.1.2	No row labelling	The missing row labelling makes the correct identification of the various areas of the plant more difficult leading to increased reaction times during corrective maintenance.
3.1.3	Rust on the mounting structure components	The rust can lead to a reduction of the structural strength of the mounting structure, especially in combination with strong wind.
3.2	Combiner boxes	
3.2.1	Dust and dirt inside the housing	The presence of dust and dirt inside the combiner boxes can lead to the development of micro-organisms and possible corrosion and chemical reactions that damage the electrical components inside the housing. Additionally, the dust tends to grip the electrical protections such as fuse holders and breakers limiting their functionality.
3.2.2	No labelling of the boxes.	The missing combiner box labelling makes the correct identification of the various areas of the plant more difficult leading to increased reaction times during corrective maintenance. Additionally, electrical parts that aren't properly labelled may hide safety risks when manipulated by O&M members.
3.3	Cables	

3.3.1	Mechanical damage visible	The cables damaged by monkey bites represent a severe safety issue since the minimum required insulation values of the electrical circuit are lost. Additionally, the contact of the cables with the sharp edges of the mounting structure may also cause damages in the shield of the cables leading to the same problem described previously.
3.3.2	Poor or not existing labelling of the DC cables	A non-durable or non-existing cable labelling makes the correct identification of the various electrical circuits more difficult leading to increased reaction times during corrective maintenance. Additionally, the confusion caused by the missing tags and labels represents a safety issue for the O&M staff during preventive and corrective maintenance.
3.3.3	Open connectors	Connectors not properly closed have an increased local resistance between the male and female connector leading to an increase fire risk.
3.3.4	Poor cable fixation	Hanging cables due to non-durable cable ties are more exposed to mechanical damage caused by the wind and the friction against other components such as the mounting structure or the module frames.
3.3.5	Insufficient bending radius	Not respecting the bending radius specified by the cable manufacturer leads to the loss of the product warranty and to an increased risk of shield damage. Damaged cable shields are responsible for insulation losses and associated safety issues.
3.3.6	Not suitable tubes for outdoor	The tubes used for routing the cables should be suitable for outdoor conditions and should withstand the action of humidity, rain and UV radiation among others. Not fulfilling these conditions makes these tubes useless in the midterm leaving the cables without protection.
3.3.7	No sealing of pipes	Sealing the pipes and tubes helps protecting the cables from water and dirt accumulation as well as mechanical damage caused by animals. No foam was used to seal the pipes.
3.4	Inverter	
3.4.1	Poor cable guidance into the inverter	The connection of the RS 485 cable wasn't conducted with appropriate junctions and cable glands. Additionally, the size of the input cable is lower than the RS 485 cable which leads to an improvised solution where the shield had to be removed letting the interface between cable and gland unprotected. The long-term durability of the cable at the interface with the inverter is not ensured.
3.5	Grounding and equipotential bonding system	
3.5.1	Continuity not ensured due to corrosion	The continuity of the equipotential bonding system is not ensured due to the appearance of rust at the junctions of the various belts. The rust is responsible for an increase of the resistance of the belts, which leads to an increased voltage drop when the fault current flows through the rusted conductor. As rust develops, the voltage drop increases limiting the correct functionality of the equipotential bonding system losing its capacity to protect against uneven potentials.
3.5.2	No functional grounding against PID	No anti-PID measures were taken in order to avoid the appearance and development of PID. The Delhi region is a PID risk area due to high temperatures and humidity. The development of PID can't be excluded as long as the PID sensitivity in the modules isn't confirmed.
3.6	Documentation	
3.6.1	No compliance of the as-built documentation with the IEC 62446	The as-built documentation is not complete according to the applicable norms and standards. This represents a risk for instance during takeover, as the new Owner acquires an asset whose installation, BOM and drawings are not properly documented.
3.6.2	Missing construction progress reports	The installation phase reports are very helpful during O&M as they include valuable information of one of the most relevant phases of the project. Not having access to this information means losing part of the history of the plant.
4	Commissioning	
4.1	Insufficient commissioning tests. No compliance with the IEC 62446	Due to the fact that no EPC contract has been issued since the Owner and EPC are the same entity, there are no warranties to be provided by the latter. One of the most relevant EPC warranties is the performance warranty which is typically expressed as a PR test to be conducted during an agreed amount of days at PAC and FAC. This test was not conducted. In regards to the commissioning requirements specified by the IEC 62446, no tests have been conducted either. The present situation shows a scenario where the plant hasn't been commissioned neither considering the performance values, nor in terms of safety.
5	System Performance	
5.1	BOM of the weather station not complete. Installation failures.	The cell temperature and the global horizontal irradiation (GHI) are not measured onsite. These parameters are an essential part of a correct meteorological data assessment of an operating plant. The cell temperature is especially important for conducting a PR correction, which is a crucial step for a proper comparison between the onsite PR and the contractual PR. Besides, the cables connecting the sensor to the communication box are neither protected nor properly fixed.
6	PV Module Quality	
6.1	No specific certificates beyond the basic IEC certification requested to the manufacturer	No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors present in Delhi. The high temperature, UV and humidity rates registered onsite represent a threat for the PV modules in terms of long-term durability.

7	Operation and Maintenance	
7.1	No evaluation of the impact of the cleaning concept on the module warranty	The impact of the selected cleaning methodology on the module warranty hasn't been analyzed. Several factors such as the material used for the wipers, the type of water, the cleaning methodology, the water pressure and the physical and chemical properties of the soil, might have an influence on the glass and the anti-reflective coating of the modules. Product damages or performance losses of any kind originated by the cleaning process are not covered by the product warranty unless the cleaning concept has been approved previously by the module manufacturer. This step was not given before starting the operational phase.
7.2	No system availability calculation	The system availability is not measured, neither on inverter nor on string level. As a consequence, it remains unknown if the amount of operational hours of the various subsystems such as inverters or module strings, can be increased leading to a maximization of the yield output.

5.2 Plant 2 - 1,505 kWp rooftop (Uttar Pradesh)

<i>Date of inspection by PI Berlin</i>	04.07.2017
<i>Name and size of the plant</i>	confidential, 1505kWp (roof top)
<i>Coordinates</i>	confidential
<i>Commercial Operation Date (COD)</i>	confidential
<i>Name of the Owner</i>	confidential
<i>Name of the EPC</i>	confidential
<i>Name of the O&M company</i>	confidential
<p><i>The 1,505 kW PV plant is split into several roofs. 2 PV modules are arranged in portrait and tilted at 20° building strings of 20 modules in series. Between 4 and 10 strings are connected in parallel to 20kW or 50kW string inverters. The inverters are connected with 4R: 1Cx10mm² or 4R: 1Cx35mm² XLPE Cu protected with 63A or 100A breakers to IP65 AC combiner boxes. The 1R 3.5Cx50mm² lines are protected with 100, 125, 200, 250 or 400A and are collected by one aluminium bar that leads to the meter. A PPA between the PV plant owner and the building owner was signed for 25 years.</i></p>	

5.2.1 Contracts

Under this chapter PI Berlin has put the main focus on:

- EPC contract
- O&M contract
- Role of the Owner's Engineer
- Role of the Lender's Technical Advisor supporting the financing institution

The evaluation of the above mentioned points leads to the following outcomes

- A typical EPC contract wasn't created since the Owner and EPC are the same entity. Hence, no standard EPC warranties expressed as Provisional Acceptance Commissioning (PAC) or Final Acceptance Commissioning (FAC) certificates exist.
- A typical O&M contract wasn't created since the owner and operator are the same entity. Hence, no standard O&M warranties based on Performance Ratio or system availability were formulated.
- There is no EPC contract, hence no binding Provisional Acceptance Commissioning (PAC) tests have been conducted.
- No Owner's Engineer was appointed.
- No Lender's Technical Advisor was appointed since this was not required by the financing institution.

5.2.2 PV Plant Design

This chapter analyses:

- Interrow shading based on the selected pitch and tilt
- Statics
- Location of inverters and combiner boxes

Interrow shading based on the selected pitch and tilt

PI Berlin has measured the pitch at several locations. The results show variations between 5.1m and 6.5m (lower edge-lower edge). No PV SYST simulation was provided by the Owner. PI Berlin has measured module tilt values between 19° and 20° in most locations of the PV plant. The tilt angle of the PV modules seems to be very consistent. A variation of the pitch at 19° leads to variations in the interrow shading of 1.9% according to the PV SYST simulations.

Statics

No static calculations were shared with PI Berlin, hence the structural integrity of the roof in combination with the PV plant loads could not be proven.

Location of inverters and combiner boxes

The inverters and distribution boxes are located considering cable and voltage drop reduction criteria. The cable runs are kept short avoiding an unnecessary voltage mismatch at inverter level. This statement bases both on the onsite inspection as well as on the review of the as-built layouts provided by the Owner.⁸

5.2.3 Electromechanical Installation

The quality of the electromechanical installation was assessed onsite by PI Berlin evaluating the following subsystems:

- Mounting structure
- Combiner boxes
- Cables fixation
- Inverter
- Grounding and equipotential bonding
- Civil work
- Documentation

Mounting structure and module fixation

- Module fixation: The modules are fixed to galvanize steel U-profiles using screws and nuts. This system does not always ensure a proper fixation.



Figure 41: Loose fixation of the PV modules to the cross beam

⁸ PI Berlin has reviewed the drawings "1.2 IIT XXX-1 Plant Array Layout 504 kW.pdf", "2.2 IIT XXX-2 Plant Array Layout 504 kW.pdf" and "3.2 IIT XXX-3 Plant Array Layout 510 kW.pdf" sent by the Owner on the 3rd July 2017

- ii. Labelling of rows: No labelling of module rows could be observed.



Figure 42: Missing labelling of the module rows

- iii. Rust on the mounting structure surface: Rust couldn't be observed on the mounting structure profiles, the galvanized steel layer remains undamaged.



Figure 43: Clean mounting structure surface with no rust

- iv. Foundation: The foundation of the mounting structure does not seem to be durable for the whole lifetime of the project.



Figure 44: Improper anchorage of the mounting structure foundation to the roof top surface

Combiner boxes

The AC combiner boxes are properly sealed and are clean inside. The AC combiner boxes are not labelled with durable tags.

Cables fixation and routing

- i. Cable damage: The cables do not show damages caused by external agents.
- ii. Labelling of cables: Both the strings cables entering the inverter and the AC cables connecting the inverter with the AC combiner box, do not show a consistent labelling concept. In both cases the used tags do not seem to be durable for the whole lifetime of the project.




Figure 45: (left) Inconsistent labelling of the string cables; (right) Non-durable tags of the AC cables

- iii. Connectors: The connectors are in general in a good shape.
- iv. Cable fixation: The cables ties used for the cable fixation are not suitable for outdoor exposure and start falling apart.




Figure 46: Improper fixing of the string cables to the mounting structure

- v. Bending radius: In general, the minimum bending radius of the cables has been respected.
- vi. Protection against UV: A lack of UV protection of the cables has been detected in the gaps between module tables.



Figure 47: Missing UV protection of the string cables

- vii. Sealing of tubes: The tubes conducting the DC cables to the inverter are not sealed.



Figure 48: Non sealed cable conduits

- viii. Cable pipes: The tubes where the cables are routed do not show degradation due to outdoor exposure.



Figure 49: Cable pipes used for routing the string cables

Inverter

The inverters have an overvoltage protection both on the DC and AC side as well as a DC switch. The cooling of the inverter is ensured with active fans and the inverter filters are clean. The housing is grounded and the IP 65 is ensured. The inverters could not be opened due to warranty aspects, hence no information about the cleanliness of the inverter inside can be provided. All inverters are protected from the sun.

Grounding and equipotential bonding

The equipotential bonding system connects all conductive parts of the PV plant as the mounting structure, module frames or housings. The equipotential bonding system of the PV plant is not integrated in the equipotential bonding system of the building which violates the requirements specified in the IEC 62305-3. The equipotential bonding belt does not show signs of corrosion. In terms of Potential Induced Degradation (PID) avoidance, no measures have been taken, such as functional grounding of the negative pole. The presence of PID could be confirmed on site as shown in chapter 5.2.6.



Figure 50: Equipotential bonding system conductor

Documentation

In terms of completeness, the provided documents do not comply with most of the requirements of the IEC 62446. Several aspects, such as the project report, commissioning protocols, string layout, O&M activities or mechanical design information have not been documented. During the installation phase no progress reports were issued.

5.2.4 Commissioning

PI Berlin considers the commissioning process conducted at the end of the installation phase a crucial milestone in the deployment of a PV project. The commissioning process as per IEC 62446 is divided in “cold” and “hot” commissioning, and ends with the issuance of the Provisional Acceptance Certificate, and is the last step before the EPC warranty starts. This process gives an idea of the status of the plant in terms of safety and functionality. Due to the fact that no EPC contract has been issued since the Owner and EPC are the same entity, there are no warranties to be provided by the latter either. Thus, a proper commissioning of the PV plant as specified in the IEC 62446 was not conducted prior to COD. The only test carried out on site corresponds to the AC phase voltage check and the earth resistance check conducted in the various buildings.⁹ No third party was involved during the commissioning process, as the same did not take place as required by the IEC 62446.

5.2.5 System Performance

In this chapter PI Berlin analyses several factors that influence the calculation of the system performance.

Weather station status and sensor accuracy

The review of the logged ambient temperature and the cell temperature for the period between the 23rd March 2017 and 25th June 2017 shows significant deviations above +/- 5.6K. The ambient temperature is not placed at a representative location of the site.¹⁰ No calibration certificates were provided to PI Berlin.

⁹ “PI Berlin has reviewed the file “Earthing& Voltage test.pdf” sent by the Owner on the 3rd July 2017.”

¹⁰ PI Berlin has reviewed the file “pIITXXX Sensor data_Daily.xlsx” sent by the Owner on the 3rd July 2017.”



Figure 51: Ambient temperature sensor

The weather station is constituted by a c-Si sensor which is measuring both the irradiation on the tilted plane and the ambient temperature. A Pt sensor adhered to the backsheet of the modules for measuring the module temperature is missing. The global horizontal irradiation (GHI) is not measured either.

Performance Ratio calculation

No Performance Ratio tracking is conducted onsite. The losses due to soiling are not measured in order to calculate the real PR of the plant. The simulated output during the development phase is based on 1 month of operation and uses data and estimations provided by papers and studies and not necessarily site specific variables.

5.2.6 PV Module Quality

The PV modules represent the most sensitive part of the PV plant, especially in harsh climates with high UV loads, high temperatures and high humidity. These environmental stressing factors are present on site whose climate is classified as Csa according to Köppen-Geiger [21]. In order to assess the quality of the modules PI Berlin has conducted a visual inspection and an infrared analysis using the equipment specified in Annex IV. The investigated aspects are listed as follows:

Results of the visual inspection


The visual inspection on the modules did not show major defects affecting the quality of the BOM, the system performance or the safety of persons, animals and goods. No scratches of the backsheet were detected. No snail trails were detected on site either.

Long term durability certificates

No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors mentioned above. Apart from this, no flash lists of the PV modules are available.

Infrared analysis

The infrared inspection showed clear evidences of PID.






Figure 52: PV modules affected by PID

Electroluminescence analysis

The electroluminescence analysis on a selected amount of PV modules confirmed the presence of PID.




Figure 53: PV modules affected by PID

5.2.7 Operation and Maintenance

The quality of the Operation and Maintenance service has been evaluated considering the points listed below. PI Berlin had the chance to interview a few members of the O&M team while conducting the site visit.

Experience of the O&M team

According to the Owner, at the time of the installation of the PV plant, the workers had no previous experience in PV. This is the first PV project operated by the Owner.

Cleaning methodology and calculation of the soiling loss

The module cleaning is performed 2 times a month using cotton wipers and tap water. The impact of the selected cleaning methodology on the module warranty hasn't been analysed by the Owner and Operator. 2 persons are involved in the cleaning. The impact of the selected cleaning methodology on the module warranty hasn't been analysed. No soiling losses are measured onsite.



Figure 54: Wipers used for the module cleaning

Tools used on site

No PV specific tools and devices are used onsite.

Reporting and reaction times

No O&M reports are issued, only the generation is registered. According to the Operator, the reaction time is kept below 24h for all failures. PI Berlin could not prove this statement.

Preventive and corrective maintenance

No preventive and corrective maintenance programs had been set up at the time of the visit.

Availability calculation and SCADA monitoring

The system availability is not calculated. The PV plant has no SCADA system.

Curtailement and grid stability

According to the plant Operator the curtailment losses originated by the DSO are not significant due to the high grid availability. According to the plant Operator the PV plant is not forced to support actively the grid due to its reduced size.

5.2.8 Summary of the Results

The following table summarizes the failures detected onsite and the associated risks.

Table 2: Summary of the failures and the associated risks – Plant 2

Ref.	Item	Risk Description
1	Contracts	
1.1	No appointment of an Owner's Engineer	The OE has the task to support the Owner's interests against the EPC and the various product suppliers. The OE conducts independent checks and verifications starting at the earlier phases of the EPC tendering and ending after commissioning or beyond. The absence of an experienced OE as an independent party, may lead to an increased risk for the Owner. The quality assurance services provided by an OE are highly recommended in order to avoid mistakes in all stages of the value chain.
1.2	No appointment of a Lender's Technical Advisor	Similarly to the OE, the LTA supports the interests of the bank as the financing institution. Accordingly, the bank is interested in financing projects which are bankable and are exposed to low risks. Thus, the task of the LTA is to ensure the bankability of the project by supervising that all steps made by the Developer (very often also the Owner at the same time) lead to a low risk scenario. In this project the financing institution did not require the services of an LTA.
1.3	Not existing EPC contract.	A typical EPC contract wasn't created since the Owner and EPC are the same entity. Hence, no standard EPC warranties expressed as Provisional Acceptance Commissioning (PAC) or Final Acceptance Commissioning (FAC) certificates exist. Only the product warranties prevail. The lack of an EPC contract is typical in scenarios where the Owner and EPC are the same company since all services are placed under the same roof. The EPC warranties have the goal to put pressure on the EPC in order to ensure that the plant meets certain quality criteria which ensure that the plant will last longer than the EPC warranty period (usually 24 months). According to the present scenario, no EPC warranties exist, so no specific tests were conducted that would help to assess the quality of the plant in terms of functionality, safety and performance.

1.4	Not existing O&M contract. Poor or not existing O&M warranties	A typical O&M contract wasn't created since the Owner and Operator are the same entity. Hence, no standard O&M warranties based on Performance Ratio or system availability were formulated. The lack of O&M warranties leads to a comfortable scenario where the O&M team has no special incentive to force the PV plant to run at its maximum potential. The consequences are usually a lower availability and a lower output than expected.
2	PV Plant Design	
2.1	Not consistent interrow shading simulation.	The PV plant shows variations of the pitch between 5.1m and 6.5m in different areas which leads to an interrow shading variation of 1.8% according to the PV SYST simulations conducted by PI Berlin. The design and simulation of the plant has been conducted by the EPC with a fixed tilt and pitch which does not fully reflect the as-built situation. This uncertainty affects directly the P90 and the financial model of the project.
2.2	Missing statics	No static calculations were conducted by the EPC considering the applicable wind loads and mounting structure design. Hence, the structural integrity of the roof in combination with the PV plant loads could not be proven. This scenario carries risks to the Owner.
3	Electromechanical Installation	
3.1	Mounting structure	
3.1.1	Poor module fixation	The module fixation based on screws and nuts fixed to the U-profile does not ensure the long-term durability of the module fixation and is not suitable for PV applications.
3.1.2	No row labelling	The missing row labelling makes the correct identification of the various areas of the plant more difficult leading to increased reaction times during corrective maintenance.
3.1.3	Weak foundation, no solid anchorage	The foundation loses adherence to the roof top surface which affects the structural strength of the mounting structure.
3.2	Combiner boxes	
3.2.1	No labelling of the boxes.	The missing combiner box labelling makes the correct identification of the various areas of the plant more difficult leading to increased reaction times during corrective maintenance. Additionally, electrical parts that aren't properly labelled hide safety risks when manipulated by O&M members.
3.3	Cables	
3.3.1	Poor or not existing labelling of the DC cables	A non-durable or non-existing cable labelling makes the correct identification of the various electrical circuits more difficult leading to increased reaction times during corrective maintenance. Additionally, the confusion caused by the missing tags and labels represents a safety issue for the O&M staff during preventive and corrective maintenance.
3.3.2	Poor cable fixation	Hanging cables due to non-durable cable ties are more exposed to mechanical damage caused by the wind and the friction against other components such as the mounting structure or the module frames.
3.3.3	Poor or insufficient UV protection	The cables should not be exposed to the direct sunlight since the long term durability of the cable shield may be affected. This effect was detectable mainly in the gaps between the mounting tables.
3.3.4	No sealing of pipes	Sealing the pipes and tubes helps protecting the cables from water and dirt accumulation as well as mechanical damage caused by animals. No foam was used to seal the pipes.
3.4	Grounding and equipotential bonding system	
3.4.1	Equipotential bonding system (EBS) not integrated in the EBS of the building	The equipotential bonding system of a PV plant installed on a roof should be integrated in the equipotential bonding system of the building in order to avoid uneven potentials and risks of indirect contact.
3.4.2	No functional grounding against PID	No anti-PID measures were taken in order to avoid the appearance and development of PID. The region around Plant 2 is a PID risk area due to high temperatures and humidity. The presence of PID was confirmed onsite.
3.5	Documentation	
3.5.1	No compliance of the as-built documentation with the IEC 62446	The as-built documentation is not complete according to the applicable norms and standards. This represents a risk for instance during takeover, as the new Owner acquires an asset whose installation, BOM and drawings are not properly documented.
3.5.2	Missing construction progress reports	The installation phase reports are very helpful during O&M as they include valuable information of one of the most relevant phases of the project. Not having access to this information means losing part of the history of the plant.
4	Commissioning	
4.1	Insufficient commissioning tests. No compliance with the IEC 62446	Due to the fact that no EPC contract has been issued since the Owner and EPC are the same entity, there are no warranties to be provided by the latter. One of the most relevant EPC warranties is the performance warranty which is typically expressed as a PR test to be conducted during an agreed amount of days at PAC and FAC. This test was not conducted. In regards to the commissioning requirements specified by the IEC 62446, only a few tests were conducted. The present situation shows a scenario where the plant hasn't been commissioned considering the performance values, and the safety checks according to the IEC 62446 have been conducted only partially.
5	System Performance	

5.1	Not consistent logging of the temperature values	The ambient temperature sensor does not provide consistent data. Besides, the location where it's placed is not representative for the whole PV plant. Both aspects combined lead to recorded values that do not reflect the real situation on site. Inaccurate values lead to a wrong assessment of the system performance of the plant.
5.2	BOM of the weather station not complete	The cell temperature and the global horizontal irradiation (GHI) are not measured onsite. These parameters are an essential part of a correct meteorological data assessment of an operating plant. The cell temperature is especially important for conducting a PR correction, which is a crucial step for a proper comparison between the onsite PR and the contractual PR.
5.3	No PR calculation conducted onsite	The real PR is not calculated which makes a correct assessment of the system performance impossible.
5.4	The yield simulation during the development phase does not use site specific data	The yield assessment conducted during the development phase should use input data that are site and project specific. Otherwise, the assessment won't reflect the system performance properly (with the corresponding limitations) and won't be bankable.
6	PV Module Quality	
6.1	No flash lists available	The flash lists shall be provided by the module manufacturer as part of the quality control program. The flash lists are useful for determining the exact nominal power of the PV plant and for conducting an adequate module sorting, among other reasons.
6.2	No specific certificates beyond the basic IEC certification requested to the manufacturer	No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors present on site. The high temperature, UV and humidity rates registered onsite represent a threat for the PV modules in terms of long-term durability.
6.3	Presence of PID	The PID effect can be responsible in the short term, for a significant reduction of the PV power output of the modules located on the negative side of the string, and should be stopped immediately. The development of PID is accelerated with high temperatures and humidity rates, both present at the PV plant location.
7	Operation and Maintenance	
7.1	Lack of experience of the O&M team	The lack of experience of the O&M team may lead to a wrong diagnose of the detected failures, as well as to an inaccurate corrective maintenance, among other consequences. In order to maximize the performance and availability of the PV plant, the O&M team should be familiar with as many events as possible in all potential scenarios.
7.2	Definition of the cleaning intervals without knowing the accumulated soiling losses between 2 periods	The losses due to soiling are not measured onsite. 2 cleaning rounds per month have been agreed without conducting a previous study on the accumulated soiling loss between 2 periods. As a consequence, the cleaning frequency is not adjusted to a defined soiling loss which should not be exceeded. Actually, due to the amount of cleaning rounds defined in advance, there might be some periods when the PV plant is "undercleaned" and others in which the PV plant is "overcleaned". In the first case performance is lost, while in the second case unnecessary costs are generated.
7.3	No evaluation of the impact of the cleaning concept on the module warranty	The impact of the selected cleaning methodology on the module warranty hasn't been analyzed. Several factors such as the material used for the wipers, the type of water, the cleaning methodology, the water pressure and the physical and chemical properties of the soil, might have an influence on the glass and the anti-reflective coating of the modules. Product damages or performance losses of any kind originated by the cleaning process are not covered by the product warranty unless the cleaning concept has been approved previously by the module manufacturer. This step was not given before starting the operational phase.
7.4	No PV specific devices used onsite	Devices and tools used in the PV industry such as IV curve tracers, electroluminescence sets and infrared cameras help detecting and evaluating failures easily. The regular use of these devices is necessary during O&M for detecting and monitoring defects and degradation phenomena such as hot spots, cracks or PID.
7.5	Poor reporting	The reporting of the O&M activities should contain monthly and yearly reports specifying production data, availability values, spare parts managements, costs, outage time, preventive and corrective actions, trend analysis, meteorological data and accumulated production among other values. A poor reporting activity does not support a proper monitoring of the plant operation which is crucial for a successful asset management orientated to maximize the performance and operating hours.
7.6	Preventive maintenance not adjusted to the PV technology. Corrective maintenance without analysis of the root cause, mitigation measures, documentation and follow up	There is neither preventive nor corrective maintenance conducted onsite. The maintenance activities are a crucial task to maximize the performance and the availability of the system. No root cause analysis, mitigation actions and follow up is conducted on the events registered onsite. Part of the corrective maintenance is to investigate the origin of the failures, find a solution and monitor the evolution in the short term.
7.7	No system availability calculation	The system availability is not measured, neither on inverter nor on string level. As a consequence, it remains unknown if the amount of operational hours of the various subsystems such as inverters or module strings, can be increased leading to a maximization of the yield output.

5.3 Plant 3 - 50MW ground mounted (Rajasthan)

Date of inspection by PI Berlin	06.07.2017
Name and size of the plant	confidential, 50MW (ground mounted)
Coordinates	confidential
Commercial Operation Date (COD)	confidential
Name of the Owner	confidential
Name of the EPC	confidential
Name of the O&M company	confidential
<p>The 50MW PV plant uses three different module types with an arrangement of 2 modules portrait and 4 landscape at 22° tilt building strings of 21 or 24 modules in series. Between 8 and 20 strings are connected in parallel to 8 DC combiner boxes leading to 680kW inverters.</p> <p>3 or 4 inverters are connected to a 4 or 5 winding transformer (0.38/33kV) of 2.1 or 2.8MVA. The 33kV line 3Cx185mm² AL is connected to a common bar with 3Cx300mm² AL leading to the substation. The level of injection is at 132kV. Each owner of the five 10MW blocks has signed a PPA with SECI for 25 years.</p>	

5.3.1 Contracts

Under this chapter PI Berlin has put the main focus on:

- EPC contract
- O&M contract
- Role of the Owner's Engineer
- Role of the Lender's Technical Advisor supporting the financing institution

The evaluation of the above mentioned points leads to the following outcomes:

- The EPC warranty has a limited duration of 12 months. A PR test is conducted at PAC and FAC. The Procurement of the components has been conducted by the Owner. The EPC advised the Owner on the procurement of the PV modules. Besides the PR test, the EPC isn't forced to conduct any other test as per the IEC 62446
- A typical O&M contract wasn't created since the Owner and Operator are the same entity. Hence, no standard O&M warranties based on Performance Ratio or system availability were formulated.
- A consultancy company was appointed as Owner's Engineer. According to the Owner, the consultant was involved in the production and transport of the modules, including a factory audit.
- A consultancy company was hired by the bank as Lender's Technical Advisor

5.3.2 PV Plant Design

This chapter analyses:

- Interrow shading based on the selected pitch and tilt
- Statics
- Location of inverters and combiner boxes
- Electrical overbuilt

Interrow shading based on the selected pitch and tilt

The pitch (lower edge-lower edge) is 7m according to the design. This value was confirmed onsite by PI Berlin. No PV SYST simulation was provided by the Owner. PI Berlin has measured module tilt values very close to 22° in most locations of the PV plant. The tilt angle of the PV modules seems to be very consistent and matches the design criteria. 2 different module arrangements have been mixed: 2 portrait and 4 landscape. According to the PV SYST simulations the different arrangement barely influence the mutual shading behavior.




Figure 55: Tilt measurement device

Statics

No static calculations were shared with PI Berlin, hence the structural integrity of the mounting structure couldn't be proven. However, the module fixation doesn't withstand the wind loads registered onsite.



Figure 56: Damaged modules due to strong winds

Location of inverters and combiner boxes

The inverters and distribution boxes are located considering cable and voltage drop reduction criteria. The cable runs are kept short avoiding an unnecessary voltage mismatch at inverter level. This statement bases both on the onsite inspection as well as on the review of the as-built layouts provided by the Owner. The following screenshot of one of the inspected drawings shows the location of the inverters and AC combiner boxes




Figure 57: DC combiner boxes in green and inverters in red

Electrical overbuilt

The tender specifications¹¹ allow a plant design with an overbuilt higher than 1 as long as the AC capacity is not exceeded. However, the selected capacity is very close to 1 which leads to waste AC capacity even though the partial load behavior of the inverter is more efficient. The DC and AC capacity values specified in some of the evaluated documents are not consistent. The DC and AC capacity are specified as 50 MWp and 50MW respectively according to the excel file "Checklist XXXX.xlsx" provided by the Owner, and as 57.5 MWp and 48.96 MW according to the EPC contract¹² and the as-built drawings¹³.

5.3.3 Electromechanical Installation

The quality of the electromechanical installation was assessed onsite by PI Berlin evaluating the following subsystems:

- Mounting structure
- Combiner boxes
- Cables fixation
- Inverter

¹¹ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013

¹² The file "TGE_MEPC_Contract backup.pdf" was provided to PI Berlin by the Owner on the 20th June 2017

¹³ The file "Array layout.pdf" was provided to PI Berlin by the Owner on the 20th June 2017

- Grounding and equipotential bonding
- Civil work
- Documentation

Mounting structure and module fixation

- Module fixation:** The modules are not always properly fixed to the cross beams which leads to a misalignment along the mounting tables.



Figure 58: Improper module fixation

- Labelling of rows:** The labelling of the mounting structure hasn't been conducted in all areas of the PV plant. Besides, the labels are not durable for the entire lifetime of the project.



Figure 59: Improper row labelling

- Rust on the mounting structure surface:** The mounting structure shows advanced levels of rust due to the salty environment.






Figure 60: Mounting structure affected by rust due to the salty environment

Combiner boxes

- i. Sealing of the cable glands: The cable glands of the combiner boxes are not properly sealed.



Figure 61: Not sealed cable glands (a screwdriver has been passed through the cable gland to show that it is not properly sealed)

- ii. Cleanliness of the combiner box: The dust accumulation inside the combiner boxes is significant.




Figure 62: Dust presence inside the combiner boxes

- iii. Labelling of the combiner box: The DC combiner boxes aren't labelled with durable tags.



Figure 63: Non-durable labelling of the DC combiner boxes

Cables fixation and routing

- i. **Cable damage**: The cables do not show damages caused by external agents. However, many cables are in contact with sharp edges of the metallic cable trays, thus, an erosion of the cable shield can't be excluded in the midterm.



Figure 64: String cables in contact with sharp edges

- ii. **Labelling of cables**: Both the strings cables entering the combiner box and the main DC cables connecting the combiner box with the inverter aren't properly labelled. In both cases the used tags are either not durable or do not exist at all.



Figure 65: Non-durable string cable labelling

- iii. **Connectors**: The connectors are in general in a good shape. In some cases the connectors are not properly closed.



Figure 66: MC connectors

- iv. Cable fixation: The cables ties used for the cable fixation are not suitable for outdoor exposure and start falling apart.



Figure 67: Improper cable fixation of the string cables

- v. Bending radius: In general, the minimum bending radius of the cables has been respected. In some cases the manufacturer requirements are not fulfilled.



Figure 68: Low bending radius of the string cables

- vi. Protection against UV: A lack of UV protection of the cables has been detected in many areas of the plant. This affects mainly hanging cables between module rows and open cable trays.



Figure 69: String cables not protected against UV radiation

- vii. Sealing of tubes: The tubes conducting the DC cables to the inverter are not sealed.




Figure 70: Tubes used for the string cable routing not sealed

- viii. Cable pipes: The tubes where the cables are routed show degradation due to outdoor exposure.



Figure 71: Degraded cable pipes due to outdoor exposure

Inverter

The inverter has an overvoltage protection on the AC side as well as a DC switch. The inverter room shows a significant amount of dust. During the site visit a dust cloud was created when the air ventilation fan was switched on showing that the dust accumulates fast. The inverter has a default ventilation system. The inverter room does not have a thermostat that regulates the temperature inside the housing, so the cooling is conducted when the air ventilation fan is connected manually which happens only during selected months of the year. The inverter filters and air inlets are clean.



Figure 72: (top and bottom left) Presence of dust inside the PCU; (right) Air inlets of the PCU

Grounding and equipotential bonding

The equipotential bonding system connects all conductive parts of the PV plant as the mounting structure, module frames or housings. The equipotential bonding conductor is heavily damaged by the corrosion of the ground and is not properly buried. In terms of Potential Induced Degradation (PID) avoidance, no measures have been taken, such as functional grounding of the negative pole. The PV plant does not show signs of PID.




Figure 73: Heavily damaged equipotential bonding system due to corrosion

Civil work

The status of the internal roads is good. No drainage system has been installed on site. According to the Owner and Operator of the plant, the terrain has problems absorbing high amounts of rain water. The concrete used for the foundations onsite corresponds to the type M30.

Documentation

In terms of completeness, the provided documents comply with most of the requirements of the IEC 62446. During the installation phase no progress reports were issued.

5.3.4 Commissioning

PI Berlin considers the commissioning process conducted at the end of the installation phase a crucial milestone in the deployment of a PV project. The commissioning process as per IEC 62446 is divided in “cold” and “hot” commissioning, and ends with the issuance of the Provisional Acceptance Certificate, and is the last step before the EPC warranty starts. This process gives an idea of the status of the plant in terms of safety and functionality.

In the case of the 50MW PV plant a proper commissioning of the PV plant as specified in the IEC 62446 was not conducted prior to COD. According to the EPC contract, the commissioning is passed when following conditions are met: “*The Subcontractors have installed the Facility in accordance with the Contract and the respective Subcontractors, excluding any punch-list items; and the Facility has delivered power to the Grid*”.¹⁴ Additionally, on page 42 of the EPC contract the requirements for a Performance Ratio test are specified. This test is conducted during 7 consecutive days and the contractual value is defined on monthly basis. The simulated values base on a plant configuration which uses PV modules different than those actually built and no correction of the temperature is requested. According to the Owner, the LTA was present during the PR test. A Final Acceptance Commissioning (FAC) is mentioned but no date is specified.

Besides the contractual conditions described in the EPC contract, the official commissioning is approved as per the tender requirements¹⁵ after the submission of a short document issued by the State Nodal Agency of Rajasthan containing the installed capacity, an electrical inspector report, the connectivity report, the synchronization certificate, photos and an installation report.

5.3.5 System Performance

In this chapter PI Berlin analyses several factors that influence the calculation of the system performance.

Weather station status and sensor accuracy

PI Berlin had no access to the readings of the irradiation and temperature data of the installed sensors. According to the Owner, the sensors are calibrated each 6 months. No calibration certificates were provided to PI Berlin. The weather station is constituted by a pyranometer on the tilted plane, an ambient temperature sensor and an anemometer. A Pt sensor adhered to the backsheet of the modules for measuring the module temperature is missing. The global horizontal irradiation (GHI) is not measured. The metal arm fixing the pyranometer to the mounting structure is too long leading to an oscillation of the sensor when the wind blows.



Figure 74: Pyranometer installed onsite

¹⁴ “PI Berlin has reviewed the file “XXXX_Contract backup.pdf” sent by the Owner on the 17th July 2017.”

¹⁵ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013

Performance Ratio calculation

The data corresponding to the first year of operation were not registered since the sensors were missing, and those corresponding to the second year were not provided to PI Berlin. According to the tender requirements specified by SECI¹⁶ the minimum CUF shall not be below 17%¹⁷. Evidences showing that the plant is matching this condition haven't been shared with PI Berlin. The PR is calculated using the irradiation values registered by the pyranometer and the metered production. PI Berlin had no access to daily or monthly PR values. The simulated output of the plant using Meteororm data and calculated for defining the contractual PR of the EPC contract was not provided to PI Berlin.

5.3.6 PV Module Quality

The PV modules represent the most sensitive part of the PV plant, especially in harsh climates with high UV loads, high temperatures, abrasion, high humidity rates, salinity and presence of sand and dust. These environmental stressing factors are present on site whose climate is classified as BWh according to Köppen-Geiger [21]. In order to assess the quality of the modules, PI Berlin has conducted a visual inspection, an infrared analysis and an electroluminescence inspection using the equipment specified in Annex IV. The investigated aspects are listed as follows:

Results of the visual inspection

The visual inspection on the modules showed clear signs of snail trails and evidences of burned cells. Some modules showed backsheet fully covered with mud while others were scratched pointing towards an improper module handling. In some sporadic cases, the junction box is not properly aligned with the module frame. Footprints were detected on the module surface in some areas of the plant. According to the Owner the flash lists of the PV modules are available, however these were not shared with PI Berlin.



Figure 75: (top left) Scratched module backsheet; (top right) J-box misaligned; (bottom left) Burned cell front; (bottom right) Burned cell

¹⁶ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013

¹⁷ "The declared annual CUF shall in no case be less than 17% over a year." - page 23 section 3.8 (i)



Figure 76: Module backsheet covered with mud



Figure 77: PV modules showing snail trails

Long term durability certificates

No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors mentioned above. The BOM was directly negotiated with the module supplier.

Infrared analysis

The infrared inspection showed clear evidences of soldering problems. Additionally, the cell and module cracks evidenced by the snail trails, are also visible on infrared basis as hot spots.




Figure 78: PV modules affected by bad soldering

Electroluminescence analysis

The electroluminescence analysis on a selected amount of PV modules confirmed the presence of cell cracks and shunts caused by an inaccurate soldering process of the ribbon to the busbars¹⁸.




Figure 79: PV Modules affected by cracks




Figure 80: (Black) Damaged cells due to backsheet scratches; (blue) Inhomogeneous current flow due to bad soldering; (red) Shunts due to bad soldering; (green) Hotspots due to bad soldering

5.3.7 Operation and Maintenance

The quality of the Operation and Maintenance service has been evaluated considering the points listed below. PI Berlin had the chance to interview a few members of the O&M team while conducting the site visit.

Experience of the O&M team

This is the first project operated by the Owner. 15 people are involved in the O&M of the plant. The years of experience of the O&M members vary between 2 and 5. At the moment the Owner owns and operates more

¹⁸ See chapter 4.4

than 100MWp of PV assets in India, all of them have signed PPAs with governmental bodies.

Relevant environmental elements

The most relevant environmental phenomena reported onsite are: sandstorms, highly corrosive environment due to salt presence, strong winds and difficulties with water drainage. The O&M plan does not include specific actions to mitigate the effects of the abovementioned phenomena.



Figure 81: (top and bottom right) Salt presence onsite; (bottom left) Removed modules due to strong winds

Cleaning methodology and calculation of the soiling loss

According to the Owner and Operator, the module cleaning is performed 2 times a month using cotton wipers and underground water stored at 5kg/cm². The impact of the selected cleaning methodology on the module warranty was not analysed by the Owner and Operator. 2 persons are involved in the cleaning. No soiling losses are measured onsite and the cleaning campaign is started after conducting only a visual analysis of the PV module surface. It could be observed that the remaining water drops on the module surface attract dust and dirt particles.





Figure 82: (top and bottom left) Module cleaning system; (bottom left) Dust and soil attracted by water drops

Tools used on site

The O&M team uses current clamps, multimeters, insulation measurement devices and tools for measuring the continuity and the ground resistance. No PV specific tools and devices are used onsite.

Reporting and reaction times

Daily O&M reports are issued registering only the PV plant output generation. According to the Operator, the reaction time is kept below 24h for all failures. PI Berlin could not prove this statement. An increase of the reaction times is caused by the cable trays blocking the access by car to the interrow space.



Figure 83: Cable routing system disturbing the access by car to the interrow space

Preventive and corrective maintenance

The preventive maintenance program focuses mainly on the switchyard, inverters, combiner boxes, LV DC module, HV and MV transformers and weather station. No preventive actions are conducted on PV modules and DC cables. No corrective maintenance program has been shared with PI Berlin. PI Berlin could identify signs of bad module handling onsite




Figure 84: (left) Inaccurate module transport; (right) Footprints on the module surface

Availability calculation and SCADA monitoring

The system availability is only calculated on inverter level. The value is kept around 98%. The availability of the module strings is proved weekly using current clamps. All events registered during the PV plant operation are listed in a daily fault record specifying the root cause, time, date and follow up of each event.¹⁹ The SCADA system was installed 1 year after COD and visualizes only up to DC combiner box level. The SCADA system logs the inverter input and output parameters, the DC combiner box input and output parameters, the irradiation on the POA and the ambient temperature each 2min. The cell temperature is not measured.

5.3.8 Summary of the Results

The following table summarizes the failures detected onsite and the associated risks.

Table 3: Summary of the failures and the associated risks – Plant 3

Ref.	Item	Risk Description
1	Contracts	
1.1	Not existing O&M contract. Poor or not existing O&M warranties.	A typical O&M contract wasn't created since the Owner and Operator are the same entity. Hence, no standard O&M warranties based on Performance Ratio or system availability were formulated. The lack of O&M warranties leads to a comfortable scenario where the O&M team has no special incentive to force the PV plant to run at its maximum potential. The consequences are usually a lower availability and a lower output than expected.
1.2	Poor or not existing EPC warranties	The EPC warranty period is limited to 12 months, which is significantly shorter than the standard period of 24 months. Short EPC warranty periods are safer for the EPC and more risky for the Owner since the likelihood of detecting system failures while the warranty is active increases with the duration of the same. The warranties highlighted in the contract base only on a PR test which was not conducted according to standards.
2	PV Plant Design	
2.1	Inconsistent DC and AC power values.	The DC and AC power values specified in the project files are not consistent and show variations that introduce an uncertainty that influences the PR and P90 calculations. The exact definition of the nominal power is crucial for a correct assessment of the system performance.
2.2	Low overbuilt	The tender specifications ²⁰ allow a PV plant design with an overbuilt higher than 1 as long as the AC capacity is not exceeded. However, the selected capacity is very close to 1 which leads to waste AC capacity even though the partial load behavior of the inverter is more efficient.
2.3	Missing statics	The module fixation doesn't seem to be suitable for the applicable wind loads, considering the reported damaged caused by strong winds. This evidence represents a high risk for the entire PV plant and may lead to a significant reduction of the system performance.
3	Electromechanical Installation	
3.1	Mounting structure	
3.1.1	Rust on the mounting structure components	The rust can lead to a reduction of the structural strength of the mounting structure, especially in combination with strong wind.
3.1.2	Poor module fixation	The module clamps are unsuitable for PV applications and do not ensure the proper fixation of the modules to the mounting structure. In case of strong wind, the modules might suffer severe damages. Apart from this, the micro-shadings caused by the clamps have an influence on the module performance.
3.1.3	No row labelling	The missing row labelling makes the correct identification of the various areas of the plant more difficult, leading to increased reaction times during corrective maintenance.
3.2	Combiner boxes	
3.2.1	Cable glands not sealed	Not sealed cable glands allow dust and dirt entering the combiner box housing. This is especially critical in desert areas with a high amount of dust in the air combined with winds carrying sand and dirt particles.
3.2.2	Dust and dirt inside the housing	The presence of dust and dirt inside the combiner boxes can lead to the development of micro-organisms and possible corrosion and chemical reactions that damage the electrical components inside the housing. Additionally, the dust tends to grip the electrical protections such as fuse holders and breakers limiting their functionality.
3.2.3	No labelling of the boxes.	The missing combiner box labelling makes the correct identification of the various areas of the plant more difficult leading to increased reaction times during corrective maintenance. Additionally, electrical parts that aren't properly labelled hide safety risks when manipulated by the O&M members.

¹⁹ PI Berlin has reviewed the file "Checklist XXXX.xlsx" sent by the Owner on the 20th June 2017.

²⁰ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013

3.3	Cables	
3.3.1	Mechanical damage visible	The contact of the cables with the sharp edges of the mounting structure may cause damages in the shield of the cables leading to insulation loss of the electrical circuit.
3.3.2	Poor or not existing labelling of the DC cables	A nondurable or not existing cable labelling makes the correct identification of the various electrical circuits more difficult leading to increased reaction times during corrective maintenance. Additionally, the confusion caused by the missing tags and labels represents a safety issue for the O&M staff during preventive and corrective maintenance.
3.3.3	Open connectors	Connectors not properly closed have an increased local resistance between the male and female connectors leading to an increase fire risk. Open connectors have been detected at several locations of the plant.
3.3.4	Poor cable fixation	Hanging cables due to nondurable cable ties are exposed to mechanical damage caused by the wind and the friction against other components such as the mounting structure or the module frames.
3.3.5	Insufficient bending radius	Not respecting the bending radius specified by the cable manufacturer leads to the loss of the product warranty and an increased risk of shield damage. Damaged cable shields are responsible for insulation losses and associated safety issues.
3.3.6	Poor or insufficient UV protection	The cables should not be exposed to the direct sunlight since the long term durability of the cable shield may be affected. This effect was detectable mainly in the gaps between the mounting tables and in the interrow spaces.
3.3.7	No sealing of pipes	Sealing the pipes and tubes helps protecting the cables from water and dirt accumulation as well as mechanical damage caused by small animals. No foam was used to seal the pipes.
3.3.8	Not suitable tubes for outdoor	The tubes used for routing the cables should be suitable for outdoor conditions and withstand the action of humidity, rain and UV radiation among others. Not fulfilling these conditions makes these tubes useless in the midterm leaving the cables without protection.
3.4	Inverter	
3.4.1	Presence of dust inside the room, dirty filters	The significant amount of dust inside the inverter room may affect on the one hand the electrical protection devices by causing grip and limiting their functionality, and on the other hand the presence of dust tends also to block the filters reducing the heat evacuation capacity of the ventilation system. A poor ventilation system is critical for the long term durability of the inverter.
3.4.2	Cooling concept not comprehensive	The absence of a thermostat that avoids the room temperature to exceed certain limits is compensated with a ventilation fan that is connected manually. The temperature control should be fully automatized since the manual action does not ensure a proper control and judgement of the cooling demand.
3.5	Grounding and equipotential bonding system	
3.5.1	Continuity not ensured due to corrosion	The continuity of the equipotential bonding system is not given due to the severe damages of the equipotential bonding conductor buried in the ground. The rust appears due to a corrosion process triggered by the salty environment in combination with heat and humidity. The rust is responsible for an increase of the resistance of the belts, which leads to an increased voltage drop when the fault current flows through the rusted conductor. As rust develops, the voltage drop increases limiting the correct functionality of the equipotential bonding system losing its capacity to protect against uneven potentials.
3.5.2	Belt not buried	The equipotential bonding conductor (belt) should be buried at a depth according to the applicable norms (typically around 60cm) in order to avoid safety issues due to possible interactions between personnel and fault currents flowing through the conductor. Additionally, the conductor should be buried in order to avoid mechanical damages caused by vehicles and machinery.
3.6	Documentation	
3.6.1	Missing construction progress reports	The installation phase reports are very helpful during O&M as they include valuable information of one of the most relevant phases of the project. Not having access to this information means losing part of the history of the plant.
4	Commissioning	
4.1	Insufficient commissioning tests. No compliance with the IEC 62446	One of the most relevant EPC warranties is the performance warranty which is typically expressed as a PR test to be conducted during an agreed amount of days at PAC and FAC. This test was conducted at PAC but the applied methodology shows deviations towards the established standards. In regards to the commissioning requirements specified by the IEC 62446, no tests have been conducted. The commissioning process complies with the tender requirements specified by SECI. The present scenario shows a PV plant that was not commissioned according to the best practices, neither in terms of performance validation, nor in terms of safety.
5	System Performance	
5.1	BOM of the weather station not complete	The cell temperature and the global horizontal irradiation (GHI) are not measured onsite. These parameters are an essential part of a correct meteorological data assessment of an operating plant. The cell temperature is especially important for conducting a PR

		correction, which is a crucial step for a proper comparison between the onsite PR and the contractual PR.
5.2	Installation failures detected	The excessively long arm that supports the pyranometer oscillates with the wind. The accuracy of the registered data can thus be affected.
5.3	Poor or no PR calculation conducted onsite	Due to the fact that the SCADA system was installed one year after COD, the PR calculation during the first year could not be performed. Thus, the performance history of the first operational year is lost.
6	PV Module Quality	
6.1	Presence of module and cell cracks due to bad module handling	The snail trails detected on site are an evidence of the presence of cell cracks which can be confirmed with infrared and electroluminescence technology. These cracks show the typical pattern of damages caused by bad module handling during the construction phase. Cracks may lead to performance losses as they develop further, and to hot spots when parts of the cells are isolated by the cracks. The strong winds registered onsite may contribute to a faster development of the cracks due to the dynamic loads associated to them. Further signs of bad module handling are the presence of mud in the backsheet or footprints on the module surface. Both effects were present on site.
6.2	Presence of burned cells	Burned cells might be responsible for fire events. Thus, the affected modules should be replaced immediately.
6.3	Presence of manufacturing failures	Failures such as inaccurate soldering of the ribbons or misalignment of the module junction boxes point towards lack of quality inspection programs at certain stages of the value chain. In the specific case of the inaccurate soldering, the further development of the hot spots visible along the busbars, can lead to a permanent damage of the module or even to fire events.
6.4	Presence of scratched backsheets	Some modules showed scratches in the backsheet, pointing towards clear signs of bad module handling. This failure leads to the loss of the required insulation value of the electrical circuits and eventually to cell cracks combined with corrosion at the location of the scratches. This effect is especially critical in areas with high humidity rates.
6.5	No specific certificates beyond the basic IEC certification requested to the manufacturer	No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors present on site. The high temperature, UV load and humidity rates, as well as the effect of the sand as abrasive agent and the high salinity of the region, represent a threat for the PV modules in terms of long-term durability.
7	Operation and Maintenance	
7.1	Definition of the cleaning intervals without knowing the accumulated soiling losses between 2 periods	The losses due to soiling are not measured onsite. 2 cleaning rounds per month have been agreed without conducting a previous study on the accumulated soiling loss between 2 periods. As a consequence, the cleaning frequency is not adjusted to a defined soiling loss which should not be exceeded. Actually, due to the amount of cleaning rounds defined in advance, there might be some periods when the PV plant is "undercleaned" and others in which the PV plant is "overcleaned". In the first case performance is lost, while in the second case unnecessary costs are generated.
7.2	Lack of experience of the O&M team	The lack of experience of the O&M team may lead to a wrong diagnose of the detected failures, as well as to an inaccurate corrective maintenance, among other consequences. In order to maximize the performance and availability of the PV plant, the O&M team should be familiar with as many events as possible in all potential scenarios.
7.3	No evaluation of the impact of the cleaning concept on the module warranty	The impact of the selected cleaning methodology on the module warranty hasn't been analyzed. Several factors such as the material used for the wipers, the type of water used, the cleaning methodology, the water pressure and the physical and chemical properties of the dust and sand, might have an influence on the glass and the anti-reflective coating of the modules. Product damages or performance losses of any kind originated by the cleaning process are not covered by the product warranty unless the cleaning concept has been approved previously by the module manufacturer. This step was not given before starting the operational phase.
7.4	Preventive maintenance not adjusted to the PV technology	The preventive maintenance program focuses mainly on the switchyard, inverters, combiner boxes, LV DC module, HV and MV transformers and weather station. No preventive actions are conducted on PV modules and DC cables, which are an essential part of the system. They require specific checklists which can't be recycled from other technologies.
7.5	No PV specific devices used onsite	Devices and tools used in the PV industry such as IV curve tracers, electroluminescence devices and infrared cameras help detecting and evaluating failures easily. The regular use of these devices is necessary during O&M for detecting and monitoring defects and degradation phenomena such as hot spots, cracks or PID.
7.6	Poor reporting	The reporting of the O&M activities should contain monthly and yearly reports specifying production data, availability values, spare parts managements, costs, outage time, preventive and corrective actions, trend analysis, meteorological data and accumulated production among other values. A poor reporting activity does not support a proper monitoring of the plant operation which is crucial for a successful asset management orientated to maximize the performance and operating hours. In this project only daily reports are generated.

5.4 Plant 4 - 100MW ground mounted (Rajasthan)

Date of inspection by PI Berlin AG	07.07.2017
Name and size of the plant	confidential, 100MW (ground mounted)
Coordinates	confidential
Commercial Operation Date (COD)	confidential
Name of the Owners	confidential
Name of the EPC	confidential
Name of the O&M company	confidential
<p>The 100MW PV plant is split in five 20MW projects and uses three different module types with an arrangement of 4 and 6 modules landscape. The modules are seasonally tracked in 3 projects while at the two others a fixed tilt solution is used. The strings contain between 16 and 24 modules in series and are connected over a DC combiner box to 1000kW inverters. 4 inverters are connected with 4R-1Cx300m² to a 0.38/33kV transformer of 3 or 4MVA. The 11kV line 1R-3Cx185mm² AL is connected to a common bar with 4R-3Cx300mm² AL leading to the substation. The level of injection is at 132kV. Each owner of the five 20MW blocks has signed a PPA with SECI for 25 years.</p>	

5.4.1 Contracts

Under this chapter PI Berlin has put the main focus on:

- EPC contract
- O&M contract
- Role of the Owner's Engineer
- Role of the Lender's Technical Advisor supporting the financing institution

The evaluation of the above mentioned points leads to the following outcomes:

- The new Owner has no access to the EPC contract signed between the previous owner and the EPC companies. Only the product warranties are in place at the moment.
- A PR test was agreed as part of the PAC process. However, the test hasn't been conducted yet and due to this reason, a claim is ongoing. The same case applies to the FAC. Besides the PR test, the EPC isn't forced to conduct any other test as per the IEC 62446.
- A typical O&M contract wasn't created since the Owner and Operator are the same entity. Hence, no standard O&M warranties based on Performance Ratio or system availability were formulated.
- No Owner's Engineer was appointed
- A consultant was involved as LTA at the time when the former owner was still active in the project. After the change of the owner, no LTA activity has been documented onsite.

5.4.2 PV Plant Design

This chapter analyses:

- Interrow shading based on the selected pitch and tilt
- Statics
- Location of inverters and combiner boxes
- Electrical overbuilt

Interrow shading based on the selected pitch and tilt

The pitch (lower edge-lower edge) is 6.9 m according to the as-built situation. This value was confirmed onsite by PI Berlin. PI Berlin has measured module tilt values very close to 5° in the manual tracked plants and 21° tilt in the fixed tilt plants. The values match the design criteria. The simulation values provided by the Owner in the project report corresponding to one 20MW block, indicate that the plant suffers a total annual performance loss of 1.3% due to shading²¹. This is caused by the interrow shading and near shading of the PCU buildings. No PV SYST simulation was provided by the Owner. The simulated losses and yield

²¹ PI Berlin has reviewed the file "DPR_AGPPPL-20MW-SPV-XXXX-11kV.pdf" sent by the Owner on the 17th July 2017

generation values of the other plants were not provided either.




Figure 85: Tracked and fixed tilt systems

Statics

No static calculations were shared with PI Berlin, hence the structural integrity of the mounting structure couldn't be proven. The mounting structures have been designed for a maximum wind speed of 47 m/s. However, the module fixation doesn't withstand the wind loads registered onsite.



Figure 86: PV modules damaged by strong winds

Location of inverters and combiner boxes

The inverters and distribution boxes are located considering cable and voltage drop reduction criteria. The cable runs do not exceed critical values even though the PCU concentrates close to 4MW DC capacity and only one distribution level has been planned on the DC side. This statement bases both on the onsite inspection as well as on the review of the as-built layouts provided by the Owner.²² The following screenshot of one of the inspected drawings shows the location of the inverters.

Electrical overbuilt

The selected overbuilt (DC/AC ratio) of 20% is considered as acceptable considering the environmental conditions present in the region and the selected components.

5.4.3 Electromechanical Installation

The quality of the electromechanical installation was assessed onsite by PI Berlin and focused on the following subsystems:

- Mounting structure
- Combiner boxes
- Cables fixation
- Inverter
- Grounding and equipotential bonding
- Civil work
- Documentation

²² PI Berlin has reviewed the file "DPR_AGPPPL-20MW-SPV-XXXX-11kV.pdf" sent by the Owner on the 17th July 2017

Mounting structure and module fixation

- i. **Module fixation:** The modules are properly fixed to the cross beams. The thin film modules installed in two 20MW blocks show occasionally micro-shading effects due to cell coverage through the clamps.




Figure 87: Module clamps shading the cells

- ii. **Labelling of rows:** The labelling of the mounting structure was conducted in the entire PV plant. Besides, the labels are durable for the entire lifetime of the project.



Figure 88: Labelling of the rows

- iii. **Foundation:** Sporadically, damages in the foundation were observed.



Figure 89: Sporadic damages in the foundation

Combiner boxes

- i. **Sealing of the cable glands:** The cable glands are properly sealed in all combiner boxes



Figure 90: Combiner box view

- ii. Cleanliness of the combiner box: The dust accumulation inside the combiner boxes is significant.



Figure 91: Dust inside the combiner boxes

- iii. Labelling of the combiner box: The DC combiner boxes are labelled with durable tags. The datasheets adhered to the combiner box enclosure do not withstand an outdoor exposure.



Figure 92: (left) Missing datasheet; (right) Combiner box labelling

Cables fixation and routing

- i. Cable damage: The cables do not show damages caused by external agents. However, some cables are in contact with sharp edges of the metallic cable trays, thus, an erosion of the cable shield can't be excluded in the midterm.



Figure 95: Improper cable fixation

- v. Bending radius: In general, the minimum bending radius of the cables was respected.
- vi. Protection against UV: In general the DC cables are protected from UV exposure by using pipes. In some cases however, the protection between module tables is missing.




Figure 96: (left) String cables protected from UV; (right) Missing UV protection

- vii. Sealing of tubes: The tubes conducting the DC cables to the inverter are sealed.




Figure 97: Accurate sealing of cable tubes

- viii. Cable pipes: The tubes where the cables are routed do not show degradation due to outdoor exposure.

Inverter

The inverter has an overvoltage protection on the AC side as well as a DC switch. The inverter room shows a significant amount of dust, especially in the filters. The inverter has a default ventilation system. The inverter room does not have a thermostat that regulates the temperature inside the housing. A forced ventilation system was installed inside the PCUs. The door is kept open to ensure natural convection. The inverter filters and air inlets are clean.



Figure 98: Inverter room



Figure 99: Dirty filters due to dust accumulation

Grounding and equipotential bonding

The equipotential bonding system connects all conductive parts of the PV plant as the mounting structure, module frames or housings. The equipotential bonding system is undamaged and doesn't show any signs of corrosion or rust. The equipotential bonding conductor is not properly buried. In some junctions, the continuity is not ensured in the long-term. In terms of Potential Induced Degradation (PID) avoidance, no measures have been taken, such as functional grounding of the negative pole. The PV plant does not show signs of PID.



Figure 100: Equipotential bonding system



Figure 101: Not buried equipotential bonding conductor

Civil work

The status of the internal roads is good. A drainage system was implemented on site. The drainage channels are not well maintained in all areas of the plant. According to the Owner and Operator of the plant, the terrain has problems absorbing high amounts of rainwater.



Figure 102: Drainage system



Figure 103: Internal roads

Documentation

In terms of completeness, the provided documents comply with most of the requirements of the IEC 62446. The Owner didn't receive any progress reports from the previous owner.

5.4.4 Commissioning

PI Berlin considers the commissioning process conducted at the end of the installation phase a crucial milestone in the deployment of a PV project. The commissioning process as per IEC 62446 is divided in "cold" and "hot" commissioning, and ends with the issuance of the Provisional Acceptance Certificate, and is the last step before the EPC warranty starts. This process gives an idea of the status of the plant in terms of

safety and functionality. In the case of the 5x20MW PV plant, a proper commissioning of the PV plant as specified in the IEC 62446 was not conducted prior to COD. The only test formulated in the EPC contract is a PR test that is still pending. PI Berlin had no access to the PR test requirements and methodology description. Besides the contractual conditions described in the EPC contract, and according to the tender requirements of SECI²³, the official commissioning is approved after the submission of a short document issued by the State Nodal Agency of Rajasthan containing the installed capacity, an electrical inspector report, the connectivity report, the synchronization certificate, photographs and an installation report.

5.4.5 System Performance

In this chapter PI Berlin analyses several factors that influence the calculation of the system performance.

Weather station status and sensor accuracy

PI Berlin had access to the readings of the irradiation and temperature data of the installed sensors. The values are consistent.²⁴ According to the Owner, the sensors are calibrated each 24 months. No calibration certificates were provided to PI Berlin




Figure 104: (left) Module temperature sensor; (right) Weather station

The weather station of each 20MW block is constituted by a pyranometer on the tilted plane (POA), a pyranometer on the horizontal surface (GHI), a module temperature sensor, a cell temperature and an anemometer. One value is recorded each 10min. In some weather stations the GHI sensor is missing. No redundancy was considered. Due to the fact that both pyranometers are installed close to each other and one is higher than the other, a reduction of the diffuse light absorption in the lower pyranometer can't be excluded.



Figure 105: Pyranometers on the horizontal and tilted surface

²³ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013

²⁴ PI Berlin has reviewed the files "Data 2015.xlsx", "Data 2016.xlsx", "Data 2017.xlsx" and "Temperature Reading.xlsx" sent by the Owner on the 8th July 2017

Performance Ratio calculation

The production on monthly basis since COD, is properly documented. In compliance with the tender requirements specified by SECI²⁵, the minimum CUF 17% is met so far according to the Owner. The PR is calculated using the irradiation values registered by the pyranometer and the metered production. PI Berlin had no access to daily or monthly PR values. The simulated output of the one 20MW blockt using PV SYST data and shown in the project report²⁶ is plausible and well documented. A similar analysis for the other 4 plants was not shared with PI Berlin.

5.4.6 PV Module Quality

The PV modules represent the most sensitive part of the PV plant, especially in harsh climates with high UV loads, high temperatures, high humidity rates, abrasion and presence of sand and dust. These environmental stressing factors are present on site whose climate is classified as BWh according to Köppen-Geiger [21]. In order to assess the quality of the modules, PI Berlin has conducted a visual inspection, an infrared analysis and an electroluminescence inspection using the equipment specified in Annex IV. The investigated aspects are listed as follows:

Results of the visual inspection

The visual inspection on the modules showed clear signs of snail trails. Some modules are also affected by corrosion originated by moisture ingress through the damaged edge sealing. The damage is caused by improper handling. No other relevant defects were detected by PI Berlin.

According to the Owner the flash lists of the PV modules are available, however these were not shared with PI Berlin.




Figure 106: PV modules showing snail trails




Figure 107: PV modules affected by corrosion

²⁵ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013

²⁶ PI Berlin has reviewed the file "DPR_AGPPL-20MW-SPV-XXXX-11kV.pdf" sent by the Owner on the 17th July 2017

Long term durability certificates

No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors mentioned above.

Infrared analysis

The infrared inspection didn't show major problems besides some sporadic hot spots and inactive cell strings both in the crystalline modules.




Figure 108: PV modules affected by inactive cell strings






Figure 109: PV modules affected by hot spots

Electroluminescence analysis



The electroluminescence analysis on a selected amount of crystalline PV modules confirmed the presence of cell cracks. The same analysis conducted on the thin film modules showed a high shunt sensitivity caused by shading.




Sr.Nr.: confidential
Figure 110: Broken PV module




Sr.Nr.: confidential
Figure 111: PV modules affected by inactive cell strings



Sr.Nr.: confidential
Figure 112: PV modules affected by cell cracks evidenced by snail trails





Sr.Nr.: confidential Sr.Nr.: confidential
Figure 113: (left) (before shading); (right) after shading

5.4.7 Operation and Maintenance

The quality of the Operation and Maintenance service has been evaluated considering the points listed below. PI Berlin had the chance to interview a few members of the O&M team while conducting the site visit.

Experience of the O&M team

The Operator has vast experience in the O&M of PV plants. 50 people are involved in the O&M of this plant and 40 people in the security. The O&M members are allowed to operate MV components of the plant.

Cleaning methodology and calculation of the soiling loss

According to the Owner and Operator, the module cleaning is performed 2 times a month using cotton wipers and underground water. The applied water pressure is 5kg/cm².



Figure 114: Module cleaning system

The impact of the selected cleaning methodology on the module warranty hasn't been analysed. According to the Operator, the cleaning is performed after the inverters shut down. The cleaning campaign is properly recorded specifying which tables are cleaned which day.²⁷ The losses due to soiling are not measured onsite. 2 cleaning rounds per month have been agreed without conducting a previous study on the actual needs. PI Berlin observed that the remaining water on the PV module surface after conducting the cleaning attracts dust and dirt particles accelerating the soiling storage on the PV module.

²⁷ PI Berlin has reviewed the file "Module Cleaning Schedule.pdf" sent by the Owner on the 7th July 2017.



Figure 115: Dust accumulated on the remaining water after the cleaning process

The losses due to soiling were quantified by PI Berlin using an IV-curve tracer with the specifications shown in Annex IV. The soiling losses vary depending on the module technology, the tilt and the degree of soiling among others.



Figure 116: Module cleaned

The soiling measurements were conducted at three sample locations and the results are shown below:

Table 4: Soiling measurements conducted by PI Berlin

PV module	Module type 1	Module type 1	Module type 3
20 MW block	1	1	2
Tilt	5°	21°	21°
Soiling loss	3,61%	2,70%	2,13%

These values correspond to the accumulated losses after the last rainfall which happened 3 days before the site visit. The results show an increase of the losses with a reduction of the tilt and also a better behavior of

the thin film modules compared to the c-Si technology. According to the infrared analysis conducted by PI Berlin onsite, the soiling accumulation on the module surface leads to soiling induced hotspots as shown in the pictures below.




Figure 117: Soiling induced hot spots

Tools used on site

The O&M team uses current clamps, multimeters, IR camera and insulation measurement devices among others. No PV specific tools and devices are used onsite except the infrared camera.



Figure 118: Tools used during the O&M activities

Reporting and reaction times

At the time of the visit, PI Berlin had the chance to inspect the O&M reports issued by the team which can be described as comprehensive and detailed. According to the Operator, the failure detection time is kept below 5min for all failures. One O&M worker is permanently visualizing the SCADA. No O&M reports were issued until the new investor acquired the project.

Preventive and corrective maintenance

The preventive maintenance is very comprehensive and includes several checklists and forms for all system components such as DC cables, connectors, modules, switchyard, inverters, combiner boxes, LV DC module, HV and MV transformers, grounding system, UPS and weather station. A selection of corrective maintenance documents were shown to PI Berlin onsite. Every action taken by the O&M team is documented. Some sporadic shading due to vegetation was detected. 2 vegetation cuts are conducted each year.



Figure 119: Vegetation growth

Availability calculation and SCADA monitoring

The system availability is only calculated on inverter level. The value is kept above 99%. The SCADA system monitors up to DC combiner box level and the most important parameters are logged. One person is permanently in charge of visualizing the SCADA system. All events registered during the PV plant operation are listed in a daily fault record. A detailed description of the root cause, time, date and follow up of each event is missing.

Curtailement and grid stability

According to the plant Operator the curtailment losses originated by the DSO are less than 3% per year. According to the plant Operator the PV plant is not forced to support actively the grid.

5.4.8 Summary of the Results

The following table summarizes the failures detected onsite and the associated risks.

Table 5: Summary of the failures and the associated risks – Plant 4

Ref.	Item	Risk Description
1	Contracts	
1.1	Not existing O&M contract. Poor or not existing O&M warranties	A typical O&M contract wasn't created since the Owner and Operator are the same entity. Hence, no standard O&M warranties based on Performance Ratio or system availability were formulated. The lack of O&M warranties leads to a comfortable scenario where the O&M team has no special incentive to force the PV plant to run at its maximum potential. The consequences are usually a lower availability and a lower output than expected.
1.2	Poor or not existing EPC warranties	The handover from the previous owner to new one didn't happen in a smooth way. As a consequence, the new owner had no access to the EPC contract which might have been still valid at the time of handover. Besides, the PR test defined as part of the EPC warranty, has not been conducted yet leading to an ongoing claim. As a result, the actual scenario shows a contract violation (no PR test conducted) combined with a non-transparent handover where the validity of the former contract agreements is questionable.
1.3	No appointment of an Owner's Engineer	The OE has the task to support the Owner's interests against the EPC and the various product suppliers. The OE conducts independent checks and verifications starting at the earlier phases of the EPC tendering and ending after commissioning or beyond. The absence of an experienced OE as an independent party, may lead to an increased risk for the Owner. In this project, the services of an OE were not requested even though the quality assurance services provided by an OE are highly recommended in order to avoid mistakes in all stages of the value chain.
1.4	No appointment of a Lender's Technical Advisor	The LTA supports the interests of the bank as the financing institution. Accordingly, the bank is interested in financing projects which are bankable and are exposed to low risks. Thus, the task of the LTA is to ensure the bankability of the project by supervising that all steps made by the Developer (very often also the Owner at the same time) lead to a low risk scenario. An LTA was hired during development and construction and left the project after the change of the Owner. The plant has currently no LTA involved.
2	PV Plant Design	
2.1	Missing statics	The module fixation doesn't seem to be suitable for the applicable wind loads, considering the reported damages caused by strong winds. This evidence represents a high risk for the entire PV plant and may lead to a significant reduction of the system performance.
3	Electromechanical Installation	

3.1	Mounting structure	
3.1.1	Poor module fixation	The micro-shadings caused by the clamps used for fixing the thin film modules have an influence on the module performance.
3.2	Combiner boxes	
3.2.1	Dust and dirt inside the housing	The presence of dust and dirt inside the combiner boxes can lead to the development of micro-organisms and possible corrosion and chemical reactions that damage the electrical components inside the housing. Additionally, the dust tends to grip the electrical protections such as fuse holders and breakers limiting their functionality.
3.2.2	Loss of adherence of the datasheets attached to the housings	The tags and datasheets attached to the housing are losing adherence. The missing combiner box labelling makes the correct identification of the various areas of the plant more difficult leading to increased reaction times during corrective maintenance. Additionally, electrical parts that aren't properly labelled hide safety risks when manipulated by O&M members.
3.3	Cables	
3.3.1	Mechanical damage visible	The contact of the cables with the sharp edges of the mounting structure may cause damages in the shield of the cables leading to insulation loss of the electrical circuit.
3.3.2	Poor cable fixation	Hanging cables due to nondurable cable ties are more exposed to mechanical damage caused by the wind and the friction against other components such as the mounting structure or the module frames.
3.3.3	Poor or insufficient UV protection	The cables should not be exposed to the direct sunlight since the long term durability of the cable shield may be affected. This effect is seen sporadically in the gaps between the mounting tables.
3.4	Inverter	
3.4.1	Presence of dust inside the room, dirty filters	The significant amount of dust inside the inverter room may affect on the one hand the electrical protection devices by causing grip and limiting their functionality, and on the other hand the presence of dust tends also to block the filters reducing the heat evacuation capacity of the ventilation system. A poor ventilation system is critical for the long term durability of the inverter.
3.4.2	Cooling concept not comprehensive	No thermostat that avoids the room temperature to exceed certain limits was installed. The temperature control should be fully automatized and the door of the inverter room should be kept closed in order to avoid the heat and dust entering the room.
3.5	Grounding and equipotential bonding system	
3.5.1	Continuity not ensured due to corrosion	The continuity of the equipotential bonding system is not given due to the appearance of rust in the equipotential bonding conductor buried in the ground. The rust appears due to a corrosion process triggered by the salty environment in combination with heat and humidity. The rust is responsible for an increase of the resistance of the belts, which leads to an increased voltage drop when the fault current flows through the rusted conductor. As rust develops, the voltage drop increases limiting the correct functionality of the equipotential bonding system losing its capacity to protect against uneven potentials.
3.5.2	Belt not buried	The equipotential bonding conductor (belt) should be buried at a depth according to the applicable norms (typically around 60cm) in order to avoid safety issues due to possible interactions between personnel and fault currents flowing through the conductor. Additionally, the conductor should be buried in order to avoid mechanical damages caused by vehicles and machinery.
3.6	Documentation	
3.6.1	Missing construction progress reports	The installation phase reports are very helpful during O&M as they include valuable information of one of the most relevant phases of the project. Not having access to this information means losing part of the history of the plant.
4	Commissioning	
4.1	Insufficient commissioning tests. No compliance with the IEC 62446	One of the most relevant EPC warranties is the performance warranty which is typically expressed as a PR test to be conducted during an agreed amount of days at PAC and FAC. This test wasn't conducted at PAC even though it was specifically mentioned in the EPC contract. A claim is ongoing due to this reason. In regards to the commissioning requirements specified by the IEC 62446, no tests have been conducted. The present scenario shows a PV plant that was not commissioned according to the best practices, neither in terms of performance validation, nor in terms of safety. The commissioning process complies with the tender requirements specified by SECI.
5	System Performance	
5.1	Installation failures detected	Due to the fact that both pyranometers (GHI and POA) are installed close to each other and one is higher than the other, a reduction of the diffuse light absorption in the lower pyranometer can't be excluded. Thus, the accuracy of the readings could be affected.
5.2	No cell temperature correction of the PR	The cell temperature even if recorded, it's not used for conducting a PR correction, which is a crucial step for a proper comparison between the onsite PR and the contractual PR.
6	PV Module Quality	

6.1	Presence of module and cell cracks due to bad module handling	The snail trails detected on site are an evidence of the presence of cell cracks which can be confirmed with infrared and electroluminescence technology. These cracks show the typical pattern of damages caused by bad module handling during the construction phase. Cracks may lead to performance losses as they develop further, and to hot spots when parts of the cells are isolated by the cracks. The strong winds registered onsite may contribute to a faster development of the cracks due to the dynamic loads associated to them.
6.2	Corrosion due to moisture ingress	The glass-glass modules show damages at the corners, which lead to the ingress of moisture triggering a corrosion process in the cells. The further development of the corrosion process and the associated performance loss of the module can't be excluded. The root cause of these damages is bad handling.
6.3	Presence of shunts	The thin film modules have a high sensitivity towards shading, which leads to the development of shunts as soon as the module cells are shaded. The shunts reduce the active surface of the cells. Thus, the shading of the cells should be avoided in any case, which is difficult to fulfill during cleaning or replacement actions.
6.4	No specific certificates beyond the basic IEC certification requested to the manufacturer	No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors present on site. The high temperature, UV and humidity rates, as well as the presence of sand as an abrasive agent, represent a threat for the PV modules in terms of long-term durability.
7	Operation and Maintenance	
7.1	Definition of the cleaning intervals without knowing the accumulated soiling losses between 2 periods	The losses due to soiling are not measured onsite. 2 cleaning rounds per month have been agreed without conducting a previous study on the accumulated soiling loss between 2 periods. As a consequence, the cleaning frequency is not adjusted to a defined soiling loss which should not be exceeded. Actually, due to the amount of cleaning rounds defined in advance, there might be some periods when the PV plant is "undercleaned" and others in which the PV plant is "overcleaned". In the first case performance is lost, while in the second case unnecessary costs are generated.
7.2	No evaluation of the impact of the cleaning concept on the module warranty	The impact of the selected cleaning methodology on the module warranty hasn't been analyzed. Several factors such as the material used for the wipers, the type of water used, the cleaning methodology, the water pressure and the physical and chemical properties of the dust and sand, might have an influence on the glass and the anti-reflective coating of the modules. Product damages or performance losses of any kind originated by the cleaning process are not covered by the product warranty unless the cleaning concept has been approved previously by the module manufacturer. This step was not given before starting the operational phase.
7.3	No PV specific devices used onsite	Devices and tools used in the PV industry such as IV curve tracers, electroluminescence devices and infrared cameras help detecting and evaluating failures easily. The regular use of these devices is necessary during O&M for detecting and monitoring defects and degradation phenomena such as hot spots, cracks or PID.

5.5 Plant 5 - 30 MW ground mounted (Madhya Pradesh)

Date of inspection by PI Berlin	11.07.2017
Name and size of the plant	confidential, 30MW (ground mounted)
Coordinates	confidential
Commercial Operation Date (COD)	confidential
Name of the Owner	confidential
Name of the EPC	confidential
Name of the O&M company	confidential
<p>The 30 MW PV plant uses two different c-Si module types, part of it contains also a-Si modules. The crystalline modules are installed on a horizontal E-W tracking system with a tracking range of $\pm 45^\circ$. The strings contain 21 modules in series and are connected in pairs to 12 input DC combiner boxes. 10 combiner boxes are connected with an Rx1Cx300mm² 1.1kV Al cable and protected with 315A fuses prior to the LV DC module. 7 outputs lead to a 1,474kW inverter that operates in master/slave mode. The 3-phase output with 8R-1Cx300mm² leads to a 0.38/11kV transformer of 1.5MVA or 3.2MVA. The level of injection is at 33kV. The Owners have signed a 25 year PPA with SECI.</p>	

5.5.1 Contracts

Under this chapter PI Berlin has put the main focus on:

- EPC contract
- O&M contract
- Role of the Owner's Engineer
- Role of the Lender's Technical Advisor supporting the financing institution

The evaluation of the above mentioned points leads to the following outcomes:

- Only product warranties and 2 years civil work guarantee exist in written form between the EPC and the Owner. However, since the main EPC went bankrupt, there seems to be a legal gap that released the EPC from his obligations. Between the main EPC and the subcontracted EPC, some warranties were agreed whose validity are also questioned due to the bankruptcy of the main EPC. The Operator did not share with PI Berlin the list of the specified tests and its results. No warranties in regards to FAC were agreed according to the Operator.
- The Developer purchased the modules, inverters, trackers and the weather station. All remaining components were bought by the subcontracted EPC.
- A typical O&M contract wasn't created since the owner and operator are the same entity. Hence, no standard O&M warranties based on Performance Ratio or system availability were formulated. The only requirement that applies is an availability of 97% on inverter level.
- According to the Operator, the Owner's Engineer appointed during development and construction was an Indian company and the name was not shared with PI Berlin.
- A consultancy company was hired by the bank as Lender's Technical Advisor

5.5.2 PV Plant Design

This chapter analyses:

- Interrow shading based on the selected pitch and tilt
- Statics
- Location of inverters and combiner boxes
- Electrical overbuilt

Interrow shading based on the selected pitch and tilt

The pitch (lower edge-lower edge) is 5.5m according to the design. This value was confirmed onsite by PI Berlin. The E-W tracking range of the solar tracker is $\pm 45^\circ$. Due to the considerable height difference between the trackers in N-S an additional mutual shading loss can't be excluded. The reason for this height difference is the fact that the installation manual of the tracker specifies 1° as the maximum N-S slope²⁸. In order to meet this condition, the installation company adjusted the foundation height in order to absorb the terrain slope that is significantly higher than 1° in some areas of the plant.




Figure 120: Height difference between the tracker units

Statics

No static calculations were shared with PI Berlin, hence the structural integrity of the mounting structure couldn't be proven. However, a few deviations from the installation manual were detected. On the one hand the cantilever arm at the end of the tracker unit is 3.5m long which exceeds the dimensions specified in the installation manual. This length is the result of conducting the anchorage of each tracker unit to the ground with only 6 foundation piles instead of 8 as prescribed in the manual. Additionally, the modules are fixed to the tracker using only one crossbeam, while the installation manual recommends two.




Figure 121: (left) Real length of the cantilever; (right) Module fixation using two crossbeams according to the installation manual

²⁸ PI Berlin reviewed the file "8.XXXX Tracker Installation Manual RevD:pdf" provided by the Operator on the 24th July 2017

Location of inverters and combiner boxes

The location of the PCUs containing the inverters, transformers and MV switchgear was not selected considering voltage drop minimization. The cable runs are long enough to exceed 3% of voltage drop between some combiner boxes and the corresponding inverter²⁹. Additionally, the resulting voltage difference between combiner boxes located close and other located far away from the inverter may lead to a voltage mismatch on inverter level. The following screenshot of one of the reviewed drawings³⁰ shows with red dots the location of the inverters and how long the cable runs are on the DC side.




Figure 122: Location of the inverters

Electrical overbuilt

The DC capacity of the plant is 31.00608MWp while the AC capacity is labelled as 29.4MW. The resulting DC/AC ratio is close to 5%. The tender specifications³¹ allow a PV plant design with an overbuilt higher than 1 as long as the AC capacity is not exceeded. However, the selected capacity is very close to 1 which leads to waste AC capacity even though the partial load behaviour of the inverter is more efficient.

5.5.3 Electromechanical Installation

The quality of the electromechanical installation was assessed onsite by PI Berlin evaluating the following subsystems:

- Mounting structure
- Combiner boxes
- Cables fixation
- Inverter
- Grounding and equipotential bonding
- Civil work
- Documentation

Mounting structure and module fixation

- i. Module fixation: The modules are properly fixed to the cross beams.

²⁹ PI Berlin reviewed the file "DC CABLE SCHEDULE AND LOSS CALCULATION.pdf" sent by the Owner on the 8th July

³⁰ PI Berlin reviewed the file "12- OVERALL SITE PLAN--OVERALL PLANT LAYOUT.pdf" sent by the Owner on the 8th July

³¹ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013



Figure 123: Fixation of the modules to the tracker

- ii. Labelling of rows: The labelling of the mounting structure was conducted in the entire PV plant. Besides, the labels are durable for the entire lifetime of the project.



Figure 124: Labelling of the trackers

- iii. Rust on the mounting structure surface: The mounting structure doesn't show signs of rust.



Figure 125: Good surface status of the tracker structure

- iv. Status of the motors and dampers: Both elements are in a good shape and no not show signs of deterioration.



Figure 126: (left) Dampers of the tracking system; (right) Motor of the tracking system

Combiner boxes

- i. Sealing of the cable glands: The cable glands are properly sealed in all combiner boxes



Figure 127: Sealing of the cable glands inside the DC combiner boxes

- ii. Cleanliness of the combiner box: The combiner boxes are clean inside.




Figure 128: Clean DC combiner box

- iii. Labelling of the combiner box: The DC combiner boxes are clearly labelled. The tags are starting to bleach. The torques are marked in the screws of all electrical connections.




Figure 129: (left) Torque marking; (right) Bleaching of the combiner box labels

- iv. Protection: Overvoltage protection and DC main switch is included inside the DC combiner boxes. Only the positive pole is protected with 30A fuses.



Figure 130: View of the DC combiner box

Cable fixation and routing

- i. Cable damage: The cables do not show damages caused by external agents. However, some cables are in contact with rocks and stones, thus, an erosion of the cable shield can't be excluded.



Figure 131: Cable ducts covered with stones

- ii. Labelling of cables: Both the strings cables entering the combiner box and the main DC cables connecting the combiner box with the inverter, are properly labelled. In both cases the used tags seem to be durable for the whole lifetime of the project.



Figure 132: Labelling of the string cables

- iii. Connectors: The connectors are in general in a good shape.



Figure 133: MC4 connectors

- iv. Cable fixation: The cables ties used for the cable fixation are not suitable for outdoor exposure and start falling apart.




Figure 134: Fixation of the string cables

- v. Bending radius: In general, the minimum bending radius of the cables was respected.
- vi. Protection against UV: The cables are protected from UV light. Sporadically, some string cables are directly exposed to the sun.



Figure 135: (left) UV protection of the string cables; (right) Missing UV protection of the string cables

- vii. Sealing of tubes: The tubes conducting the DC cables to the inverter are sealed. However, the used foam doesn't seem to be durable.



Figure 136: Sealing of the cable ducts

- viii. Cable pipes: The tubes where the cables are routed do not show degradation due to outdoor exposure.



Figure 137: Cable pipes used for the string cable routing

Inverter

The inverter is based on 7 modular units building a master-slave concept. It has an overvoltage protection on the AC side as well as a DC switch. The PCU is clean, no significant amount of dust has been detected. The inverter has a default ventilation system. The inverter room does not have a thermostat that regulates the temperature inside the housing. A forced ventilation system was installed inside the PCUs. The inverter filters and air inlets are clean.



Figure 138: Central inverter



Figure 139: (left) Filters of the inverter room; (right) Ventilation system inside the inverter room

Grounding and equipotential bonding

The equipotential bonding system connects all conductive parts of the PV plant as the tracker, module frames or housings. The equipotential bonding conductor is not properly buried and does not comply with the requirement that specifies a minimum depth of 60cm. No signs of rust or corrosion were observed. The negative pole of the generator is grounded with a GFDI kit in order to avoid the development of PID.



Figure 140: Equipotential bonding conductor not buried



Figure 141: Equipotential bonding system

The earthing, lightning protection and resistivity calculations are traceable and properly conducted.

Civil work

The status of the internal roads is good. A drainage system was implemented on site. The drainage channels aren't kept clean. According to the Owner and Operator of the plant, the terrain has problems to absorb high amounts of rainwater during heavy rainfalls registered on site.



Figure 142: Drainage system

Documentation

In terms of completeness, the provided documents comply with most of the requirements of the IEC 62446. No progress reports are available according to the Operator.

5.5.4 Commissioning

PI Berlin considers the commissioning process conducted at the end of the installation phase a crucial milestone in the deployment of a PV project. The commissioning process as per IEC 62446 is divided in "cold" and "hot" commissioning, and ends with the issuance of the Provisional Acceptance Certificate, and is the last step before the EPC warranty starts. This process gives an idea of the status of the plant in terms of safety and functionality. Between the main EPC and the subcontracted EPC, some warranties were agreed whose validity is questioned due to the bankruptcy of the main EPC. No warranties in regards to FAC were agreed according to the Operator. Independently of what was stated in the EPC contract, the project developer conducted internal tests to verify the safety of the plant. These tests include earthing/ground resistance check, string tests and checks of the modules, tracker, combiner box, LVDC module, inverters, transformer, MV switchgear and substation among others. The testing protocols were not shared with PI Berlin. These tests do not fully comply with the IEC 62446 requirements.

Besides the contractual conditions described in the EPC contract, the official commissioning was approved following the specifications of the tender documentation³². The requirements included the submission of the

³² Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013

electrical inspector report, the connectivity report issued by the Discom authority, a confirmation of compliance from SECI, a synchronization certificate issued by the Discom authority, snapshots of the plant, plant layout, SLD and meter readings submitted by the Solar Project Developer, and an installation report also submitted by the Solar Project Developer.

5.5.5 System Performance

In this chapter PI Berlin analyses several factors that influence the calculation of the system performance.

Weather station status and sensor accuracy

The 3 weather stations installed onsite are constituted by a pyranometer on the tilted plane, a pyranometer on the horizontal surface (GHI), a module temperature sensor, a cell temperature and an anemometer. The metal arm fixing the pyranometer to the mounting structure is too long leading to an oscillation of the sensor when the wind blows. One value is recorded each minute. According to the Owner, the sensors are calibrated each 2 years. The calibration certificates were provided to PI Berlin. The readings of the irradiation and temperature sensors show gaps due to communication problems due to the weak internet connection onsite.



Figure 143: (left) Weather station; (right) Pyranometer

Performance Ratio calculation

The PR is calculated using the irradiation values registered by the pyranometer and the metered production. However, the PR calculated by the SCADA system is very unprecise due to the lack of data caused by communication failures. The calculated PR value can oscillate from one day to the next from 59% to 198% which is physically impossible³³. According to the tender requirements specified by SECI the minimum CUF shall not be below 17%. Evidences showing that the plant is fulfilling this condition haven't been shared with PI Berlin. No soiling losses are calculated onsite. This calculation would help to evaluate the PR without the influence of dust and dirt accumulated on the module surface.

5.5.6 PV Module Quality

The PV modules represent the most sensitive part of the PV plant, especially in harsh climates with high UV loads, high temperatures and high humidity rates. These environmental stressing factors are present on site whose climate is classified as BSh according to Köppen-Geiger [21]. In order to assess the quality of the modules, PI Berlin has conducted a visual inspection, an infrared analysis and an electroluminescence inspection using the equipment specified in Annex IV. The investigated aspects are listed as follows:

³³ PI Berlin reviewed the files "Daily Generation Report.xlsx" sent by the Owner to PI Berlin on the 8th July

Results of the visual inspection

The visual inspection on the modules showed clear signs of snail trails and shunts [23].



Figure 144: PV modules showing snail trails




Figure 145: PV modules showing shunts

Additionally, scratches of the module backsheet caused by the bushing of the tracker were found. These scratches are also visible from the front side of the modules in form of a localized corrosion. According to the Owner the flash lists of the PV modules are not available.



Figure 146: PV modules damaged by the dampers

Long term durability certificates

No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors mentioned above.

Infrared analysis

The infrared inspection didn't show major problems besides some sporadic hot spots and inactive cell strings both in the crystalline modules.




Figure 147: (left) Infrared inspection on site conducted by PI Berlin; (right) PV modules affected by one inactive cell string





Figure 148: PV modules affected by hot spots

Electroluminescence analysis


The electroluminescence analysis on a selected amount of crystalline PV modules confirmed the presence of cell cracks caused by improper handling, as well as a cell damage at the spots of the backsheet scratches caused by the bushings.



Sr.Nr.: confidential

Sr.Nr.: confidential

Figure 149: (left) Cell damages caused by the dampers; (right) PV module affected by one inactive cell string



Sr.Nr.: confidential

Sr.Nr.: confidential

Figure 150: PV module affected by cell cracks

5.5.7 Operation and Maintenance

The quality of the Operation and Maintenance service has been evaluated considering the points listed below. PI Berlin had the chance to interview a few members of the O&M team while conducting the site visit.

Experience of the O&M team

The Operator has vast experience in the O&M of PV plants and has introduced many O&M procedures in the this project. 2 engineers, 4 technicians and 1 site supervisor are involved in the O&M of this plant. The O&M staff has 2 years of PV experience.

Most relevant events occurred since COD

Problems in the oil pressure (PRV) of the MV transformers were reported in the first year. The EPC lead the replacement of the affected transformers and provided the O&M team with spare parts at site to mitigate future losses. The production loss registered during the transformer outage (around 30 days) wasn't compensated as no PR warranty was in place between the main EPC and the subcontracted EPC or between the Owner and the main EPC. During rainy days insulation problems were detected in connectors, damaged cables and modules. Fire events caused by a faulty contact in the connectors were also reported.

Cleaning methodology and calculation of the soiling loss

The losses due to soiling are not measured onsite. 2 cleanings per month have been agreed without conducting a previous study on the actual needs. The module cleaning is performed 2 times a month using cotton wipers and underground water. The impact of the selected cleaning methodology on the module warranty was not analyzed. According to the Operator, the cleaning is performed after the inverters shut down.

Tools used on site

The O&M team uses current clamps, multimeters, IR camera and insulation measurement devices among others. No PV specific tools and devices are used onsite except the infrared camera.

Reporting and reaction times

The O&M team generates the following reports: preventive maintenance report (monthly), generation report (daily), spare parts management (monthly) and safety report (daily). The reports include detailed information in regards to the working hours of the inverters, PR, irradiation on the POA, GHI, yield, internet connectivity data, inverter output/input, meter output, availability data, curtailment losses and outage time of the inverters, among others. No specific data regarding reaction times were shared with PI Berlin.

Preventive and corrective maintenance

The preventive maintenance is very comprehensive and includes several checklists and forms for all system components such as DC cables, connectors, modules, switchyard, inverters, combiner boxes, LV DC module, HV and MV transformers, grounding system, UPS and weather station among others. The corrective maintenance actions are recorded onsite and sent to the staff in the operational headquarter, who is conducting the root cause analysis and advises on the mitigation actions to be taken. The O&M members are allowed to operate all MV components of the plant.

Availability calculation and SCADA monitoring

The system availability is calculated by the staff in the operational headquarter based on the data provided by the team onsite. The staff based in the HQ is permanently visualizing the SCADA system. In case of failure, the HQ staff communicates with the field staff. The internet connection onsite is very slow which leads to communication problems with the monitoring system and with the HQ. The lost data are not recoverable, no server is installed onsite. The SCADA system visualizes each pair of strings entering the combiner box.

Curtailement and grid stability

According to the plant Operator, under frequency and under voltage events in the grid cause synchronization problems in the inverters leading to availability losses. The PV plant is not forced to support actively the grid as per grid code requirements.

5.5.8 Summary of the Results

The following table summarizes the failures detected onsite and the associated risks.

Table 6: Summary of the failures and the associated risks – Plant 5

Ref.	Item	Risk Description
1	Contracts	
1.1	Poor or not existing EPC warranties	After the bankruptcy of the EPC, the validity of the warranties specified in the EPC contract went lost. This legal gap had negative consequences on the Owner since no party was longer responsible for the performance losses caused by defect components installed by the EPC. The Owner was not compensated for the reduction of the system output since no EPC warranty was longer in place. This scenario might arise again if the warranties given by the EPC are not assumed by a new entity. This affects mainly the product warranties.
1.2	Poor or not existing O&M warranties	A typical O&M contract wasn't created since the Owner and Operator are the same entity. Hence, no standard O&M warranties based on Performance Ratio or system availability were formulated. The lack of O&M warranties leads to a comfortable scenario where the O&M team has no special incentive to force the PV plant to run at its maximum potential. The internal requirement which sets the inverter availability at a minimum of 97% is very lax. Inverter availabilities close to 99.5% and beyond are achievable in large scale PV plants with central inverters.
1.3	No appointment of an Owner's Engineer	The OE has the task to support the Owner's interests against the EPC and the various product suppliers. The OE conducts independent checks and verifications starting at the earlier phases of the EPC tendering and ending after commissioning or beyond. The absence of an experienced OE as an independent party, may lead to an increased risk for the Owner. In this project, the services of an OE were not requested even though the quality assurance services provided by an OE are highly recommended in order to avoid mistakes in all stages of the value chain.
2	PV Plant Design	
2.1	Missing statics or deviation from the manufacturer's racking design manual	The deviations from the installation manual of the solar tracker add uncertainty to the long-term durability of the mechanical assembly. Failures caused by limit states are not excludable as long as appropriate static calculations based on the alternative design prove the contrary.
2.2	Not consistent interrow shading simulation.	Due to the considerable height difference between the trackers, an additional mutual shading loss to the already existing E-W interrow shadings can't be excluded. This effect can be reduced by adjusting the foundation height of the trackers during the design phase.
2.3	High DC cable runs	The DC cable losses between the string combiner boxes and the inverter exceed 3% in some locations due to the fact that the PCUs concentrate a high amount of power without introducing a second distribution level between the string combiner boxes and the inverters. Additionally, the resulting voltage difference between combiner boxes located close and other located far away from the inverter, may lead to a voltage mismatch on inverter level. These combined effects lead to performance losses that could have been avoided with a more accurate design.

2.4	Low overbuilt	The tender specifications ³⁴ allow a PV plant design with an overbuilt higher than 1 as long as the AC capacity is not exceeded. However, the selected capacity is very close to 1 which leads to waste AC capacity even though the partial load behavior of the inverter is more efficient.
3	Electromechanical Installation	
3.1	Cables	
3.1.1	Mechanical damage visible or non-excludable	Some cables are in contact with rocks and stones, thus, an erosion of the cable shield can't be excluded leading to insulation losses of the electrical circuit.
3.1.2	Poor cable fixation	Hanging cables due to nondurable cable ties are more exposed to mechanical damage caused by the wind and the friction against other components such as the mounting structure or the module frames.
3.1.3	Poor or insufficient UV protection	The cables should not be exposed to the direct sunlight since their long term durability may be affected. This effect was detectable sporadically in the gaps between the mounting tables.
3.1.4	No sealing of pipes	Sealing the pipes and tubes helps protecting the cables from water and dirt accumulation as well as from mechanical damage caused by small animals. The proper sealing of the tubes is not ensured in the midterm since the used foam is starting to degrade.
3.2	Grounding and equipotential bonding system	
3.2.1	Belt not buried	The equipotential bonding conductor (belt) should be buried at a depth according to the applicable norms (typically around 60cm) in order to avoid safety issues due to possible interactions between personnel and fault currents flowing through the conductor. Additionally, the conductor should be buried in order to avoid mechanical damages caused by vehicles and machinery.
3.3	Documentation	
3.3.1	Missing construction progress reports	The installation phase reports are very helpful during O&M as they include valuable information of one of the most relevant phases of the project. Not having access to this information means losing part of the history of the plant.
4	Commissioning	
4.1	Insufficient commissioning tests. No compliance with the IEC 62446	One of the most relevant EPC warranties is the performance warranty which is typically expressed as a PR test to be conducted during an agreed amount of days at PAC and FAC. This test was not conducted at PAC due to the change of the scenario occurred after the bankruptcy of the EPC contractor which lead to questioning the validity of the previously agreed conditions in the EPC contract. In regards to the commissioning requirements specified by the IEC 62446, only part of the tests were conducted. The present scenario shows a PV plant that was not commissioned according to the best practices, neither in terms of performance validation, nor in terms of safety. The commissioning process complies with the tender requirements specified by SECI.
5	System Performance	
5.1	Installation failures detected	The excessively long arm that supports the pyranometer oscillates with the wind. Thus, the accuracy of the registered data can be affected.
5.2	PR fluctuation due to communication failures	The internet access onsite is not good which leads to an inconsistent logging of the meteorological data registered by the sensors. As a result, the PR calculations are not consistent either, leading to unrealistic values with very high daily PR fluctuations.
5.3	No cell temperature correction of the PR	The cell temperature even though it's recorded, it's not used for conducting a PR correction, which is a crucial step in the comparison between the onsite PR and the contractual PR.
6	PV Module Quality	
6.1	Presence of scratched backsheets	Some modules showed scratches in the backsheet, caused by the bushings of the trackers. This failure leads to the loss of the required insulation value of the electrical circuits and to cell cracks combined with corrosion at the location of the scratches. This effect is especially critical in areas with high humidity rates.
6.2	Presence of shunts	The thin film modules show signs of shunt presence. The consequences and root cause of this effect should be further investigated.
6.3	Presence of module and cell cracks due to bad module handling	The snail trails detected on site are an evidence of cell cracks which were confirmed with infrared and electroluminescence technology by PI Berlin. These cracks show the typical pattern of damages caused by bad module handling during the construction phase. Cracks may lead to performance losses as they develop further, and to hot spots when parts of the cells are isolated by the cracks.
6.4	No flash lists available	The flash lists shall be provided by the module manufacturer as part of the quality control program. The flash lists are useful for determining the exact nominal power of the PV plant and for conducting an adequate module sorting, among other reasons.

³⁴ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SP/P-2/B-1/RfS/102013

6.5	No specific certificates beyond the basic IEC certification requested to the manufacturer	No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors present on site. The high temperature, UV and humidity rates registered onsite represent a threat for the PV modules in terms of long-term durability.
7	Operation and Maintenance	
7.1	Corrective maintenance conducted remotely	The HQ is conducting the system availability calculation, the event registration, the root cause analysis and the advisory on the mitigation measures to be taken, even though they are not present onsite. The local O&M members should be more involved with the operational data and daily activities of the plant in order to increase their knowledge and improve their capability to detect, solve and predict failures as well as to assess the operational quality of the system.
7.2	No evaluation of the impact of the cleaning concept on the module warranty	The impact of the selected cleaning methodology on the module warranty hasn't been analyzed. Several factors such as the material used for the wipers, the type of water used, the cleaning methodology, the water pressure and the physical and chemical properties of the soil, might have an influence on the glass and the anti-reflective coating of the modules. Product damages or performance losses of any kind originated by the cleaning process are not covered by the product warranty unless the cleaning concept has been approved previously by the module manufacturer. This step was not given before starting the operational phase.
7.3	Definition of the cleaning intervals without knowing the accumulated soiling losses between 2 periods	The losses due to soiling are not measured onsite. 2 cleaning rounds per month have been agreed without conducting a previous study on the accumulated soiling loss between 2 periods. As a consequence, the cleaning frequency is not adjusted to a defined soiling loss which should not be exceeded. Actually, due to the amount of cleaning rounds defined in advance, there might be some periods when the PV plant is "undercleaned" and others in which the PV plant is "overcleaned". In the first case performance is lost, while in the second case unnecessary costs are generated.
7.4	No PV specific devices used onsite	Devices and tools used in the PV industry such as IV curve tracers, electroluminescence devices and infrared cameras help detecting and evaluating failures easily. The regular use of these devices is necessary during O&M for detecting and monitoring defects and degradation phenomena such as hot spots, cracks or PID.
7.5	Communication problems	The internet connection onsite is very slow which leads to communication problems with the monitoring system and with the HQ. The lost data are not recoverable since no server is installed onsite. A proper logging, recording and sending of the data used for calculating the key performance indicators is crucial for a correct assessment of the plant operation.

5.6 Plant 6 - 10MW ground mounted (Karnataka)

Date of inspection by PI Berlin	15.07.2017
Name and size of the plant	confidential, 10MW (ground mounted)
Coordinates	confidential
Commercial Operation Date (COD)	confidential
Name of the Owner	confidential
Name of the EPC	confidential
Name of the O&M company	confidential
<p>The 10 MW PV plant uses PV modules arranged in two portrait tilted at 12° on a fixed mounting structure. The strings contain 20 modules in series and are connected to a 16 input DC combiner box. 7 combiner boxes are connected to one 630kW inverter and 2 inverters are connected in parallel to a 0.35/11kV 1.6MVA transformer. The 11kV line 1Rx3Cx185mm² is connected to a common bar with 2Rx3Cx400mm² leading to the substation. The level of injection is at 66kV. The Owner has signed a 25 year PPA with SECI.</p>	

5.6.1 Contracts

Under this chapter PI Berlin has put the main focus on:

- EPC contract
- O&M contract
- Role of the Owner's Engineer
- Role of the Lender's Technical Advisor supporting the financing institution

The evaluation of the above mentioned points leads to the following outcomes:

- The EPC has guaranteed 14,892 GWh per year for the first 3 years considering 1% degradation per year. This value must be achieved regardless the registered irradiation and temperature data onsite. However, this value can be considered as lenient considering the irradiation and temperature values typical for the site, as well as the relatively low interannual variability compared to other regions. The analysed production data for the first two years of operation show that the contractual value has been exceeded by 4% in the first year and by 10% in the second year³⁵.
- The O&M contract has been signed for 3 years between the O&M company and the EPC contractor.
- No PAC tests are mentioned in the EPC contract
- No Owner's Engineer was appointed.
- No Lender's Technical Advisor was appointed. SECI is the financing institution.

5.6.2 PV Plant Design

This chapter analyses:

- Interrow shading based on the selected pitch and tilt
- Statics
- Location of inverters and combiner boxes
- Electrical overbuilt

Interrow shading based on the selected pitch and tilt

The pitch (lower edge-lower edge) is 5.5 m according to the as-built situation. This value was confirmed onsite by PI Berlin. No PV SYST simulation was provided by the Owner. PI Berlin has measured tilt values very close to 12° in most locations of the PV plant. The tilt angle of the PV modules seems to be very consistent and matches the design criteria. The height differences in E-W direction may lead to additional shading losses.

³⁵ PI Berlin reviewed the file "measurement of irradiation ambient temp & gen.xlsx" sent by the Owner on the 27th June 2017



Figure 151: Height differences between the mounting tables in E-W direction

The reason for this height difference is the non-adjustment of the foundation height in order to absorb the terrain slope.

Statics

No static calculations were shared with PI Berlin, hence the structural integrity of the mounting structure couldn't be proven.

Location of inverters and combiner boxes

The inverters and distribution boxes are located considering cable and voltage drop reduction criteria. The cable runs are kept short avoiding an unnecessary voltage mismatch at inverter level. This statement bases both on the onsite inspection as well as on the review of the as-built layouts provided by the Owner.³⁶

Electrical overbuilt

The tender specifications³⁷ allow a PV plant design with an overbuilt higher than 1 as long as the AC capacity is not exceeded. However, the selected overbuilt is low (2.14%) which leads to waste AC capacity even though the partial load behavior of the inverter is more efficient.

5.6.3 Electromechanical Installation

The quality of the electromechanical installation was assessed onsite by PI Berlin evaluating the following subsystems:

- Mounting structure
- Combiner boxes
- Cables fixation
- Inverter
- Grounding and equipotential bonding
- Civil work
- Documentation

Mounting structure and module fixation

- i. Module fixation: The modules are properly fixed to the cross beams. No misalignment could be observed.

³⁶ PI Berlin has reviewed the drawings "array layout part A.pdf" and "array layout part B.pdf" sent by the Owner on the 27th June 2017

³⁷ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013



Figure 152: PV modules fixed to the mounting structure

- ii. Labelling of rows: The labelling of the mounting structure hasn't been conducted properly. The used labelling system is not durable and some areas are not labelled at all.



Figure 153: Missing labelling of the module rows

- iii. Rust on the mounting structure surface: The mounting structure shows signs of rust




Figure 154: Presence of rust in the mounting structure

Combiner boxes

- i. Sealing of the cable glands: Some cable glands in the DC combiner boxes are open.



Figure 155: Open cable glands in the DC combiner box

- ii. Cleanliness of the combiner box: The dust accumulation inside the combiner boxes is not significant.



Figure 156: Clean DC combiner box

- iii. Labelling of the combiner box: The DC combiner boxes are labelled. Some of the tags attached to the housing are starting to lose adherence.




Figure 157: Missing labelling of the DC combiner box

Cables fixation and routing

- i. Cable damage: the string cables show damages caused by external agents. Some of them are in contact with sharp edges, thus, an erosion of the cable shield can't be excluded in the midterm.



Figure 158: String cables in contact with sharp edges

- ii. Labelling of cables: Both the strings cables entering the combiner box and the main DC cables connecting the combiner box with the inverter are properly labelled. In both cases the used tags seem to be durable for the whole lifetime of the project.



Figure 159: Labelling of the string cables

- iii. Connectors: The connectors are in general in a good shape
- iv. Cable fixation and bending radius: The cables ties used for the cable fixation do not show degradation due to outdoor exposure. In general, the minimum bending radius of the cables has been respected.
- v. Protection against UV: The cables aren't protected from UV light between the mounting tables.



Figure 160: Missing UV protection of the string cables

- vi. Cable pipes and sealing: The tubes conducting the DC cables to the inverter are sealed with durable foam. The tubes where the cables are routed do not show degradation due to outdoor exposure.



Figure 161: Sealed cable tubes

Inverter

The inverter has an overvoltage protection on the AC side as well as a DC switch. The PCU is clean, no significant amount of dust has been detected. The inverter has a default ventilation system. The inverter room does not have a thermostat that regulates the temperature inside the housing. A forced ventilation system was installed inside the PCUs. The inverter filters and air inlets are clean.



Figure 162: View of the central inverter

Grounding and equipotential bonding

The equipotential bonding system connects all conductive parts of the PV plant as the mounting structure, module frames or housings. The equipotential bonding conductor is not properly buried due to the stony ground. No rust or corrosion was observed. In terms of Potential Induced Degradation (PID) avoidance, no measures have been taken, such as functional grounding of the negative pole. The PV plant is affected by PID.



Figure 163: (left) Equipotential bonding conductor; (right) Not buried equipotential bonding conductor

Civil work

The status of the internal roads is very good. The drainage system is clean and well maintained. According to the EPC, the costs associated to the civil work represent 3% of the total CAPEX due to the levelling, grading and removing of stones and trees.



Figure 164: (left) Internal roads; (right) Drainage system

Documentation

In terms of completeness, the provided as-built documents do not comply with many requirements of the IEC 62446. No progress reports of the installation phase are available.

5.6.4 Commissioning

PI Berlin considers the commissioning process conducted at the end of the installation phase a crucial milestone in the deployment of a PV project. The commissioning process as per IEC 62446 is divided in “cold” and “hot” commissioning, and ends with the issuance of the Provisional Acceptance Certificate, and is the last step before the EPC warranty starts. This process gives an idea of the status of the plant in terms of safety and functionality. The EPC contract doesn’t mention any tests to be conducted by the EPC following the IEC 62446. Thus, no commissioning tests were performed during PAC. No EOW tests are defined either. Besides the contractual conditions described in the EPC contract, the official commissioning was approved following the specifications of the tender documentation³⁸. The requirements included the submission of the electrical inspector report, the connectivity report issued by the Discom authority, a confirmation of compliance from SECI, a synchronization certificate issued by the Discom authority, snapshots of the plant, plant layout, SLD and meter readings submitted by the Solar Project Developer, and an installation report also submitted by the Solar Project Developer.

5.6.5 System Performance

In this chapter PI Berlin analyses several factors that influence the calculation of the system performance.

Weather station status and sensor accuracy

The weather stations installed onsite is constituted by a pyranometer on the horizontal surface, an ambient temperature sensor and an anemometer. Both the irradiation on the plane of the array (POA) and the cell temperature are not measured. The file “*measurement of irradiation ambient temp & gen.xlsx*” shows consistent values of the ambient temperature and wind velocity. The recorded GHI data of the first two years lead to PR values of 124% for the first year and 96% for the second year which are non-realistic values. The communication cable is in a very bad shape and the reliability is not ensured. According to the Owner, the sensors are calibrated each 2 years. The calibration certificates were not provided to PI Berlin.

³⁸ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013



Figure 165: (left) Weather station; (right) Ambient temperature sensor and anemometer



Figure 166: (left) Pyranometer on the horizontal surface; (right) Damaged communication cable

Performance Ratio calculation

The PR is not calculated onsite. According to the EPC, the contractual yield output value used for Financial Close was simulated with PV SYST using meteorological data from NASA. The achieved value was 14,892 GWh/year considering a linear degradation of 1% per year. PI Berlin had no access to the simulation reports. The analysed production data for the first two years of operation shows that the contractual value has been exceeded by 4% in the first year and by 10% in the second year³⁹. The minimum CUF requirement in the tender documentation specified by SECI⁴⁰ is fulfilled.

5.6.6 PV Module Quality

The PV modules represent the most sensitive part of the PV plant, especially in harsh climates with high UV loads, high temperatures and high humidity rates. These environmental stressing factors are present on site whose climate is classified as Aw according to Köppen-Geiger [21]. In order to assess the quality of the modules, PI Berlin has conducted a visual inspection, an infrared analysis and an electroluminescence inspection using the equipment specified in Annex IV. The investigated aspects are listed as follows:

Results of the visual inspection

The visual inspection on the modules showed clear signs of snail trails, evidences of burned cells, soldering failures and burned busbars. The flash lists are available since the Operator is also the module supplier.

³⁹ PI Berlin has evaluated the file "measurement of irradiation ambient temp & gen.xlsx" sent by the Owner on the 27th June 2017

⁴⁰ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SP/P-2/B-1/RfS/102013




Figure 167: (left) Detached ribbon; (right) Burned cell




Figure 168: Hot spots



Figure 169: (left) Browning along the busbars; (right) Signs of snail trails

Long term durability certificates

No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors mentioned above.

Infrared analysis

The infrared inspection showed clear evidences of hot spots along the ribbon, cell hotspots and PID. Other minor effects such as inactive cell strings or cell mismatch were also visible.




Figure 170: PV modules affected by hot spots




Figure 171: (left) PV module with one inactive cell string; (right) PV module affected by bad soldering




Figure 172: (left) PV module affected by bad soldering; (right) PV module affected by PID





Figure 173: PV modules affected by PID

Electroluminescence analysis

The electroluminescence analysis on a selected amount of crystalline PV modules confirmed the presence of PID and cell cracks caused by improper module handling.




Sr.Nr.: confidential

Sr.Nr.: confidential

Sr.Nr.: confidential

Sr.Nr.: confidential

Figure 174: PV modules affected by cracks



Sr.Nr.: confidential

Sr.Nr.: confidential

Figure 175: PV modules affected by PID

5.6.7 Operation and Maintenance

The quality of the Operation and Maintenance service has been evaluated considering the points listed below. PI Berlin had the chance to interview a few members of the O&M team while conducting the site visit.

Experience of the O&M team

The O&M team subcontracted by the Operator is currently maintaining 125MW of PV plants across India. The subcontracted company has 5 years of experience in O&M of PV plants. This project is the first experience for the staff involved onsite.

Relevant environmental elements

The most relevant environmental phenomena reported onsite are: rainfalls and erosion. The O&M plan does not include specific action to mitigate the effects of the erosion.



Figure 176: Signs of erosion

Cleaning methodology and calculation of the soiling loss

The soiling losses are not measured onsite. According to the Owner and Operator, the module cleaning is performed 3 times a month using cotton wipers and underground water. The resulting soiling losses derived from the established cleaning frequency were not calculated by the Operator. The impact of the selected cleaning methodology on the module warranty was not analysed either. According to the Operator, the module cleaning is performed after the inverters shut down.




Figure 177: (left) Soil accumulation; (right) Module cleaning team



Figure 178: (left) Module cleaning team; (right) Module cleaning device

Tools used on site

The O&M team uses current clamps, multimeters, an arcing measurement device and an insulation measurement device. No PV specific tools and devices are used onsite.

Reporting and reaction times

The O&M team generates the following reports: (i) generation report (daily); (ii) cleaning, vegetation cut, spares, string current measurements at CB level and corrective maintenance actions (monthly). The reports are issued as an excel file. The reaction times agreed by the Operator and the EPC were not shared with PI Berlin. The water pipes used for water cleaning disturb the access by car to the interrow space during preventive maintenance and may lead to an increase of the reaction time.

Preventive and corrective maintenance

The daily, monthly and yearly maintenance plans do not cover the entire PV system. Certain subsystems such as the DC cabling, mounting structure or combiner boxes do not have a proper maintenance plan. Some safety aspects are covered by the checklists shared with PI Berlin, such as the earth resistance measurements, but other aspects like insulation measures, continuity measures of the equipotential bonding system or the functionality check of the protective devices remain uncovered. A specific plan for the PV modules using specialized devices is also missing. The vegetation is cut every 15 days. The corrective maintenance actions are logged onsite and added to the monthly reports. No root cause analysis or mitigation plans were shared with PI Berlin.

Availability calculation and SCADA monitoring

One person is responsible for the daily visualization of the SCADA system. The system availability is not calculated. The SCADA monitors data up to string pair level. All values are recorded each 15min and a local server is used for storing the recorded data.

5.6.8 Summary of the Results

The following table summarizes the failures detected onsite and the associated risks.

Table 7: Summary of the failures and the associated risks – Plant 6

Ref.	Item	Risk Description
1	Contracts	
1.1	Poor or not existing O&M warranties	The O&M was signed between the EPC and the O&M company for a period of 3 years. However, no warranties based on Performance Ratio or system availability were formulated. The lack of O&M warranties leads to a comfortable scenario where the O&M team has no special incentive to force the PV plant to run at its maximum potential. The consequences are usually a lower availability and a lower output than expected.
1.2	Poor or not existing EPC warranties	The EPC has guaranteed 14,892 GWh per year for the first 3 years considering 1% degradation per year regardless the registered meteorological values. Even if this requirement is binding, this condition is easy to fulfill considering the registered POA values in the region and the output values registered for the first two years. Additional requirements in terms of safety and long-term durability were not required to the EPC, so evidences in this regard weren't provided.
1.3	No appointment of an Owner's Engineer	The OE has the task to support the Owner's interests against the EPC and the various product suppliers. The OE conducts independent checks and verifications starting at the earlier phases of the EPC tendering and ending after commissioning or beyond. The absence of an experienced OE as an independent party, may lead to an increased risk for the Owner. In this case, the Owner did not request the services of an OE even though the quality assurance services provided by an OE are highly recommended in order to avoid mistakes in all stages of the value chain.
1.4	No appointment of a Lender's Technical Advisor	Similarly to the OE, the LTA supports the interests of the bank as the financing institution. Accordingly, the bank is interested in financing projects which are bankable and are exposed to low risks. Thus, the task of the LTA is to ensure the bankability of the project by supervising that all steps made by the Developer (very often also the Owner at the same time) lead to a low risk scenario. In this project the financing institution did not require the services of an LTA.
2	PV Plant Design	
2.1	Missing statics	As long as static calculations are not performed showing that the selected design is appropriate for the applicable environmental conditions, the structural integrity of the mounting structure is not ensured.
2.2	Not consistent interrow shading simulation.	Due to the height difference between the module tables in E-W direction, an additional mutual shading loss to the already existing N-S interrow shadings can't be excluded. This effect can be reduced by adjusting the foundation height of the mounting tables during the design phase.

2.3	Low overbuilt	The tender specifications ⁴¹ allow a PV plant design with an overbuilt higher than 1 as long as the AC capacity is not exceeded. However, the selected capacity is very close to 1 which leads to waste AC capacity even though the partial load behavior of the inverter is more efficient.
3	Electromechanical Installation	
3.1	Mounting structure	
3.1.1	No row labelling	The missing row labelling makes the correct identification of the various areas of the plant more difficult leading to increased reaction times during corrective maintenance.
3.1.2	Rust on the mounting structure components	The rust can lead to a reduction of the structural strength of the mounting structure, especially in combination with strong wind.
3.2	Combiner boxes	
3.2.1	Cable glands not sealed	Not sealed cable glands allow dust and dirt entering the combiner box housing.
3.2.2	Loss of adherence of the datasheets attached to the housings	The tags and datasheets attached to the housing are losing adherence. The missing combiner box labelling makes the correct identification of the various areas of the plant more difficult leading to increased reaction times during corrective maintenance. Additionally, electrical parts that aren't properly labelled hide safety risks when manipulated by O&M members.
3.3	Cables	
3.3.1	Mechanical damage visible or non-excludable	Some cables are in contact with rocks and stones, thus, an erosion of the cable shield can't be excluded in the midterm.
3.3.2	Poor or insufficient UV protection	The cables should not be exposed to the direct sunlight since the long term durability of the cable shield may be affected. This effect was detectable mainly in the gaps between the mounting tables.
3.4	Grounding and equipotential bonding system	
3.4.1	Belt not buried	The equipotential bonding conductor (belt) should be buried at a depth according to the applicable norms (typically around 60cm) in order to avoid safety issues due to possible interactions between personnel and fault currents flowing through the conductor. Additionally, the conductor should be buried in order to avoid mechanical damages caused by vehicles and machinery. In this specific project, burying the belt was difficult due to the high amount of stones in the ground.
3.4.2	No functional grounding against PID	No measures were taken in order to avoid the appearance and development of PID. The Karnataka region is a PID risk area due to relatively high temperatures and humidity. The presence of PID was confirmed onsite.
3.5	Documentation	
3.5.1	No compliance of the as-built documentation with the IEC 62446	The as-built documentation is not complete according to the applicable norms and standards. This represents a risk for instance during takeover, as the new Owner acquires an asset whose installation, BOM and drawings are not properly documented.
3.5.2	Missing construction progress reports	The installation phase reports are very helpful during O&M as they include valuable information of one of the most relevant phases of the project. Not having access to this information means losing part of the history of the plant.
4	Commissioning	
4.1	Insufficient commissioning tests. No compliance with the IEC 62446	One of the most relevant EPC warranties is the performance warranty which is typically expressed as a PR test to be conducted during an agreed amount of days at PAC and FAC. This test was not conducted. In regards to the commissioning requirements specified by the IEC 62446, no tests have been conducted either. The present situation shows a scenario where the plant hasn't been commissioned neither considering the performance values, nor in terms of safety. The commissioning process complies with the tender requirements specified by SECI.
5	System Performance	
5.1	No PR calculation conducted onsite	The real PR is not calculated which makes a correct assessment of the system performance impossible.
5.2	BOM of the weather station not complete	The cell temperature and the irradiation on the tilted plane (POA) are not measured onsite. These parameters are an essential part of a correct meteorological data assessment of an operating plant and were required in the tender specifications. Both values are crucial to conduct a PR calculation. The cell temperature values help correcting the PR value, which is a crucial step for a proper comparison between the onsite PR and the contractual PR. These values would be useful to conduct a PR calculation at a later stage.
5.3	Not consistent logging of the irradiation values	The logged irradiation values lead to unrealistic PR values above 100% for the first two years of operation. Thus, the system performance is not properly reflected.
5.4	Installation failures detected	The communication cable is in a very bad shape and as a consequence, the reliability of the data sent to the SCADA system are not ensured. Besides, the weather station is not located at a representative place.

⁴¹ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013

5.5	The yield simulation during the development phase does not use site specific data	The yield assessment conducted during the development phase should use meteorological data that are as accurate as the project phase demands. Otherwise the assessment won't reflect the system performance properly (with the corresponding limitations) and won't be bankable.
6	PV Module Quality	
6.1	Presence of module and cell cracks due to bad module handling	The snail trails detected on site are an evidence of the presence of cell cracks which can be confirmed with infrared and electroluminescence technology. These cracks show the typical pattern of damages caused by bad module handling during the construction phase. Cracks may lead to performance losses as they develop further, and to hot spots when parts of the cells are isolated by the cracks.
6.2	Presence of burned cells	Burned cells might be responsible for fire events. Thus, the affected modules should be replaced immediately. In some cases, burned busbars were also visible.
6.3	Presence of manufacturing failures	The presence of inaccurate soldering of the ribbons points towards lacking quality inspection programs during manufacturing. When this specific failure arises, the further development of the hot spots visible along the busbars, can lead to a permanent damage of the module or even to fire events.
6.4	Presence of PID	The PID effect can be responsible in the short term for a significant reduction of the PV power output of the modules located on the negative side of the string, and should be stopped immediately. The development of PID is accelerated with high temperatures and humidity rates, both present at the PV plant location.
6.5	No specific certificates beyond the basic IEC certification requested to the manufacturer	No specific certificates beyond the basic IEC certification were requested by the Owner in regards to the long term durability of the modules considering the environmental stressing factors present on site. The high temperature, UV and humidity rates registered onsite represent a threat for the PV modules in terms of long-term durability.
7	Operation and Maintenance	
7.1	Lack of experience of the O&M team	The lack of experience of the O&M team may lead to a wrong diagnose of the detected failures, as well as to an inaccurate corrective maintenance, among other consequences. In order to maximize the performance and availability of the PV plant, the O&M team should be familiar with as many events as possible in all potential scenarios.
7.2	Definition of the cleaning intervals without knowing the accumulated soiling losses between 2 periods	The losses due to soiling are not measured onsite. 2 cleaning rounds per month have been agreed without conducting a previous study on the accumulated soiling loss between 2 periods. As a consequence, the cleaning frequency is not adjusted to a defined soiling loss which should not be exceeded. Actually, due to the amount of cleaning rounds defined in advance, there might be some periods when the PV plant is "undercleaned" and others in which the PV plant is "overcleaned". In the first case performance is lost, while in the second case unnecessary costs are generated.
7.3	No evaluation of the impact of the cleaning concept on the module warranty	The impact of the selected cleaning methodology on the module warranty hasn't been analyzed. Several factors such as the material used for the wipers, the type of water used, the cleaning methodology, the water pressure and the physical and chemical properties of the soil, might have an influence on the glass and the anti-reflective coating of the modules. Product damages or performance losses of any kind originated by the cleaning process are not covered by the product warranty unless the cleaning concept has been approved previously by the module manufacturer. This step was not given before starting the operational phase.
7.4	Preventive maintenance not adjusted to the PV technology	The preventive maintenance program focuses mainly on the switchyard, inverters, combiner boxes, LV DC module, HV and MV transformers and weather station. No preventive actions are conducted on PV modules and DC cables, which are an essential part of the system and require specific checklists which can't be recycled from other technologies.
7.5	No PV specific devices used onsite	Devices and tools used in the PV industry such as IV curve tracers, electroluminescence devices and infrared cameras help detecting and evaluating failures easily. The regular use of these devices is necessary during O&M for detecting and monitoring defects and degradation phenomena such as hot spots, cracks or PID.
7.6	Corrective maintenance without root cause analysis, mitigation measures, documentation and follow up	No root cause analysis, mitigation actions and follow up is conducted on the events registered onsite. Part of the corrective maintenance is to investigate the origin of the failures, find a solution and monitor the evolution in the short term.
7.7	No system availability calculation	The system availability is not measured, neither on inverter nor on string level. As a consequence, it remains unknown if the amount of operational hours of the various subsystems such as inverters or strings, can be increased leading to a maximization of the yield output.

6 Interpretation of the Results

6.1 Failure Matrix

The following table gives an overview of all failures and defects detected in the 6 analyzed plants and also in which of the 6 sites each of the failures is present. The norms and references applicable to each defect are indicated in the last column.

Table 8: Failure matrix

Ref.	Item	Plant 1	Plant 2	Plant 3	Plant 4	Plant 5	Plant 6	Literature and normative guidelines
1	Contracts and warranties							
1.1	Not existing EPC contract	X	X					
1.2	Poor or not existing EPC warranties	X	X	X	X	X	X	
1.3	Not existing O&M contract	X	X	X	X	X		
1.4	Poor or not existing O&M warranties	X	X	X	X		X	
1.5	No appointment of an Owner's Engineer	X	X		X	X	X	
1.6	No appointment of a Lender's Technical Advisor	X	X				X	
2	PV Plant Design							
2.1	Not consistent interrow shading simulation.	X	X					
2.2	Missing statics or deviation from the manufacturer's racking design manual		X	X	X	X	X	
2.3	High DC cable runs					X		
2.4	Low overbuilt			X		X	X	
2.5	Height differences between module tables in E-W or N-S direction					X	X	
3	Electromechanical Installation							
3.1	Mounting structure							
3.1.1	Poor module fixation	X	X	X	X			
3.1.2	No row labelling	X	X	X			X	
3.1.3	Rust on the mounting structure components	X		X			X	
3.1.4	Weak foundation, no solid anchorage		X					
3.2	Combiner boxes							
3.2.1	Cable glands not sealed			X			X	
3.2.2	Dust and dirt inside the housing	X		X	X			IEC 62548
3.2.3	Poor or no labelling	X	X	X	X		X	IEC 62548 ⁴²

⁴² 10.2: "...be constructed and affixed to remain legible for the life of the equipment..."

Ref	Item	Plant 1	Plant 2	Plant 3	Plant 4	Plant 5	Plant 6	Literature
3.3	Cables							
3.3.1	Mechanical damage visible or non-excludable	X		X	X	X	X	IEC 62446, IEC 62548 ⁴³ , IEC 60664-1, VDE-AR-E-2283-4:2010-10, [16]
3.3.2	Poor or not existing labelling of the DC cables	X	X	X				
3.3.3	Open or damaged connectors	X		X				
3.3.4	Poor cable fixation	X	X	X	X	X		IEC 60364-5-52:2009, IEC 62548 ⁴⁴ , [10], [14]
3.3.5	Insufficient bending radius	X		X				IEC 60364-5-52:2009
3.3.6	Poor or insufficient UV protection		X	X	X	X	X	IEC 60364, IEC 62548 ⁴⁵ , VDE-AR-E-2283-4:2010-10, IEC 60721 3-4, IEC 60445:2010 y 2 PfG 1169/08.2007, [10] ⁴⁶
3.3.7	No sealing of pipes	X	X	X		X		IEC 62548, IEC 60364-7-712, IEC 60364-5-52:2009
3.3.8	Non durable cable pipes	X		X				IEC 62548 ⁴⁷
3.4	Inverter and inverter room							
3.4.1	Presence of dust inside the room, dirty filters			X	X			IEC 60364-7-712, IEC 62548, [14] ⁴⁸
3.4.2	Poor cable guidance into the inverter	X						
3.4.3	Cooling concept not comprehensive			X	X			
3.5	Grounding and equipotential bonding system							
3.5.1	Continuity not ensured due to corrosion	X		X	X			
3.5.2	Belt not buried			X	X	X	X	IEC 60364, [16] ⁴⁹
3.5.3	No functional grounding against	X	X				X	

⁴³ 7.3.6.3: "Cables shall be supported so that their properties and installation requirements are maintained over the stated life of the PV plant."; "They shall also be protected from sharp edges"

⁴⁴ 7.3.6.3: "Cable ties shall not be used as a primary means of support unless they have a lifetime greater than or equal to the life of the system or the scheduled maintenance period"; "Cables shall be supported so they do not suffer fatigue due to wind/snow effects."

⁴⁵ 7.3.6.2: "... if exposed to the environment, be UV-resistant, or be protected from UV light by appropriate protection, or be installed in UV-resistant conduit..."

⁴⁶ "Cable care"; PV Magazine; issue 05-2013, 3rd May 2013. "Despite being rated as UV-resistant or able to withstand high temperature ranges to combat environmental factors, cables and connectors alike should be kept out of direct sunlight as much as possible. Materials that are exposed to high irradiation conditions can face degradation over time despite ratings and having been tested."

⁴⁷ 7.3.6.3: "All non-metallic conduit and ducting exposed to sunlight shall be of a UV resistant type."

⁴⁸ "Manual of good and bad practices to improve the quality and reduce the cost of PV systems"; PV Crops; 2013. "The room is full of dust and the filters of the inverter fans are clogged. Therefore, the inverter cooling and the efficiency are reduced."

⁴⁹ "Utility Scale Solar Power Plants - A guide for developers and investors"; IFC; 2012; page 118: "Underground cables should be buried at a suitable depth (generally between 500mm and 1,000mm) with warning tape or tiles placed above and marking posts at suitable intervals on the surface."

Ref	Item	Plant 1	Plant 2	Plant 3	Plant 4	Plant 5	Plant 6	Literature
	<i>PID</i>							
3.5.4	<i>Equipotential bonding system (EBS) not integrated in the EBS of the building</i>		X	n/a	n/a	n/a	n/a	
3.6	<i>Documentation</i>							
3.6.1	<i>No compliance of the as-built documentation with the IEC 62446</i>	X	X				X	
3.6.2	<i>Missing construction progress reports</i>	X	X	X	X	X	X	
4	Commissioning							
4.1	<i>Insufficient commissioning tests. No compliance with the IEC 62446.</i>	X	X	X	X	X	X	IEC 62446, IEC 62548 ⁵⁰ , [16] ⁵¹
4.2	<i>No witnessing of the PR Test</i>	X	X	X	X	X	X	
5	System Performance							
5.1	<i>Not consistent logging of the irradiation values</i>	X				X	X	
5.2	<i>Not consistent logging of the temperature values</i>		X			X	X	
5.3	<i>BOM of the weather station not complete</i>	X	X	X			X	
5.4	<i>Installation failures detected</i>	X	X	X	X	X	X	[9] ⁵²
5.5	<i>Poor or no PR calculation conducted onsite</i>		X			X	X	
5.6	<i>No cell temperature correction of the PR</i>	X	X	X	X	X	X	
5.7	<i>Bankable yield simulation for FC not conducted acc. to standards</i>		X	*		*	X	[19] ⁵³
6	PV Module Quality							
6.1	<i>Presence of cell cracks due to bad module handling</i>			X	X	X	X	[5], [6], [7], [8], [14], [17] ⁵⁴ , [18], [16] ⁵⁵
6.2	<i>Scratched backsheets</i>			X		X		IEC 61730, IEC 62446, IEC 62548, UL 1703, IEC 60364-7-712, [16]
6.3	<i>Burned cells</i>			X			X	

⁵⁰ section 8 Ed. 2013 "Acceptance testing should be performed according to the requirements of IEC 62446."

⁵¹ Utility Scale Solar Power Plants-A guide for developers and investors"; IFC; 2012; page 122: "Commissioning should follow the procedure described in IEC 62446 and prove three main criteria..."

⁵² "The Atacama desert, extreme conditions for instrumentation"; Kipp & Zonen news; Thursday, March 17, 2016. "The cables must be channelled through metal tubes and waterproofed."

⁵³ Page 52: "State of the art in PV yield assessments"; Power PV TECH – PV Power Plant Technology and Business, página 52; André Schuman (SolPEG); May 2016.

⁵⁴ "Review of failures of photovoltaic modules"; IEA - International Energy Agency; Report IEA-PVPS T13-01:2014. "Once cell cracks are present in a solar module, there is an increased risk that during operation of the solar module short cell cracks can develop into longer and wider cracks."

⁵⁵ "Utility Scale Solar Power Plants - A guide for developers and investors"; IFC; 2012; page 116: "Controlling construction quality is essential for the success of the project. The required level of quality should be defined clearly and in detail in the contract specifications."

Ref	Item	Plant 1	Plant 2	Plant 3	Plant 4	Plant 5	Plant 6	Literature
6.4	<i>PID</i>		X				X	
6.5	<i>Presence of manufacturing failures</i>			X			X	
6.6	<i>Presence of shunts</i>				X	X		
6.7	<i>No specific certificates beyond the basic IEC certification requested to the manufacturer</i>	X	X	X	X	X	X	[15]
6.8	<i>No flash lists available</i>		X			X		
7	Operation and Maintenance							
7.1	<i>Lack of experience of the O&M team</i>		X	X			X	
7.2	<i>No evaluation of the impact of the cleaning concept on the module warranty</i>	X	X	X	X	X	X	[3], [4], [11]
7.3	<i>Definition of the cleaning intervals without knowing the accumulated soiling losses between 2 periods</i>		X	X	X	X	X	
7.4	<i>No PV specific devices used onsite</i>		X	X	X	X	X	
7.5	<i>Poor reporting</i>	*	X	X				
7.6	<i>Preventive maintenance not adjusted to the PV technology</i>	*	X	X			X	
7.8	<i>Corrective maintenance without analysis of the root cause, mitigation measures, documentation and follow up</i>	*	X	*			X	
7.9	<i>No system availability calculation</i>	X	X				X	

*: no information provided by the Owner

6.2 Risk Analysis

This chapter will identify and describe the risks derived from the failures and deviations found in the 6 analyzed plants. The assessment will be divided in the seven topics that constitute the Q3-Technical Due Diligence product that PI Berlin developed for operating plants. In this assessment, the risks will be evaluated from the perspective of the Owner or the SPD⁵⁶.

Contracts and Warranties

In the EPC⁵⁷ and O&M⁵⁸ contracts signed between the involved parties, the warranties are not properly addressed. In the EPC contracts, these warranties are typically fixed with a Performance Ratio (PR) test, additional tests to be conducted before and after grid connection⁵⁹ and a defined warranty period⁶⁰, while the O&M contracts focus usually on yearly system availability values defined either on inverter or string level. The purpose of agreeing on contractual warranties is to reduce the risk of the Owner while ensuring first, a minimum quality of installation, and second a proper operation that maximizes the performance and the operating hours.

After evaluating the contracting of the 6 analyzed projects, PI Berlin could identify two different scenarios: on the one hand, the warranties do not exist in all those projects where (i) the Owner is at the same time the EPC or (ii) the Owner is at the same time the Operator. In this situation there is no way to assess both the construction quality at the time of grid connection⁶¹ and the operational quality during the lifetime of the project, as neither the EPC nor the O&M company are contractually forced to provide evidences. *Plants 1 and 2* correspond to this case where EPC and O&M contracts don't even exist.

The second scenario is given by those cases where certain warranties are defined, but they do not represent the state of the art as they are expressed in a very lenient manner. In the case of *Plant 3*, the EPC warranty is limited to 12 months and the PR test is conducted with deviations from the industrial standards. In *Plant 6* the EPC is forced to reach 14,892 GWh of net production per year during the first 3 years of operation, which is easily achievable considering the irradiation sources in the region and the registered production during the first 2 years. The third example is shown in *Plant 5* where the lack of O&M contract and O&M warranties is compensated with an internal requirement, which sets the inverter availability at a minimum of 97%. This value is very lax as inverter availabilities close to 99.5% and beyond are nowadays common in stabilized large scale PV plants with central inverters.

Non-existing EPC warranties provide a high comfort to the Contractor as neither the suitability of the selected components nor the design and installation are supervised. Only the product warranties apply. It should be kept in mind that the EPC is interested in building as fast and cheap as possible in order to maximize his margin and also to leave the project as soon as possible by reducing the warranty periods to the maximum. Short warranty periods⁶² are safer for the EPC and riskier for the Owner since the likelihood of detecting system failures while the warranty is active decreases the shorter the warranty periods are. The lack of O&M warranties leads to a comfortable scenario where the O&M team has no special incentive to force the PV plant to run at its maximum potential. The consequences are usually a lower availability and a lower output than the theoretical maximum.

In regards to the OE⁶³ and LTA⁶⁴, these two entities play an important role in the quality assurance of any project. The OE has the task to support the Owner's interests against the EPC and eventually the various product suppliers. The OE conducts independent checks and verifications starting at the earlier phases of the EPC tendering and ending after commissioning or beyond. The absence of an experienced OE acting as independent party, may lead to an increased risk for the Owner as mistakes and inaccurate decisions might be overseen at any of the project stages [20]. Similarly to the OE, the LTA supports the interests of the bank as the financing institution. The latter is interested in financing projects which are bankable and are exposed to low risks. Thus, the task of the LTA is to ensure the bankability of the project by supervising that all steps made by the stakeholders lead to a low risk scenario. Out of the 6 evaluated projects, only *Plant 3* used an OE. The services of the LTA were only used in *Plant 3, Plant 4 and Plant 5*.

⁵⁶ Solar Project Developer

⁵⁷ Engineering Procurement Construction

⁵⁸ Operation and Maintenance

⁵⁹ These tests fall under the Provisional Acceptance Commissioning (PAC) process which is described below

⁶⁰ Typically 24 months

⁶¹ Usually close to COD (Commercial Operation Date)

⁶² 24 months

⁶³ Owner's Engineer

⁶⁴ Lender's Technical Advisor

Table 9: Risk summary – Contracts and warranties

Risk Summary
<p><i>Missing or poorly expressed warranties in the EPC and O&M contracts are a risk for the Owner since the quality can't be properly assessed during construction, commissioning and operation. EPC and O&M companies push in the opposite direction trying to reduce or even eliminate any warranties that put contractual pressure on them. Not having an LTA and/or an OE on board may lead to oversee failures and mistakes at early, intermediate and advanced stages of the PV plant deployment threatening the profitability of the project. Projects financed, constructed and operated by the same companies are less bankable in refinancing or acquisition processes since self-imposed quality control measures usually don't exist.</i></p>



PV Plant Design

The design of the PV plant is a process that needs to be performed in regards to a minimization of the LCOE⁶⁵ which is not necessary equal to a minimization of the CAPEX⁶⁶. The reason is that the CAPEX is only one of the inputs of the financial model together with the OPEX⁶⁷, capital costs and energy production among others, and some design decisions orientated towards reducing the CAPEX lead automatically to an increase of the OPEX and eventually to a reduction of the energy output. The reduction of the CAPEX shouldn't be the driving factor when designing a PV plant, instead, the final decision shall be taken based on a minimization of the LCOE.

During the analysis of the various projects, PI Berlin detected a few examples of design decisions focused on a CAPEX reduction but with potential influences in the LCOE, and thus, in the profitability of the system. In *Plant 5*, the location of the PCUs containing the inverters, transformers and MV switchgear wasn't selected considering voltage drop minimization. The cable runs are long and exceed 3% of voltage drop between some combiner boxes and the corresponding inverter. Additionally, the resulting voltage difference between combiner boxes located close and other located far away from the inverter, may easily lead to a voltage mismatch on inverter level. The fact of concentrating the PCU in less locations leads to lower CAPEX in form of a reduction of civil costs and installation time. On the other hand, the long cable runs doom the plant to face increased DC cable losses and voltage imbalance on inverter level throughout the whole lifetime of the project leading to an increase of the LCOE as the system performance decreases.

A second example is also shown in *Plant 5* as well as in *Plant 3* and *Plant 6*. In this case, the selected overbuilt or DC/AC ratio is almost 1, even though the tender specifications of SECI⁶⁸ allow on page 78 section 10 (ii) a PV plant design with an overbuilt higher than 1 as long as the AC capacity is not exceeded⁶⁹. The optimal DC/AC ratio should be determined while considering investment costs, inverter warranties, PV module temperature losses, meteorological data and OPEX among others. Low overbuilt ratios lead to a low CAPEX in the short term but may also lead to waste inverter AC capacity even though the partial load behavior of the inverter is more efficient.

A third example is given by the selection criteria applied when it comes to choose a specific supplier out of a shortlisted group. It could be observed that the price is still the driving factor leaving the long term durability aspects aside. This phenomenon was detected by PI Berlin in all inspected plants but with varying levels of affection. The described situation combined with the low experience of some SPD could be solved with stricter tender requirements prescribed by the corresponding authorities. Considering the tender requirements specified by SECI in Annexure B, the selection criteria for the main components of the plant are relatively lax and general⁷⁰. It can be observed that no strict technological requirements for modules, inverters, cables and other components are defined considering Indian specific environmental conditions. The specified norms correspond to the basic IEC certification process and are not accompanied by additional tests beyond the norm created for increasing the long term durability of the products.

Other examples such as the inconsistent module row distances detected in *Plant 1* and *Plant 2* and leading to different shading losses, the absence of different MPPT⁷¹ trackers for different roof orientations detected

⁶⁵ Leveled Cost of Energy

⁶⁶ Capital Expenditures

⁶⁷ Operating Expense

⁶⁸ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013

⁶⁹ "Higher DC capacity arrays so as to achieve AC capacity limit as mentioned above for scheduling at the delivery point in compliance to Article 4.4 "Right to Contracted Capacity & Energy" of the PPA is allowed.

⁷⁰ "The Bidder shall provide sufficient proof and credentials that the technology proposed by him has been in successful operation in at least one Project anywhere in the world at the time of Financial Closure." (page 21 section 3.7 C. i)

⁷¹ Maximum Power Point Tracker

also in *Plant 2* or the weak module fixation detected in *Plant 3* and *Plant 4* that does not withstand strong winds, are further examples of design mistakes that were not detected at earlier stages.

Table 10: Risk summary – PV plant design

Risk Summary
<p><i>Focusing the design of a PV plant towards a low initial investment provides a benefit in the short term but does not necessary lead to a more profitable project crystallized in a lower LCOE at the end of the lifetime. In cases where the EPC conducts the design, the efforts to reduce the CAPEX are more visible, leading to an increase of the risk on the Owner’s side in terms of the system profitability in the long term. Soft tender requirements that do not impose strict quality criteria for the component selection and system design contribute to perpetuate the risks.</i></p>



Electromechanical Installation

In regards to the installation quality of the analyzed plants there is still room for improvement basing on the onsite surveys conducted by PI Berlin. In general it could be seen that the supervision activities during the construction phase were not thorough in some of the visited plants and that improvised solutions were applied in others, not following standardized installation patterns leading to homogeneous results that simplify the maintenance activities [16].

4 out of the 6 plants have a module fixation system unsuitable for PV applications and do not ensure the proper fixation of the modules to the mounting structure. In case of strong winds, the modules might suffer severe damages, which was actually reported in *Plant 3* and *Plant 4*. Apart from this, some plants show micro-shading effects caused by the clamps, which have an influence on the module performance. Additionally, the missing row labelling makes the correct identification of the various areas of the plant more difficult leading to increased reaction times during corrective maintenance. Another relevant aspect has to do with the rust on the mounting structure surface identified in *Plant 1*, *Plant 3* and *Plant 6*. The rust can lead to a reduction of the structural strength of the mounting structure, especially in combination with strong wind.

The DC combiner boxes installed in the PV plants of *Plant 3* and *Plant 4*, both located in the Rajasthan desert, show a significant amount of dust inside the housing. The dust accumulation reduces the heat evacuation and tends to grip the electrical protections such as fuse holders and breakers limiting their functionality. Not sealed cable glands allow dust and dirt entering the combiner box housing. This is especially critical in desert areas with a high amount of dust in the air combined with winds carrying sand and dirt particles. Additionally, and in more humid areas such as *Plant 6*, this can lead to the development of micro-organisms and possible corrosion and chemical reactions that damage the electrical components inside the housing. In nearly all investigated plants, it could be observed that the tags and datasheets attached to the housing were losing adherence. The missing combiner box labelling makes the correct identification of the various areas of the plant more difficult leading to increased reaction times during corrective maintenance.

The DC cabling is probably the subsystem that shows most installation failures. Damages in the cables are responsible for the loss of insulation of the electrical circuits, which becomes especially relevant during the rainy season due to the especially high humidity rates. The damages can be easily provoked by monkey bites or due to the contact with sharp edges or stones as seen for instance in *Plant 1*, *Plant 3* and *Plant 5* respectively. More failures were identified in 2 plants in regards to connectors that were not properly closed leading to an increase of the local resistance between the male and female and higher likelihood of fire risk. In 5 out of 6 plants the cable ties used for fixing the cables were falling apart leaving the cables loose and exposed to mechanical damage caused by the wind and the friction against other components such as the mounting structure or the module frames. It could be observed that in all PV plants except in *Plant 1* the protection of the cables against high UV loads was not completely avoided which leads to a potential affection of the long term durability of the cable shield. Finally, in half of the analyzed plants it could be observed that the cables were either labelled with non-durable tags or not labelled at all. The consequence of this is a more difficult identification of the different electrical circuits leading to increased reaction times during corrective maintenance and confusion caused by the missing tags and labels which represents a safety issue for the O&M staff during preventive and corrective maintenance.

The most relevant issues detected on inverter level are related to (i) the dust accumulation and (ii) the cooling inside the inverter room. Both aspects affect mainly the projects in *Plant 3* and *Plant 4* due to their location in an arid area. In regards to the first issue, the significant amount of dust inside the inverter room may affect on the one hand the electrical protection devices by causing grip and limiting their functionality, and on the other hand the presence of dust tends also to block the ventilation filters reducing the heat evacuation capacity. A poor ventilation system is critical for the long term durability of the inverter. The absence of a

thermostat that avoids the room temperature to exceed certain limits is compensated with a ventilation fan that is connected manually. The temperature control should be fully automatized since the manual action does not ensure a proper control and judgement of the cooling demand.

The equipotential bonding system has a pure safety function and is intended to avoid uneven potentials across the PV plant by connecting all conductive parts to a common ground. The continuity of the equipotential bonding system can be easily reduced for instance through a corrosion process or with mechanical damages. Signs of corrosion could be seen in *Plant 3* showing a conductor whose continuity was not given due to the severe damages caused by rust. The rust was created by the corrosion triggered by the salty environment in combination with heat and humidity. As rust develops, the voltage drop increases along the conductor limiting the correct functionality of the equipotential bonding system losing its capacity to protect against uneven potentials. This effect was also present in *Plant 1* and *Plant 4* but with lower levels of affection. The risk of mechanical damage is present in all plants where the equipotential bonding conductors are not buried as per normative standards⁷². A second reason for keeping the conductors underground is to avoid possible interactions between personnel and fault currents flowing through the conductor.

The as-built documentation should be complete according to the IEC 62446. This is not fulfilled in half of the analyzed plants. This represents a risk for instance during takeover, as the new Owner acquires an asset whose installation, BOM and drawings are not properly documented. In regards to the installation reports, they missed in all inspected plants. These documents are very helpful for instance during O&M as they include valuable information of one of the most relevant phases of the project. Not having access to this information means losing part of the history of the plant.

Table 11: Risk summary – Electromechanical installation

Risk Summary
<p><i>The lack of trained and experienced installers as well as poor supervision procedures combined with the use of components unsuitable for the applicable environmental conditions, are three factors that increase significantly the number of installation failures leading to performance and safety risks. The most affected subsystems are those on the DC low voltage side, especially the cabling system. In general, there is a lack of awareness among some installers in regards to the consequences derived from the installation failures, both in terms of safety and performance. The installation failures occurred during the construction phase and described above, represent a pre-damage of the plants which are in many cases barely removable during the operational phase. It is crucial to prevent the failures in order to reduce retrofitting costs and revenue losses for the Owner. The lack of documentation of both the as-built situation and the installation process, make handover processes significantly more difficult.</i></p>



Commissioning

PI Berlin considers the commissioning process conducted at the end of the installation phase a crucial milestone in the deployment of a PV project [16]. According to the best industrial practices, the commissioning process is divided in a “cold”⁷³ and a “hot”⁷⁴ commissioning, and ends with the issuance of the Provisional Acceptance Certificate. This is the last step before the EPC warranty starts and is a process that gives an idea of the status of the plant in terms of safety and functionality. Additionally a performance test (PR test) shall also be conducted during an agreed amount of days both at PAC⁷⁵ and FAC⁷⁶. The commissioning procedure as well as the description of the tests and the associated pass/fail criteria, are usually described in the EPC contract and the successful passing of these tests represents a contractual warranty between the Owner and the EPC.

The reality of the investigated plants differs significantly from the scenario described above. None of the investigated plants was commissioned according to the requirements of the IEC 62446 and the industrial best practices. In *Plant 1*, *Plant 2* and *Plant 6*, there were no requirements in the EPC contracts specifying the tests described above⁷⁷ and obviously, the EPC companies did not conduct them voluntarily. In *Plant 3*, only a PR test was conducted, but the same was not aligned with the state of the art as already described in chapter 5.5.4. The same test was required in *Plant 4* and *Plant 5* but wasn't conducted at all due to several

⁷² They should be buried at a depth according to the applicable norms, typically around 60cm (IEC 62548)

⁷³ “cold” stands for those tests conducted prior to grid connection

⁷⁴ “hot” stands for those tests conducted after grid connection once current is flowing

⁷⁵ Provisional Acceptance Commissioning

⁷⁶ Final Acceptance Commissioning

⁷⁷ In the cases of *Plant 1* and *Plant 2* there was no EPC contract signed at all.

reasons. In regards to the commissioning tests specified in the IEC 62446 which refer mainly to safety aspects such as insulation, polarity or continuity among others, only part of the prescribed tests were conducted in *Plant 2* and *Plant 5*, in the other plants none of the tests of the IEC 62446 were carried out. In those plants where either a PR tests or any of the tests specified in the IEC 62446 were conducted, no validation or witnessing from a third party was reported except in *Plant 3*. The present scenario of the analyzed projects shows PV plants that weren't commissioned according to the best practices, neither in terms of performance validation nor in terms of safety.

In regards to the commissioning requirements specified under point 11 of the Annexure B page 79 of the tender released by SECI in October 2013⁷⁸, all plants that were built under this program⁷⁹ do officially comply with the tender specifications. Therefore, following documents had to be submitted: installation report provided by the SPD (Annexure I); snapshots of the plant, plant layout, SLD and meter readings provided by the SPD (Annexure II); electrical inspector report collected by the SPD and submitted to the State Nodal Agency (Annexure III); connectivity report issued by the Discom (Annexure IV); synchronization certificate issued by the Discom (Annexure V); and compliance with tender verified by SECI (Annexure VI). In regards to the tender compliance specified under Annexure VI, PI Berlin could observe during the visits, that certain plants do not comply with some of the requirements listed in the tender. One example is shown in *Plant 6*, where an irradiation sensor on the module plane is not installed even though it's required in the tender under point 8b on page 78⁸⁰. Another example is given by the flash-lists that are requested by SECI in the section 8.a. of the Annexure B on page 78, as part of the documentation to be submitted by the SPD and that was not available in 2 of the 6 evaluated plants⁸¹.

The fact that the commissioning certificate was issued even though part of the tender requirements were not fulfilled but specifically requested⁸², raises questions in regards to how thorough the validation of the tender compliance actually was. In opinion of PI Berlin, the commissioning requirements specified in the tender under Annexure B need to be reinforced, mainly in regards to (i) DC and AC low voltage safety checks such as insulation tests, continuity tests, polarity tests, AC breaker and RCD functionality tests, (ii) verification of the nominal power, (iii) short circuit and open voltage tests on the PV modules, (iv) system availability tests, (v) PR test and (vi) inverter and SCADA reliability tests, among others.

Table 12: Risk summary – Commissioning

Risk Summary
<p><i>The inspected PV plants weren't commissioned according to the industrial best practices of the PV industry mainly due to the lack of a legal framework that required so. The few tests conducted by some SPD weren't validated by independent parties. The commissioning requirements specified under Annexure B in the tender released by SECI in October 2013 need to be reinforced in regards to safety and performance aspects both on system and component level. Certain PV plants show noncompliance with some tender requirements even though the commissioning certificate was issued. At the moment the commissioning processes applied on grid connected PV plants in India do not include strict tests and verifications especially designed for ensuring the safety and high performance of the plants during the operational phase.</i></p>



System Performance

The system performance of a PV plant expressed as the Performance Ratio (PR), is a critical value for assessing the efficiency of a PV system. Usually, this parameter has a significant contractual relevance in regards to the EPC warranties previously described. Besides the commercial meaning, the PR is a key indicator for asset managers that helps tracking the plant's efficiency and detecting performance drops at early stages. Two aspects are crucial in order to obtain valid and useful PR values: (i) the type of meteorological sensors used along with the installation quality and maintenance of the same, and (ii) the calculation methodology applied for obtaining the PR value. The main variables needed for calculating the PR are the irradiation registered on the module plane during a certain period, and the metered energy production during the same period. In order to compare the real onsite PR value with a contractual value, a temperature correction is usually conducted using the module temperature values registered during the same

⁷⁸ Request for Selection (RfS) Document for 750MW Grid Connected Solar Photovoltaic Projects Under JNNSM Phase II Batch-I; RfS No. SECI/JNNSM/SPV/P-2/B-1/RfS/102013

⁷⁹ *Plant 3, Plant 4, Plant 5 and Plant 6*

⁸⁰ "The SPDs shall install equipment to monitor solar radiation on the module plane."

⁸¹ "The SPD shall maintain the list of Module IDs along with performance characteristic data for each module."

⁸² "The Bidders shall strictly comply with the technical parameters detailed in the Annexure-B to make the Project technically eligible." - page 21 section 3.7 C. iii

period.⁸³

The onsite evaluation conducted on the 6 selected sites shows that in none of them a full weather station was installed. The cell temperature for instance, which is key for correcting the PR value as already mentioned, isn't measured in half of the analysed plants, while the GHI records are also missing in 50% of the projects. In *Plant 6*, the irradiation sensor on the tilted plane is also missing which is a tender requirement specified by SECI. The correction of the PR with the temperature isn't conducted in any of the plants, first because in some of them the cell temperature wasn't recorded, and second because in others the internal PR calculation methodologies didn't require so. In *Plant 2* and *Plant 6*, the PR value is not even calculated. In regards to the installation quality of the various sensors constituting the weather station, failures were detected in most of the plants. In *Plant 1* and *Plant 6*, the communication cables were not properly routed and in the case of *Plant 6* they were even damaged, so that the reliability of the data sent to the SCADA system was not ensured. In *Plant 3* and *Plant 5*, the excessively long arm that supports the pyranometer oscillates with the wind. Thus, the accuracy of the registered data can be affected. In some cases the location of the weather sensors was not representative for the whole PV plant. This leads usually to recorded values that do not reflect the real behavior of the modules. Inaccurate values lead to a wrong assessment of the system performance of the plant. This aspect affects especially the plants in *Plant 2* and *Plant 6*. *Plant 5* is also affected occasionally by an imprecise system performance assessment, but in this case due to communication problems. The internet access onsite was not good which lead to inconsistent loggings of the meteorological data registered by the sensors. As a result, the PR calculations are not consistent either, which leads to unrealistic values with very high daily PR fluctuations. Finally, PI Berlin could observe that the energy simulations conducted by the Owners during the development phase in *Plant 2* and *Plant 6*, weren't performed according to the industrial standards. The yield assessment conducted during the development phase should use input data that are site and project specific. Otherwise, the assessment won't reflect the system performance properly and won't be bankable.

On a separate note, when it comes to address the impact of defect system components and installation failures on the overall system performance, several failure categories with different levels of impact must be distinguished. The failures and defects of the PV modules and BOS components detected by PI Berlin during the site visits can be categorized in three main groups.

- I. **Sporadic failures with impact on the performance:** examples of this failure category are for example cell hot spots⁸⁴. The total amount of affected modules and the correspondent impact on the system performance can only be determined after an infrared inspection of 100% of the modules and a subsequent electroluminescence and nominal power evaluation of the affected samples.
- II. **Systemic failures with impact on the performance:** This failure category refers to failures inherent to a specific system component or caused by a repeated behavioural pattern that affects the entirety of the PV plant. These failures can be (i) product specific, for instance PID⁸⁵, (ii) repeated installation failures such as bad module handling causing PV module damage, or (iii) inaccurate O&M measures, for instance wrong or improper module cleaning concept. The failures corresponding to any of these three sub-categories affect in principle 100% of the PV plant, as the root cause analysis shows that they are linked to the intrinsic nature of a given system component or to an installation or maintenance behaviour adopted in all subfields of the PV plant.
- III. **Sporadic and/or systemic safety-related failures without primary impact on the system performance:** issues such as monkey bites in DC cables (sporadic), untight DC combiner boxes (systemic) or grounding rods not suitable for salty environments (systemic) among others, belong to this group. These failures lead essentially to safety issues but do not compromise necessarily the system performance in the short term.

In order to assess the influence of the performance-related failures on the overall energy output of the plant, a visual inspection of 100% of the system would be necessary combined with an in-depth analysis of the yield, system availability and other monitored data since COD. A proper evaluation is especially challenging in those plants where a monitoring system doesn't even exist.

⁸³ The temperature losses represent a big portion of the total system losses. A correction of the temperature losses helps to normalize the influence of this factor especially when the average module temperature during the onsite measuring period differs significantly from the temperature used for calculating the contractual value.

⁸⁴ See chapter 4.3

⁸⁵ See chapter 4.1

Table 13: Risk summary – System performance

Risk Summary
<p><i>Incomplete weather stations that do not record and log properly all relevant meteorological data, combined with installation failures and a disregard of the importance of calculating and correcting the Performance Ratio of the plant, are three factors that handicap a proper assessment of the performance of the system. Others aspects such as the selection of not representative locations for placing the sensors, or yield simulations not aligned with the industrial best practices, are additional factors that contribute to reducing the bankability of the project.</i></p> <p><i>The impact of the detected failures on the system performance is different dependent on the failure category and needs additional investigations to be properly assessed.</i></p>



PV Module Quality

The PV modules represent the most sensitive part of the PV plant, especially in harsh climates with high UV loads, high temperatures, high humidity rates, salinity and abrasion, all of them present at the locations visited by PI Berlin. In order to assess the quality of the modules, PI Berlin conducted a visual inspection, an infrared analysis and an electroluminescence inspection using the equipment specified in Annex IV.

After conducting the surveys on the 6 sites, it could be observed that no specific certificates beyond the basic IEC certification were requested by the Owners to the module manufacturers in regards to the long-term durability of the modules in the correspondent climates where the modules were installed [15]. The high temperatures, UV loads and humidity rates registered in places like *Plant 3*, *Plant 4* and *Plant 6*, represent a threat for the PV modules in terms of long-term stability. In this sense, the quality requirements for the module selection specified by SECI in point 1 of the Annexure B of the tender documentation⁸⁶, are limited to the basic IEC certificates⁸⁷ and only specify the salt-mist corrosion test (IEC 61701) as a test especially created for particularly harsh environments such as those present in *Plant 3*⁸⁸. Other tests and quality criteria that would help reinforcing the tender specifications and that refer to failures and defects detected by PI Berlin during the site visits, are the sand and dust test⁸⁹, the PID test⁹⁰, UV stability tests on the front and back side of the modules, advanced hot spot tests, factory audits and production supervision of the PV modules.

Certain failures detected in the inspected PV plants, are preventable when conducting some of the tests and inspections mentioned above for instance by LTAs or OEs [20]⁹¹. One example is the Potential Induced Degradation (PID) effect, which was detected in *Plant 2* and *Plant 6*. The PID effect can be responsible in the short term for a significant reduction of the PV power output of the modules located on the negative side of the string, and should be stopped immediately. The development of PID is accelerated with high temperatures and humidity rates. The PID test according to the IEC 62804 was created to analyze the PID sensitivity prior to installation. A second example is given by the manufacturing problems detected on the PV modules installed in *Plant 3* and *Plant 6*. Failures such as inaccurate soldering of the ribbons or misalignment of the module junction boxes point towards lack of quality inspection programs at certain stages of the module manufacturing process. In the specific case of the inaccurate soldering, the further development of the hot spots visible along the busbars, can lead to a permanent damage of the module or even to fire events. Accurate factory audits and production supervision services provided for instance by LTAs or OEs can help preventing these problems.

A second problem detected onsite has to do with the improper handling of the modules. The snail trails detected in 4 out of the 6 plants are an evidence of the presence of cell cracks which could be confirmed by PI Berlin using infrared and electroluminescence technology. These cracks show the typical pattern of damages caused by bad module handling during the construction phase. Cracks may lead to performance losses as they develop further, and to hot spots when parts of the cells are isolated by the cracks [17]. The strong winds registered in some of the sites may contribute to a faster development of the cracks due to the dynamic loads associated to them. Further signs of bad module handling are the presence of footprints, scratched backsheets and damages of the corners of the glass-glass modules. Cracks and signs of bad module handling were observed in *Plant 3*, *Plant 4*, *Plant 5* and *Plant 6*.

⁸⁶ Tender page 76: IEC 61215 (c-Si), IEC 61646 (TF), IEC 61730 (safety), IEC 61701 (for highly corrosive areas)

⁸⁷ IEC 61730, IEC 61215, IEC 62108 and IEC 61646

⁸⁸ Since the environment in and around *Plant 3* has a significant amount of salt present in the ground, the salt-mist corrosion test as per the IEC 61701 is a relevant test to be conducted on the modules which are installed in this region.

⁸⁹ IEC 60068

⁹⁰ IEC 62804

⁹¹ "Quality in India: battling the stereotypes"; pv tech; September 2017; "Ultimately, developers in India will need to engage in third-party testing beyond just the IEC standard...Such independent verification would help stamp out the chances of significant potential-induced degradation."

Table 14: Risk summary – PV module quality

Risk Summary
<p><i>The lack of strict quality requirements in regards to the module selection and installation contributes to increasing the risks primarily for plant owners and investors. Lax tender requirements give comfort to module suppliers and installation companies as no legal framework is forcing them to provide evidences of long-term durability products and failure free installation works. The PV modules are the most sensitive component of the PV system and its stability during the full operational live cycle is strongly affected by the environmental factors and damages caused due to improper module handling during the installation process.</i></p>



Operation and Maintenance

The O&M service is typically divided in preventive and corrective activities whose main task is to ensure the highest system performance during the highest amount of operating hours. Part of the preventive maintenance activities is the module cleaning. In regards to this, two points are key: first, the impact of the selected cleaning methodology on the PV module warranty should be analyzed before implementing it in the field. Several factors such as the material used for the wipers, the type of water, the cleaning methodology, the water pressure and the physical and chemical properties of the soil, might have an influence on the glass and the anti-reflective coating properties of the modules. Product damages or performance losses of any kind originated by the cleaning process are not covered by the product warranty unless the cleaning concept has been approved previously by the module manufacturer. Second, the accumulated soiling losses during a certain interval shall be measured before setting the amount of cleaning rounds per year. Otherwise, the cleaning frequency may not be adjusted to a defined soiling loss, which is set as the maximum acceptable value. Actually, when defining the amount of cleaning rounds without conducting a previous study on the needs of the plant, there might be some periods when the PV plant is “undercleaned” and others in which the PV plant is “overcleaned”. In the first case performance is lost, while in the second case unnecessary costs are generated. None of the two mentioned steps was given in the 6 inspected plants.

In half of the analyzed plants the preventive maintenance activities focused mainly on the switchyard, inverters, combiner boxes, LV DC module, HV and MV transformers and weather station. No preventive actions were conducted on PV modules and DC cables, which are an essential part of the system and require specific checklists which can't be recycled from other technologies. In *Plant 2* a preventive maintenance program doesn't even exist.

In regards to the corrective maintenance, in *Plant 2 and Plant 6* no root cause analysis, mitigation actions and follow up was conducted on the events registered onsite. Part of the corrective maintenance is to investigate the origin of the failures, find a solution and monitor the evolution in the short term. In *Plant 5*, the event registration, the root cause analysis and the advisory on the mitigation measures is conducted remotely. The O&M members present onsite should be more involved in the operational data and daily activities of the plant in order to increase their knowledge and improve their capability to detect, solve and predict failures as well as to assess the operational quality of the system.

Both for preventive and maintenance activities a proper set of devices and tools used in the PV industry such as IV curve tracers, electroluminescence devices and infrared cameras help detecting and evaluating failures easily. The regular use of these devices is necessary during O&M for detecting and monitoring defects and degradation phenomena such as hot spots, cracks or PID. PV specific tools such as those described in the Annex IV of this report, weren't used in any of the plants inspected by PI Berlin.

The reporting of the preventive and corrective maintenance activities should contain monthly and yearly reports specifying production data, availability values, spare parts managements, costs, outage time, preventive and corrective actions, trend analysis, meteorological data and accumulated production among other values. A poor reporting activity does not support a proper monitoring of the plant operation which is crucial for a successful asset management orientated to maximize the performance and operating hours. In *Plant 2 and Plant 3*, the reporting is especially poor or even nonexistent.

The system availability is one of the key performance indicators during the O&M period and should be constantly measured and monitored. In *Plant 1, Plant 2 and Plant 6*, the system availability is not measured, neither on inverter nor on string level. As a consequence, it remains unknown if the amount of operational hours of the various subsystems such as inverters or module strings, can be increased leading to a maximization of the yield output. In the case of *Plant 3*, the minimum availability value has been set internally at 98% at inverter level, which is lower than the industrial standard close to 99.5% in stabilized PV plants using central inverters.

The above mentioned deviations from the industrial best practices have the origin in the lack of experience of some of the O&M teams involved in the analyzed plants. This may lead to a wrong diagnose of the detected failures, as well as to an inaccurate corrective maintenance, among other consequences. In order to maximize the performance and availability of the PV plant, the O&M team should be familiar with as many events as possible in all potential scenarios.

Table 15: Risk summary – Operation and Maintenance

Risk Summary
<p><i>The preventive maintenance plan is not completely adapted to the PV technology and is still strongly focused on the electrical components that are common to other technologies. The module cleaning should be planned considering the impact on the module warranty in order to avoid legal hassle, and should also be based on a previous study that avoids undercleaning or overcleaning the plant during certain periods in order to avoid unnecessary costs and performance losses. A corrective maintenance without root cause analysis and follow up doesn't ensure an entire problem solution. A poor reporting as well as the absence of a system availability calculation, are two aspects that contribute to an inaccurate operation of a PV plant since the key performance indicators, the maintenance costs, the failure diagnosis or the event registration among others, aren't properly documented. The lack of experience of some O&M teams is responsible for the deviations detected on site.</i></p>



7 Lessons Learned and Take-away Messages for the Future PV Deployment in India

The previous chapter has described the risks present in the 6 inspected projects based on the failures and deviations from the state of the art identified during the evaluation process. The risk analysis focused mainly on contracting, installation quality, long term durability of the components, design assumptions, operation and maintenance, PV plant commissioning and accuracy of the system performance calculation during the operational phase. This chapter will use the identified risks and transform them into clear statements and recommendations that would help prevent the fast growing PV sector in India from quality concerns and loss of bankability.

- 1 The tender requirements shall include strict quality criteria applicable to the whole value chain. Special focus shall be put on the long term durability of PV modules and DC cables, electromechanical installation and commissioning.
- 2 Trainings and workshops will contribute to increase the awareness of SPD and financing institutions (FI) in regards to quality lacks and associated investment risks.
- 3 The performance warranties along with the applicable pass fail criteria should be clearly expressed in the EPC and O&M contracts in order to reduce the risks of the solar power developers (SPD).
- 4 In projects financed, constructed and operated by the same company, EPC and O&M contracts may not exist. Thus, external third party inspection should be mandatory since self-imposed quality control measures are usually not applied by the SPDs.
- 5 LTAs and OEs play an important role during the development process helping banks and SPD to detect failures at early stages.
- 6 The design of a PV plant shall be orientated towards a minimization of the LCOE. Decisions orientated towards a low initial investment provide a benefit in the short term but do not necessary lead to higher profitability.
- 7 Less experienced construction companies should be properly trained and supervisory activities during the installation phase should be defined in advance.
- 8 The awareness of the construction companies in regards to the consequences derived from the installation failures should be increased in order to prevent costs, safety issues and performance drops.
- 9 The EPC shall be liable for the installation failures. The technical requirements for allowing a proper identification of the same shall be annexed to the EPC contracts.
- 10 The as-built documentation shall be comprehensive and up to date in order to ensure a smooth take over.
- 11 The tender requirements shall ensure that all PV plants are commissioned according to the industrial best practices of the PV industry in regards to performance and safety aspects, both on system and component level.

- 12 The commissioning tests shall be validated by independent parties.
- 13 The commissioning tests along with the pass/fail criteria and the reporting specifications shall be annexed to the EPC contracts.
- 14 Clear installation guidelines and a comprehensive BOM of the weather station shall be part of the tender requirements in order to ensure a proper logging of all relevant environmental variables responsible for an accurate Performance Ratio assessment.
- 15 The location of the weather station shall be representative for the system that will be monitored.
- 16 The yield simulations issued prior to financial close shall be aligned with the industrial best practices in order to ensure the bankability of the project.
- 17 The module suppliers shall prove evidence of quality not only in regards to the basic IEC certification but also considering Indian specific environmental stress factors.
- 18 Factory audits and production supervision of PV modules shall be part of the tender requirements avoiding low quality modules reaching the PV facilities.
- 19 The prevention of module damages due to improper handling is key in order to avoid accelerated aging and degradation effects.
- 20 The preventive maintenance activities shall shift the focus from the electrical components that are common to other technologies and become more PV specific.
- 21 Before starting the operational phase, the impact of the cleaning methodology on the module warranty shall be assessed.
- 22 The amount of cleaning rounds shall be fixed based on a previous soiling study that avoids undercleaning or overcleaning the plant during certain periods.
- 23 The corrective maintenance shall include a root cause analysis, mitigation plan and follow up that prevents repetitive failure events.
- 24 A strong O&M reporting including the monitoring of the system availability contributes to an accurate tracking of a PV plant behavior.
- 25 The awareness of the O&M companies in regards to the consequences derived from an inaccurate maintenance should be increased in order to prevent safety issues and performance drops.

8 Literature and References

- [1] *Photon International*; June 2017
- [2] *pv magazine*; April 2017
- [3] "How soiling and cleaning impact module performance in deserts"; Ferretti N., Berghold J.; December 2015.
- [4] "Influence of cleaning using water and surfactants on the performance of photovoltaic panels"; Moharram Ka, Abd-Elhady MS, Kandil Ha, El-Sherif H.; *Energy Convers Manag* 2013;68:266–72.
- [5] "Influence of micro cracks in multi-crystalline silicon solar cells on the reliability of pv modules"; Grunow P. et al.; 20th European Photovoltaic Solar Energy Conference, 6–10 June 2005, Barcelona, Spain.
- [6] "Dynamic mechanical load tests on crystalline silicon modules"; Koch S. et al; 25th European Photovoltaic Solar Energy Conference and Exhibition/5th World Conference on Photovoltaic Energy Conversion, 6-10 September 2010, Valencia, Spain.
- [7] "Investigation on performance decay on photovoltaic modules: snail trails and cell microcracks"; Dolara A. et al; *IEEE Journal of photovoltaics*, vol. 4, no. 5, September 2014.
- [8] "Impact of micro-cracks on the degradation of solar cell performance based on two-diode model parameters"; Van Mülken J. I. et al; *SiliconPV: April 03-05, 2012*, Leuven, Belgium.
- [9] "The Atacama desert, extreme conditions for instrumentation"; Kipp & Zonen news; Thursday, March 17, 2016.
- [10] "Cable care"; *PV Magazine*; issue 05-2013, 3rd May 2013.
- [11] "A Comprehensive Review of the Impact of Dust on the Use of Solar Energy: History, Investigations, Results, Literature, and Mitigation Approaches". *Renewable & Sustainable Energy Reviews* 22 (2013): 698-733. Sarver, Travis, Ali Al-Qaraghuli, and Lawrence L. Kazmerski; June-July 2014.
- [12] *Performance and Reliability of Photovoltaic Systems - Subtask 3.2: Review of Failures of Photovoltaic Modules - IEA PVPS Task 13 External final report IEA-PVPS (March 2014)*
- [13] Munoz et.al; *An Investigation into Hot-Spots in Two Large Grid-Connected PV Plants -*
- [14] "Manual of good and bad practices to improve the quality and reduce the cost of PV systems"; *PV Crops*; 2013.
- [15] "Photovoltaic module qualification plus testing"; Kurtz S., NREL; December 2013.
- [16] "Utility Scale Solar Power Plants - A guide for developers and investors"; IFC; 2012.
- [17] "Review of failures of photovoltaic modules"; IEA - International Energy Agency; Report IEA-PVPS T13-01:2014.
- [18] "Investigations on crack development and crack growth in embedded solar cells"; M. Sander, S. Dietrich, M. Pander, and M. Ebert, S. Schweizer, J. Bagdahn; *Proc. Reliability of Photovoltaic Cells, Modules, Components, and Systems IV*, 81120I (SPIE, San Diego, California, USA, 2011), doi:10.1117/12.893662).
- [19] "State of the art in PV yield assessments"; *Power PV TECH – PV Power Plant Technology and Business*, page 52; André Schuman (SolPEG); May 2016.
- [20] "Quality in India: battling the stereotypes"; *pv tech*; September 2017
- [21] "World Map of the Köppen-Geiger climate classification updated"; Biometeorology Group, University of Veterinary Medicine Vienna, Vienna, Austria; Global Precipitation Climatology Centre, Deutscher Wetterdienst, Offenbach, Germany; 2006
- [22] *Assessment of Photovoltaic Module Failures in the Field; Report IEA-PVPS T13-09:2017; International Energy Agency;*
- [23] *Shadowing Investigations on thin Film Modules; Stefan Wendlandt et.al; PI Photovoltaik-Institut Berlin AG*

9 Disclaimer

Copyright © 2017 – PI Berlin AG. The content of this document is subject to the copyright and ancillary protections. Any of exploitation unauthorized by the copyright and ancillary protections needs our prior written approval. Especially any circulation to third parties, as well as any duplication, edition or manipulation in electronic media is prohibited. We suggest that the unauthorized duplication or circulation of any single content to third parties can be penal according to the copyright law. There is no license of usage associated with the transmission of the information. The contents presented are prepared with maximum diligence. If not declared otherwise, PI Berlin AG assumes no responsibility for the validity, completeness and actuality of the provided contents.

ANNEX I – Chronology of the Inspection Period

Sunday 2nd July:	Arrival in Delhi
Monday 3rd July:	Meeting with NISE (Rajesh Kumar Deputy Director General) and SECI (Bharat Reddy Deputy General Manager). Visit to the Plant 1.
Tuesday 4th July:	Visit to Plant 2.
Wednesday 5th July:	Travel time.
Thursday 6th July:	Visit to Plant 3.
Friday 7th July:	Visit to Plant 4.
Saturday 8th July:	Trip to Delhi.
Sunday 9th July:	Data post-processing.
Monday 10th July:	Travel time.
Tuesday 11th July:	Visit to Plant 5
Wednesday 12th July:	Meetings in Delhi.
Thursday 13th July:	Travel time.
Friday 14th July:	Visit to Plant 6.
Saturday 15th July:	Arrival in Berlin

ANNEX II – Shortlist Criteria

Table 16: Shortlist criteria applied for selecting the sites

Item	Relevance
Coordinates of the site	***
On-site measurements of global horizontal irradiation (GHI) in W/m ² since grid connection ideally on hourly basis. Alternatively on accumulated daily/monthly basis in kWh/m ²	***
On-site measurements of ambient temperature since grid connection ideally on hourly basis. Alternatively on average daily/monthly basis	***
Energy output values at feed-in point (kWh) on daily basis. Alternatively on accumulated daily/monthly basis.	***
Remote access to the SCADA (monitoring system)	**
Authorized access to the sites during day and night time	***
Authorization for taking pictures on site	***
Authorization for performing measurements including punctual disconnection of modules, strings and/or combiner boxes	***
Authorization for interviewing O&M personnel	***
Easy access to the sites (preferably no remote areas)	**
50m extension cables for performing the night measurements	***
As-built documentation	**
Yield assessment prior to financial close	**
EPC and O&M contracts	*
Monthly and yearly O&M reports since grid connection	***
Provisional acceptance commissioning protocols issued after grid connection	**
Grid connection date	***
Exact nominal power of the PV plant	***
Datasheet of PV modules	***
Datasheet of inverters	***
Calibration dates of the weather sensors	**
DWG plan of the module layout	***
Single line diagram	***
Photos taken during the construction phase	*

ANNEX III – Extract of the TDD Checklist

Table 17: TDD checklist (reduced version)

0	General	Interview needed?	Photo needed?	Comments	Photo Nr.	Note Nr.
0.1	Date of inspection					
0.2	Name and size of the plant					
0.3	Coordinates					
0.4	Commercial Operation Date (COD)					
0.5	Name of the Owner					
0.6	Name of the EPC					
0.7	Name of the O&M company					
1	Contracts	Interview needed?	Photo needed?	Comments	Photo Nr.	Note Nr.
1.1	Warranties of the EPC contract (PAC and FAC)					
1.2	Warranties of the O&M contract					
1.3	Completeness of the PAC in the EPC contract					
1.4	Name of the OE					
1.5	Name of the LTA					
2	PV Plant Design	Interview needed?	Photo needed?	Comments	Photo Nr.	Note Nr.
2.1	DC size					
2.2	AC size					
2.3	DC/AC ratio					
2.4	Level of injection					
2.5	Size of each PCU					
2.6	Module type					
2.7	Module technology					
2.8	Inverter type					
2.9	Pitch					
2.10	Tilt of the modules					
2.11	Mounting structure type					
2.12	Module arrangement					
2.13	Statics					
2.14	Location of the inverters and AC distribution boxes					

3	Electromechanical installation	Interview needed?	Photo needed?	Comments	Photo Nr.	Note Nr.
3.1	Mounting Structure					
3.1.1	Module fixation					
3.1.2	Labelling of rows					
3.1.3	Rust mounting structure					
3.2	Combiner box (CB)					
3.2.1	Sealing of the cable glands					
3.2.2	Cleanliness of the CB					
3.2.3	Overvoltage in the CB					
3.2.4	Labelling of the CB					
3.3	Cables					
3.3.1	Cable damage					
3.3.2	Labelling of cables					
3.3.3	Connectors					
3.3.4	Cable fixation					
3.3.5	Bending radius					
3.3.6	Protection of cables against UV					
3.3.7	Sealing of tubes					
3.3.8	Cable pipes					
3.4	Inverter					
3.4.1	Overvoltage in the inverter					
3.4.2	Cleanliness of the inverter room					
3.4.3	Cooling					
3.4.4	Status of filters					
3.4.5	Entrance of the communication cable					
3.5	Grounding					
3.5.1	Status of the grounding and equipotential bonding system					
3.5.2	Functional grounding					
3.6	Civil work					
3.6.1	Status of the roads					
3.6.2	Status of the drainage system					
3.7	Documentation					
3.7.1	Completeness of the as-built documentation					
3.7.2	Progress reports of the installation phase.					
4	Commissioning	Interview needed?	Photo needed?	Comments	Photo Nr.	Note Nr.
4.1	Tests conducted at PAC and FAC?					
4.2	Did anyone witness and validate?					
5	System performance	Interview needed?	Photo needed?	Comments	Photo Nr.	Note Nr.
5.1	Parallel logging of the irradiation sensors					
5.2	Parallel logging of the temperature sensors					
5.3	Date of calibration of the sensors					

5.4	Weather station status					
5.5	What has been the PR of the plant since grid connection?					
5.6	How is the PR calculated					
5.7	PR correction					
5.8	Yield assessment					
6	Module quality	Interview needed?	Photo needed?	Comments	Photo Nr.	Note Nr.
6.1	Visual inspection modules					
6.2	Availability of the flash lists					
6.3	Scratches in backsheet					
6.4	Long term durability certificates of the PV modules and inverters					
6.5	IR analysis					
6.6	EL analysis					
6.7	IV curve tracing					
6.8	Snail trails					
6.9	PID					
7	Operation & Maintenance	Interview needed?	Photo needed?	Comments	Photo Nr.	Note Nr.
7.1	Specific issues reported since COD					
7.2	Relevant environmental events					
7.3	Experience of workers in PV					
7.4	Experience of workers in O&M					
7.5	H&S program					
7.6	Allowance to operate MV devices					
7.7	Calculation of the soiling loss					
7.8	Cleaning methodology					
7.9	Vegetation					
7.10	Check the tools and devices used					
7.11	Reporting					
7.12	Reaction times					
7.13	Preventive maintenance					
7.14	Corrective maintenance					
7.15	Availability calculation					
7.16	Responsibility for SCADA					
7.17	SCADA resolution					
7.18	Theft on site					
7.19	Curtailment and grid stability					
7.20	Reactive power compensation and power quality requirements.					

*: This checklist is a reduced version of the extended Q3 checklist

ANNEX IV – Measurement Equipment Used On Site

PVPM1000X [S/N. **PVPM1000X08811**, calibration date **12.09.2016**, tolerance **5%**] is a peak power measuring device and IV curve tracer that provides the measurement of the I-V-curve of photovoltaic modules and strings on site. Measurements of PV array I-V characteristics under actual on-site conditions and their extrapolation to Standard Test Conditions (STC) can provide data on power rating, verification of installed array power performance relative to design specification, detection of possible differences between on-site module characteristics and laboratory or factory measurements, and detection of a possible performance degradation of module and arrays with respect to on-site initial data.



Figure 179: PVPM1000X I-V tracer [source: pv-engineering]

Irradiation sensor Si-13TC-x [S/N.**13-00000-05-16190072**, calibration date **17.05.2016**, tolerance **<3%**] is a reference cell for sun irradiation measurements that enables a precise analysis of PV module power or energy yields using measured values from the sensor. It has a double input for connection to single or multi crystalline modules.



Figure 180: Duo reference cell [source: PI Berlin]

Infrared camera Testo T890 [S/N. **2298789**, lens S/N **20488056**, tolerance **<2°**, calibration date **31.05.2017**] enables non-destructive diagnosis of some thermal and electrical failures in PV modules. It provides fast, real-time, two-dimensional infrared (IR) imaging, revealing characteristic features of PV systems. The measurements can be performed during normal operation for individual PV modules as well as large arrays.



Figure 181: Infrared camera [source: Testo]

By means of the **Nikon 800** camera [CCD High pass edge filter, ISO 400, 15 s, 2.8] **electroluminescence** pictures are taken in the field to reveal failures such as microcracks, PID, failure of diodes or similar, as a complement to the STC-measurement and infrared inspection. EL imaging is particularly suitable for the detection and tracking of crack related issues, which can occur for example during module transportation or installation.



Figure 182: Nikon 800D with CCD high pass edge filter [source: PI Berlin]

ANNEX V – Normative References Used for the Study

Table 18: Normative references used for the creation of the present study

IEC 61557-4:2007	Electrical safety in low voltage distribution systems up to 1 000 V a.c. and 1 500 V d.c. – Equipment for testing, measuring or monitoring of protective measures Part 4: Resistance of earth connection and equipotential bonding
IEC 60664-1:2007	Insulation coordination for equipment within low-voltage systems Part 1: Principles, requirements and tests
IEC 61215:2005	Crystalline silicon terrestrial photovoltaic (PV) modules - Design qualification and type approval
IEC 61730-1&2:2005	Photovoltaic (PV) module safety qualification
IEC 61829:2015	Photovoltaic (PV) array - On-site measurement of current-voltage characteristics
IEC 60364-4-41:2005	Low-voltage electrical installations - Part 4-41: Protection for safety - Protection against electric shock
IEC 60364-4-42:2010	Low-voltage electrical installations - Part 4-42: Protection for safety - Protection against thermal effects
IEC 60364-4-43:2008	Low-voltage electrical installations - Part 4-43: Protection for safety - Protection against overcurrent
IEC 60364-4-46:1981	Electrical installations of buildings. Part 4: Protection for safety. Chapter 46: Isolation and switching
IEC 60364-5-51:2005	Electrical installations of buildings - Part 5-51: Selection and erection of electrical equipment - Common rules
IEC 60364-5-52:2009	Low-voltage electrical installations - Part 5-52: Selection and erection of electrical equipment - Wiring systems
IEC 60364-5-54:2011	Low-voltage electrical installations - Part 5-54: Selection and erection of electrical equipment - Earthing arrangements and protective conductors
IEC 60364-6:2006	Low-voltage electrical installations - Part 6: Verification
IEC 60364-7-712:2011	Electrical installations of buildings - Part 7-712: Requirements for special installations or locations - Solar photovoltaic (PV) power supply systems
IEC 60529 1989+A1:1999+A2:2013	Degrees of protection provided by enclosures (IP Code)
IEC 60068-2-68:1997	Environmental testing - Part 2: Tests; test L: Dust and sand
IEC 60721 1-2:2013	Classification of environmental conditions
IEC 60721 3-4:1995	Classification of environmental conditions - Part 3: Classification of groups of environmental parameters and their severities - Section 4: Stationary use at non-weather protected locations (?)
IEC 61084-1:1991	Cable trunking and ducting systems for electrical installations
IEC 61238-1:2003	Foundation earth electrode - Planning, execution and documentation
IEC 62446:2009	Photovoltaic (PV) systems - Requirements for testing, documentation and maintenance
IEC 62548:2010	Photovoltaic (PV) arrays - Design requirements
UL 1703:2002	Standard for Flat-Plate Photovoltaic Modules and Panels
VDE-AR-E-2283-4:2010-10	Requirements for cables for PV systems
2 PtG 1169/08.2007*	Requirements for cables for use in photovoltaic-systems